



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

T01 TO RAGHUNATHPUR

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 300	
DISTRICT	KATIHAR	
BLOCK	AMDABAD	
DIVISION	MANIHARI	
TOTAL LENGTH OF ROAD	0.300	KM
TOTAL COST OF F.D.R. PART - A	Rs. 5.711 ^{2.259} 2-206	Lacs
ADD G.S.T @ 12%	Rs. 0.685 ^{0.271} 0-264	Lacs
ADD Labour Cess @ 1%	Rs. 0.057 0-023	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.377 0-145	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 6.830 ^{2.634}	Lacs

SUBMITTED BY

The Executive Engineer,
Works Division, Manihari

प्रतिवेदन

पथ का नाम :- T01 To Raghunathpur
 पथ की लम्बाई :- 0.300 KM
 प्राककलित राशि :- 2.684 L
 वित्तीय वर्ष :- 2021-22 / FDR-2021
 प्रखंड :- Amdabad

प्रस्तुत प्राककलन मो 2.684 L दो लाख 68 हजार 600 का कार्य विभाग, कार्य प्रमंडल मनिहारी अन्तर्गत अमदाबाद प्रखंड के T01 To Raghunathpur पथ हेतु तैयार की गई है। वर्तमान वर्ष 2021 के बाढ़ एवं अतिवृष्टि के कारण क्षतिग्रस्त पथ को MIS पर अपलोड किया जा चुका है, तथा विभागीय निर्देश ग्रामीण कार्य विभाग, बिहार के पत्रांक- मु0अ0-4 (मु0) विविध (कार्य)- 23/291/2019 -4275/ पटना, दिनांक 22. 10.2021 के आलोक में यातायात (Motorable) पुर्नस्थापन किया गया है।

उपर्युक्त प्राककलन में पथ के कटाव अंश पर बम्बू पाईलिंग, रनर के परचात Sand Bag से भरकर पथ को कटाव से बचाया गया है एवं कटे हुए स्थान पर ग्रीक बैट का प्राक्क्षन किया गया है तथा दो स्थानों पर GSB डाल कर पथ में आवागमन चालू किया गया है।

प्रस्तुत प्राककलन ग्रामीण कार्य विभाग, कार्य अंचल पूर्णियाँ द्वारा प्राप्त कोटेशन के न्यूनतम दर पर तैयार किया गया है प्राककलन की स्वीकृति जनहित में अति आवश्यक है।

कनीय अभियंता
 ग्रामीण कार्य विभाग
 कार्य प्रशाखा, अमदाबाद



सहायक अभियंता
 ग्रामीण कार्य विभाग
 कार्य अवर प्रमंडल, अमदाबाद



कार्यपालक अभियंता
 ग्रामीण कार्य विभाग
 कार्य प्रमंडल, मनिहारी

Inspection Report for flood damage work

Date :

1. Name of PU's Namphara
2. Name of Block Road Amalabad / Tol To Rajurathipura

A for Road

1. Damage location : 0.00 - 0.10
2. Damage Length : 0.056 Km
3. Nature of Damage : Seccuring & Cope Cut FCC Road
4. Details of Restoration :
 - i. Material being used in Restoration Bamboo Sand bags
 - ii. Equipment/Tools being used in Restoration Works Tractor
 - iii. Procedure taken up in Restoration works Manual
 - iv. Restored Length 0.056 Km

B. for Bridge

1. Damage Location/Chainage :
2. Damage Length :
3. Nature of Damage :
4. Details of Restoration :
 - i. Material being used in Restoration :
 - ii. Equipment/Tools being used in Restoration Works :
 - iii. Procedure taken up in Restoration works;
 - iv. Restored Length

Signature of *Subodh Kumar*
Subodh Kumar
Rural Works Division, Manihari

Subodh Kumar
Signature
(Name of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : T01 TO RAGHUNATHPUR

DISTRICT

KATHIHAR

DIVISION

MANIHARI

BLOCK

AMDABAD

LENGTH OF ROAD (IN KM)

0.300

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.000
3	BRICK BAT	2.688
4	SAND BAGS	4.540
5	G.S.B.	1.593
5	BAMBOO WORK	0.237
6	STEEL DRUM SHEET	0.429
		0.000
TOTAL COST OF PROJECT =		2.159
Add G.S.T. @ 12%		5.744
Add Labour Cess @ 1%		0.885
Add Seigniorage Fee @ 10%		0.057
Total Cost of Restoration Work =		8.845

26/11/21
J.E.
RWD

26/11/21
A.E.
RWD

26/11/21
S.E.
RWD

Technically Sanction for Rs. 2.694 Lac (Rs.)
Crare.
Thousand. Hundred.

Superintendent Engineer
Rural Works Department
Works Circle, Purnea