



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

T01 TO MANDAL TOLA BELGACHHI

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 950	
DISTRICT	KATIHAR	
BLOCK	AMDABAD	
DIVISION	MANIHARI	
TOTAL LENGTH OF ROAD	0.950	KM
TOTAL COST OF F.D.R. PART - A	Rs. 7.688 3.731	Lacs
ADD G.S.T @ 12%	Rs. 0.923 0.448	Lacs
ADD Labour Cess @ 1%	Rs. 0.077 0.037	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.319 0.163	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 9.007 4.379	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari


प्रतिवेदन


पथ का नाम :- T01 To Mandal Tola Belgachi
पथ की लम्बाई :- 0.950 KM
प्राक्कलित राशि :- 4.379 ~~9.007~~ Lac
वित्तीय वर्ष :- 2021-22 / FDR-2021
प्रखंड :- Amdabad


प्रस्तुत प्राक्कलन मो 0 ~~9.007~~ ^{4.379} लाख (चौ लाख सात हजार) की राशि से ग्रामीण कार्य विभाग, कार्य प्रमंडल मनिहारी अन्तर्गत अमदाबाद प्रखंड के T01 To Mandal Tola Belgachi पथ हेतु तैयार की गई है। वर्तमान वर्ष 2021 के बाढ़ एवं अतिवृष्टि के कारण क्षतिग्रस्त पथ को MIS पर अपलोड किया जा चुका है, तथा विभागीय निर्देश ग्रामीण कार्य विभाग, बिहार के पत्रांक- मु0अ0-4 (मु0) विविध (कार्य)-23/291/2019-4275/पटना, दिनांक 22.10.2021 के आलोक में यातायात (Motorable) पुर्नस्थापन किया गया है।

उपर्युक्त प्राक्कलन में पथ के गहरे कटाव स्थान पर मिट्टी भरने के पश्चात ईंट का टुकड़ा डाला गया है तथा फलैंक में जहाँ पानी का कटाव हो रहा था उस स्थान पर बास का बल्ला गाड़कर चचरी के बाद ईंट का टुकड़ा दिया गया है।

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग, कार्य अंचल पूर्णियाँ द्वारा प्राप्त कोटेशन के न्यूनतम दर पर तैयार किया गया है प्राक्कलन की स्वीकृति जनहित में अति आवश्यक है।


कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, अमदाबाद


सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, अमदाबाद


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, मनिहारी

Inspection Report for flood damage work

Date :

1. Name of PIUs Manihari

2. Name of Block/Road Amdabad / Toi To Mandal Tola Belgachi

A for Road

1. Damage location : 0.00 km, 0.30, 0.460,

2. Damage Length : 0.064 km

3. Nature of Damage : Scour & Partially Cut.

4. Details of Restoration :

- Material being used in Restoration E/w, Sand bag, bamboo, bricksbale
- Equipment/Tools being used in Restoration Works : Tractor, JCB,
- Procedure taken up in Restoration works: Manual
- Restored Length 0.064 km

B. for Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i. Material being used in Restoration :

ii. Equipment/Tools being used in Restoration Works :

iii. Procedure taken up in Restoration works:

iv. Restored Length

Signature of JE/AE/EE

Executive Engineer
Rural Works Department
Manihari

Signature

(Name of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

T01 TO MANDAL TOLA BELGACHHI

NAME OF ROAD :

DISTRICT

KATIHAR

DIVISION

MANIHARI

BLOCK

AMDABAD

LENGTH OF ROAD (IN KM)

0.950

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	3.867 1.512
2	HUME PIPE	0.000
3	BRICK BAT	2.643 1.345
4	SAND BAGS	1.178 0.874
5	G.S.B.	0.000
5	BAMBOO WORK	0.000
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		7.888 3.731
Add G.S.T. @ 12%		0.923 0.448
Add Labour Cess @ 1%		0.077 0.037
Add Seigniorage Fee @ 10%		0.319 0.163
Total Cost of Restoration Work =		9.007 4.379

J.E.
RWD
26/11/21

A.E.
RWD
26/11/21

E.E.
RWD

Technically Sanction for Rs. 4.379 Lac (Rs.)

Creore. Four Lac. thirty seven

Thousand. nine Hundred.

Superintendent Engineer
Rural Works Department
Works Circle, Purnea