



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

L030 TO EARTHAN (OXA KORA NORTH TOLA)

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 900	
DISTRICT	KATIHAR	
BLOCK	AMDABAD	
DIVISION	MANIHARI	
TOTAL LENGTH OF ROAD	0.900	KM
TOTAL COST OF F.D.R. PART - A	Rs. 4.435 1.771	Lacs
ADD G.S.T @ 12%	Rs. 0.532 0.212	Lacs
ADD Labour Cess @ 1%	Rs. 0.044 0.018	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.142 0.117	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 5.153 2.118	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari

प्रतिवेदन

पथ का नाम :- L030 To Earthen (Oxa Kora North Tola)
पथ की लम्बाई :- 0.900 KM
प्राक्कलित राशि :- ^{2.1/18} 5.153 Lac
वित्तीय वर्ष :- 2021-22 / FDR-2021
प्रखंड :- Amdabad

प्रस्तुत प्राक्कलन मो 0 ^{2.1/18} 5.153 लाख (पाँच लाख पन्द्रह हजार तीन सौ) की राशि से ग्रामीण कार्य विभाग, कार्य प्रमंडल मनिहारी अन्तर्गत अमदाबाद प्रखंड के L030 To Earthen (Oxa Kora North Tola) पथ हेतु तैयार की गई है। वर्तमान वर्ष 2021 के बाढ़ एवं अतिवृष्टि के कारण क्षतिग्रस्त पथ को MIS पर अपलोड किया जा चुका है, तथा विभागीय निर्देश ग्रामीण कार्य विभाग, बिहार के पत्रांक- मु0अ0-4 (मु0) विविध (कार्य)- 23/291/2019 -4275/ पटना, दिनांक 22.10.2021 के आलोक में यातायात (Motorable) पुर्नस्थापन किया गया है।

उपर्युक्त प्राक्कलन में पथ के गहरे कटाव स्थान पर मिट्टी भरने के पश्चात ईट का टुकड़ा डाला गया है तथा कटे हुए स्थान के दोनो तरफ Cement Bag का प्रयोग किया गया है और आवागमन चालू किया गया है।

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग, कार्य अंचल पूर्णियाँ द्वारा प्राप्त कोटेशन के न्यूनतम दर पर तैयार किया गया है प्राक्कलन की स्वीकृति जनहित में अति आवश्यक है।


कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, अमदाबाद


सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, अमदाबाद


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, मनिहारी

Inspection Report for flood damage work

Date :

1. Name of PIUs Manihasi
2. Name of Block/Road Amdabad / Lo30 To Earthan (Oxa Kora North Tole.)

A for Road

1. Damage location : 0.46
2. Damage Length : 0.093 km
3. Nature of Damage : Crops cut.
4. Details of Restoration :
 - i. Material being used in Restoration Sand, Bricks bat, E/W
 - ii. Equipment/Tools being used in Restoration Works : Tractor
 - iii. Procedure taken up in Restoration works: Manual
 - iv. Restored Length 0.093 km

B. for Bridge

1. Damage Location/Chainage :
2. Damage Length :
3. Nature of Damage :
4. Details of Restoration :
 - i. Material being used in Restoration :
 - ii. Equipment/Tools being used in Restoration Works :
 - iii. Procedure taken up in Restoration works:
 - iv. Restored Length

Signature of JE/AE/EE

[Signature]
26/11/21
Executive Engineer
Rural Works Department
Manihasi Division, Manihasi

Signature

(Name of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : L030 TO EARTHAN (OXA KORA NORTH TOLA)

DISTRICT KATIHAR

DIVISION MANIHARI

BLOCK AMDABAD

LENGTH OF ROAD (IN KM) 0.900

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	2.685
2	HUME PIPE	0.000
3	BRICK BAT	1.441
4	SAND BAGS	0.329
5	G.S.B.	0.000
5	BAMBOO WORK	0.000
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		4.435
Add G.S.T. @ 12%		0.532
Add Labour Cess @ 1%		0.044
Add Seigniorage Fee @ 10%		0.442
Total Cost of Restoration Work =		5.453

2.118

J.E.
RWD
86/10/17

A.E.
RWD

E.E.
RWD

Technically Sanction for Rs. 2.118 Lac (Rs.)

Crore. TWO Lac. Eleven

Thousand. Eight Hundred. Only

Superintendent Engineer
Rural Works Department
Works Circle, Purnea