



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

GOGAN SAH INARA AT MANIJARI AMDABAD PWD ROAD TO
GOGABIL JHILL

DETAILED ESTIMATE OF F.D.R.

ROAD LENGTH	0 TO 3500	
DISTRICT	KATIHAR	
BLOCK	MANIHARI	
DIVISION	MANIHARI	
TOTAL LENGTH OF ROAD	3.500	KM
TOTAL COST OF F.D.R. PART - A	Rs. 10.067	Lacs
ADD G.S.T @ 12%	Rs. 1.208	Lacs
ADD Labour Cess @ 1%	Rs. 0.101	Lacs
Add Seigniorage Fee @ 10 %	Rs. 0.546	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 11.922	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari

प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल मुनिहारी अन्तर्गत मुनिहारी प्रखंड के पथ गोगन साह ईनारा सर मनीजारी अमदाबाद पथ रोड पे गोजबीक झील जो विभागीय Online Morititring System MIS पर अपलोड है के बाद 2021 से क्षतिग्रस्त हो जाने के कारण यातायात लायक Moterable हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-22/10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान अपलोड करते हुए (Moterable) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में2021..... अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के करण इस पथ के रोडवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Moterable कार्य कराया गया है। MIS में उपलोडेड फोटो दिनांक 2021.09.14..... का Lat/Long के साथ लिया गया है। नेपाल तराई से निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटरेबल कार्य में आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का पाइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धत है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।

कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, मुनिहारी.....

सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, मुनिहारी.....

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, मुनिहारी.....

Inspection Report for Road damage work

Date:

1. Name of PIUs- RWD Manihari

2. Name of Block/Road- Manihari, Gogam Sah inara at Manihari
Amlebad PWD Road to Gogabikhal

A. For Road

1. Damage Location/Chainage : At different chainage

2. Damage Length : 246.0 m

3. Nature of Damage : Surface, shoulder

4. Details of Restoration :

i. Material being used in Restoration : Bitule Batts.

ii. Equipment/Tools being used in Restoration works : Tractor

iii. Procedure taken up in Restoration works : Manual

iv. Restored Length : 246.0 m

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :


4. Details of Restoration :


i. Material being used in Restoration :

ii. Equipment/Tools being used in Restoration works :

iii. Procedure taken up in Restoration works :

iv. Restored Length :


Signature of JE/AE/EE


AR




Signature

(Name of Inspector)


Scanned with CamScanner

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD GOGAN SAH INARA AT MANIJARI AMDABAD PWD ROAD TO GOGABIL
JHILL
DISTRICT KATIHAR
DIVISION MANIHARI
BLOCK MANIHARI
LENGTH OF ROAD (IN KM) 3.500

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	BRIKCK BAT	10.027
2	SAND BAGS	0.000
3	BAMBOO WORK	0.039
4	HUME PIPE	0.000
TOTAL COST OF PROJECT =		10.067
Add G.S.T. @ 12%		1.208
Add Labour Cess @ 1%		0.101
Add Seigniorage Fee @ 10 %		0.546
Total Cost of Restoration Work =		11.922


JE
RWD


AE
RWD


EE
RWD

Technically Sanction for Rs. 11.922 Lac (Rs. _____
Crore. Eleven Lac. Ninety two
Thousand. two Hundred. _____) Only


Superintendent Engineer
Rural Works Department
Works Circle, Purnea