



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

PMGSY ROAD TO DILARPUR HAT CHOWK

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 1980	
DISTRICT	KATIHAR	
BLOCK	MANIHARI	
DIVISION	MANIHARI	
TOTAL LENGTH OF ROAD	1.980	KM
TOTAL COST OF F.D.R. PART - A	Rs. 7.763	Lacs
ADD G.S.T @ 12%	Rs. 0.932	Lacs
ADD Labour Cess @ 1%	Rs. 0.078	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.423	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 9.196	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari

प्रतिवेदन

पथ का नाम :- PMGSY Road To Dilarpur Hat chowk.

पथ की लम्बाई :- 1.980 KM

प्राक्कलित राशि :- 9.196 Lac

वित्तीय वर्ष :- 2021-2022

प्रखंड :- Manihari

प्रस्तुत प्राक्कलन मौ० 9.196 (नॉ एनालिस उन्नीस हजार दस सौ)


की राशि में ग्रामीण कार्य विभाग, कार्य प्रमंडल मनिहारी अन्तर्गत मनिहारी प्रखंड के S028 To Banfh Ganga पथ हेतु तैयार की गई है। वर्तमान वर्ष 2021 के बाढ़ एवं अतिवृष्टि के कारण क्षतिग्रस्त एवं पथ को MIS पर अपलोड किया जा चुका है, तथा विभागीय निर्देश ग्रामीण कार्य विभाग, बिहार के पत्रांक-मु० अ०-4 (मु०) विविध (कार्य)-23/291/2019-4275/पटना, दिनांक- 22.10.2021 के आलोक में यातायात (Motorable) पुर्नस्थापन किया गया है।

उपर्युक्त प्राक्कलन में क्षतिग्रस्त सड़क के फलैंक/सरफेस को Bricks basts से भरकर आवागमन चाक किया गया है एवं सड़क पर होने वाली दुर्घटना को रोका गया है।

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग, कार्य अंचल पुर्णियाँ द्वारा प्राप्त कोटेशन के न्यूनतम दर पर तैयार किया गया है, प्राक्कलन की स्वीकृति जनहित में अति आवश्यक है।


कनीय अभियंता

ग्रामीण कार्य विभाग
कार्य प्रशाखा, मनिहारी


सहायक अभियंता

ग्रामीण कार्य विभाग
कार्य प्रशाखा, मनिहारी


कार्यपत्रिका अभियंता

ग्रामीण कार्य विभाग
कार्य प्रमंडल, मनिहारी

19

Inspection Report for Flood damage work

Date:

1. Name of PIUs- Rwd Mahinari

2. Name of Block/Road- Mahinari | Pmgsy Road to Dilaspur Hat Chowk.

A. For Road

1. Damage Location/Chainage : At different chainage.

2. Damage Length : 238.70m

3. Nature of Damage : Shoulder, Surface of road.

4. Details of Restoration :

i Material being used in Restoration : Botche Bats.

ii Equipment/Tools being used in Restoration works: Tractor.

iii Procedure taken up in Restoration works :

iv Restored Length : 238.70m

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :

25/11/24
JE

Signature of JE/AE/EE

25/11/24
AE

Signature

(Name of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : PMGSY ROAD TO DILARPUR HAT CHOWK

DISTRICT KATIHAR


DIVISION MANIHARI

BLOCK MANIHARI

LENGTH OF ROAD (IN KM) 1.980


Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.000
3	BRICK BAT	7.763
4	SAND BAGS	0.000
5	BAMBOO WORK	0.000
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		7.763
Add G.S.T. @ 12%		0.932
Add Labour Cess @ 1%		0.078
Add Seigniorage Fee @ 10%		0.423
Total Cost of Restoration Work =		9.196


J.E.
RWD


A.E.
RWD


E.E.
RWD

Technically Sanction for Rs. 9.196 Lac (Rs. Crore Nine Lac Nineteen Thousand Six Hundred Paise)


Superintendent Engineer
Rural Works Department
Works Circle, Purnea