



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

L021-TO PARLA ARAZI

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 2200		
DISTRICT	KATIHAR		
BLOCK	AZAMNAGAR		
DIVISION	MANIHARI		
TOTAL LENGTH OF ROAD		2.200	KM
TOTAL COST OF F.D.R. PART - A		Rs. 9.830	Lacs
ADD G.S.T @ 12%		Rs. 1.180	Lacs
ADD Labour Cess @ 1%		Rs. 0.098	Lacs
ADD Seigniorage Fee @ 10%		Rs. 0.508	Lacs
TOTAL COST OF RESTORATION WORK In Rs.		Rs. 11.615	Lacs
SUBMITTED BY The Executive Engineer, Works Division, Manihari			

प्रतिवेदन


प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल मणिहारी अन्तर्गत आजमनगर प्रखंड के पथ LO21 TO PARLA AREA (.....) जो विभागीय Online Morititring System MIS पर अपलोड है के बाद 2021 से क्षतिग्रस्त हो जाने के कारण यातायात लायक Moterable हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-22/10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान अपलोड करते हुए (Moterable) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में 2021 अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के करण इस पथ के रोडवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Moterable कार्य कराया गया है। MIS में उपलोडेड फोटो दिनांक का Lat/Long के साथ लिया गया है। नेपाल तराई से निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटेरेबल कार्य में आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का पाइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्वत है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।



कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा,



सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल,



कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल,

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : L021-TO PARLA ARAZI


DISTRICT KATIHAR


DIVISION MANIHARI

BLOCK AZAMNAGAR

LENGTH OF ROAD (IN KM) 2.200

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.000
3	BRIKCK BAT	9.321
4	SAND BAGS	0.000
5	BAMBOO WORK	0.509
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		9.830
Add G.S.T. @ 12%		1.180
Add Labour Cess @ 1%		0.098
Add Seigniorage Fee @ 10%		0.508
Total Cost of Restoration Work =		11.615


J.E.
RWD


A.E.
RWD


RWD

Technically Sanctioned for Rs. 11.615 Lac (Rupees Eleven Lac Sixty one thousand and five hundred only).


Superintendent Engineer
Rural Works Department
Works Circle, Purnea

Inspection Report for Flood Damming work

Date:

1. Name of PIUs. **CC RWD MANIHAR**

2. Name of Block/Road. **Azamagar**

A. For Road

LOZI TO Poda Azaari

1. Damage Location/Chainage :

2. Damage Length

3. Nature of Damage

4. Details of Restoration

100 - 300 m.

250 m (approx)

Road cuts due to flood

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works

iii Procedure taken up in Restoration works

iv Restored Length

Gravel bats, Barbed

Tractor, JCB

Manual

Now.

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length

3. Nature of Damage

4. Details of Restoration

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works

iii Procedure taken up in Restoration works

iv Restored Length

 Signature of JE/AE/EE

 Signature

(Name of Inspector)