



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

L022 BELAUNDA PMGSY TO GEDAWARI PURAB TOLA

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 2360		
DISTRICT	KATIHAR		
BLOCK	AZAMNAGAR		
DIVISION	MANIHARI		
TOTAL LENGTH OF ROAD		2.360	KM
TOTAL COST OF F.D.R. PART - A		Rs. 6.688	Lacs
ADD G.S.T @ 12%		Rs. 0.803	Lacs
ADD Labour Cess @ 1%		Rs. 0.067	Lacs
ADD Seigniorage Fee @ 10%		Rs. 0.462	Lacs
TOTAL COST OF RESTORATION WORK In Rs.		Rs. 8.020	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division. Manihari

प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल मतिहरी अन्तर्गत आजमनगर..... प्रखंड के पथ 1022 BELAUNDA PMASPTO GENDABARI PURA TALA (.....) जो विभागीय Online Moritring System MIS पर अपलोड है के बाढ़ 2021 से क्षतिग्रस्त हो जाने के कारण यातायात लायक Moterable हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-22/10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान अपलोड करते हुए (Moterable) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में2021..... अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के कारण इस पथ के रोडवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Moterable कार्य कराया गया है। MIS में उपलोडेड फोटो दिनांक का Lat/Long के साथ लिया गया है। नेपाल तराई से निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटरेबल कार्य में आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का पाइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धत है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।


प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।



कनीय अभियंता

ग्रामीण कार्य विभाग

कार्य प्रशाखा,



सहायक अभियंता

ग्रामीण कार्य विभाग

कार्य अवर प्रमंडल,



कनीय अभियंता


ग्रामीण कार्य विभाग

कार्य प्रमंडल,

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : L022 BELAUNDA PMGSY TO GEDAWARI PURAB TOLA
DISTRICT KATIHAR
DIVISION MANIHARI
BLOCK AZAMNAGAR
LENGTH OF ROAD (IN KM) 2.360

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.000
3	BRIKCK BAT	5.138
4	SAND BAGS	1.550
5	BAMBOO WORK	0.000
6	STEEL DRUM SHEET	0.000
	TOTAL COST OF PROJECT =	6.688
	Add G.S.T. @ 12%	0.803
	Add Labour Cess @ 1%	0.067
	Add Seigniorage Fee @ 10%	0.462
	Total Cost of Restoration Work =	8.020


J.E.
RWD


A.E.
RWD


S.E.
RWD

Technically sanctioned for Rs - 8.020 Lac (Rupees Eight Lac Two thousand) only.


Superintendent Engineer
Rural Works Department
Works Circle, Purnea

Inspection Report for Flood Damage work

Date:

1. Name of PIUs-

E.E R.W.D. Manihari

2. Name of Block/Road-

Azamgarh

W22- Belaulda PHGSy To Genda main perab
Tola.

A. For Road

1. Damage Location/Chainage :

CH-1200-2015W

2. Damage Length :

169.20M

3. Nature of Damage :

4. Details of Restoration :

Road cuts due to flood.

i Material being used in Restoration

: Bridge Bats, Bamboo

ii Equipment/Tools being used in Restoration works:

: Tractor, TCB.

iii Procedure taken up in Restoration works

iv Restored Length

169.20M

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

Signature of JE/AE/EE

Signature

(Name of Inspector)