



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

S0170 PWD PATH SONELI PATH TO LALGAUON

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 2988		
DISTRICT	KATIHAR		
BLOCK	AZAMNAGAR		
DIVISION	MANIHARI		
TOTAL LENGTH OF ROAD	2.988		KM
TOTAL COST OF F.D.R. PART - A	Rs. 9.286		Lacs
ADD G.S.T @ 12%	Rs. 1.114		Lacs
ADD Labour Cess @ 1%	Rs. 0.093		Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.445		Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 10.938		Lacs


SUBMITTED BY
The Executive Engineer,
Works Division, Manihari

प्रतिवेदन


प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल गजिहरी अन्तर्गत आजमनगर..... प्रखंड के पथ SOI 70 PWD Path Soneli Path To Lalgawan..... (.....) जो विभागीय Online Morititring System MIS पर अपलोड है के बाद 2021 से क्षतिग्रस्त हो जाने के कारण यातायात लायक Moterable हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-22/10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान अपलोड करते हुए (Moterable) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में²⁰²¹..... अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के कारण इस पथ के रोडवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Moterable कार्य कराया गया है। MIS में उपलोडेड फोटो दिनांक का Lat/Long के साथ लिया गया है। नेपाल तराई से निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटरेबल कार्य में आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का पाइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धत है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।



कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा,



सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल,



कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल,

Inspection Report for Flood damage work

Date:

1. Name of PIUs-

E.E.R.N.D, Naurani

2. Name of Block/Road-

SOITD PWD Path To Lalgaon
Azamnagar.

A. For Road

1. Damage Location/Chainage :

at 1.52 km.

2. Damage Length :

73.0 m.

3. Nature of Damage :

4. Details of Restoration :

Road cut.

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

For the Bats, Bambrophi. Bag.

Tractor, JCB, -
Manual.

73.0 m.

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

Signature of JE/AE/EE


Signature


(Name of Inspector)


GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : S0170 PWD PATH SONELI PATH TO LALGAUON
DISTRICT KATIHAR
DIVISION MANIHARI
BLOCK AZAMNAGAR
LENGTH OF ROAD (IN KM) 2.988


Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.351
2	HUME PIPE	0.000
3	BRIKCK BAT	8.175
4	SAND BAGS	0.000
5	BAMBOO WORK	0.760
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		9.286
Add G.S.T. @ 12%		1.114
Add Labour Cess @ 1%		0.093
Add Seigniorage Fee @ 10%		0.445
Total Cost of Restoration Work =		10.938


J.E.
RWD


A.E.
RWD


E.E.
RWD

Technically Sanction for Rs 10.938 lacs (Rupees ten & nineteen Ninety three thousand eight hundred only).


Superintendent Engineer
Rural Works Department
Works Circle, Purnea