



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

PMGSY ROAD HURRA HAZARA TO CHANDIPUR

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 1875	
DISTRICT	KATIHAR	
BLOCK	AZAMNAGAR	
DIVISION	MANIHARI	
TOTAL LENGTH OF ROAD	1.875	KM
TOTAL COST OF F.D.R. PART - A	Rs. 4.395	Lacs
ADD G.S.T @ 12%	Rs. 0.527	Lacs
ADD Labour Cess @ 1%	Rs. 0.044	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.205	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 5.171	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari

प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल मनिहारी अन्तर्गत आजमनगर प्रखंड के पथ PMWSY रोड हरा हाजरा से चण्डीपुर (.....) जो वेभागीय Online Morititring System MIS पर अपलोड है के बाढ़ 2021 से क्षतिग्रस्त हो जाने के कारण यातायात लायक Moterable हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य वेभाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-2/10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान अपलोड करते हुए (Moterable) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में2021..... अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के कारण इस पथ के ढोवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Moterable कार्य कराया गया है। MIS में अपलोडेड फोटो दिनांक का Lat/Long के साथ लिया गया है। नेपाल तराई से निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटेरेबल कार्य में आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का पाइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धत है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।

20/11/21

ग्रामीण कार्य विभाग

कार्य प्रशाखा, आजमनगर

20/11/21

सहायक अभियंता

ग्रामीण कार्य विभाग

कार्य अवर प्रमंडल, आजमनगर

कार्यपालक अभियंता

ग्रामीण कार्य विभाग

कार्य प्रमंडल, मनिहारी

Inspection Report for flood damage work

Date:

1. Name of PIUs- **EE RWD MANIHARI**

2. Name of Block/Road- **Azamnagar**

A. For Road **Pingey road Hura Hazra To Chandipur**

1. Damage Location/Chainage : **at 300**
2. Damage Length : **93.07 M**
3. Nature of Damage : **Side cutting due to flood**
4. Details of Restoration :
i Material being used in Restoration **Bricks: bats**
ii Equipment/Tools being used in Restoration works: **Tractor**
iii Procedure taken up in Restoration works : **Manual**
iv Restored Length : **93.07 M**

B. For Bridge

1. Damage Location/Chainage :
2. Damage Length :
3. Nature of Damage :
4. Details of Restoration :
i Material being used in Restoration :
ii Equipment/Tools being used in Restoration works :
iii Procedure taken up in Restoration works :
iv Restored Length :

DP
3/11/21

Signature of JE/AG/EE

4/11/21

Signature

(Name of Inspector)

2/11"

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : PMGSY ROAD HURRA HAZARA TO CHANDIPUR

DISTRICT KATIHAR

DIVISION MANIHARI


BLOCK AZAMNAGAR

LENGTH OF ROAD (IN KM) 1.875


Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.000
3	BRIKCK BAT	3.772
4	SAND BAGS	0.000
5	BAMBOO WORK	0.623
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		4.395
Add G.S.T. @ 12%		0.527
Add Labour Cess @ 1%		0.044
Add Seigniorage Fee @ 10%		0.205
Total Cost of Restoration Work =		5.171


J.E.
RWD


A.E.
RWD


E.E.
RWD

Technically sanctioned for Rs. 5.171 lacs (Rupees -
Five lacs Seventeen thousand & one hundred
only .


Superintendent Engineer
Rural Works Department
Works Circle, Purnea