



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

T01 TO BENGALI TOLA

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 1150	
DISTRICT	KATIHAR	
BLOCK	AZAMNAGAR	
DIVISION	MANIHARI	
TOTAL LENGTH OF ROAD	1.150	KM
TOTAL COST OF F.D.R. PART - A	Rs. 2.858	Lacs
ADD G.S.T @ 12%	Rs. 0.343	Lacs
ADD Labour Cess @ 1%	Rs. 0.029	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.156	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 3.386	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari

प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल मनिहारी अन्तर्गत आजमनगर प्रखंड
पथ 701 से वंगाली रोड (.....) जो
राष्ट्रीय Online Monitoring System MIS पर अपलोड है के बाढ़ 2021 से क्षतिग्रस्त हो जाने के
कारण यातायात लायक Motorable हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य
भाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-
/10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान
अपलोड करते हुए (Motorable) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में 2021 अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के कारण इस पथ के
अवस्था के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Motorable कार्य कराया गया है। MIS में
अपलोडेड फोटो दिनांक का Lat/Long के साथ लिया गया है। नेपाल तराई से
जलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटरेबल कार्य में
वश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का
इल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए
गये कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धत है। MIS की
छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन
संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।

नीय अभियंता

ग्रामीण कार्य विभाग

कार्य प्रशाखा, आजमनगर

सहायक अभियंता

ग्रामीण कार्य विभाग

कार्य अवर प्रमंडल, आजमनगर

कार्यपालक अभियंता

ग्रामीण कार्य विभाग

कार्य प्रमंडल, मनिहारी

Date:

Inspection Report for flood damage work

1. Name of PIUs- E.E RWD MANIHARI

2. Name of Block/Road- Azamnagar

A. For Road

Tol To Bangali Tola

1. Damage Location/Chainage : at - 50,500, g.w at different chainage

2. Damage Length : 35.2 M

3. Nature of Damage : side cutting due to flood

4. Details of Restoration :

i Material being used in Restoration Bricks : bats

ii Equipment/Tools being used in Restoration works: Tractor

iii Procedure taken up in Restoration works : Manual

iv Restored Length : 35.2 M

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration :

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works :

iv Restored Length :

Signature of JE/AE/EE

Signature

(Name of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : T01 TO BENGALI TOLA

DISTRICT KATIHAR

DIVISION MANIHARI

BLOCK AZAMNAGAR

LENGTH OF ROAD (IN KM) 1.150

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.000
3	BRIKCK BAT	2.858
4	SAND BAGS	0.000
5	BAMBOO WORK	0.000
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		2.858
Add G.S.T. @ 12%		0.343
Add Labour Cess @ 1%		0.029
Add Seigniorage Fee @ 10%		0.156
Total Cost of Restoration Work =		3.386


J.E.
RWD


A.E.
RWD


E.E.
RWD

Technically Sanction for Rs 3.386 lacs (Rupees three lacs thirty eight thousand six hundred) only


Superintendent Engineer
Rural Works Department
Works Circle, Purnea