



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

T01 NABARD PATH AZAMNAGAR PAIKWAHAN PATH TO MADHI SINGH
TOTAL WARD NO. 1

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 1545	
DISTRICT	KATIHAR	
BLOCK	AZAMNAGAR	
DIVISION	MANIHARI	
TOTAL LENGTH OF ROAD	1.545	KM
TOTAL COST OF F.D.R. PART - A	Rs. 16.313	Lacs
ADD G.S.T @ 12%	Rs. 1.958	Lacs
ADD Labour Cess @ 1%	Rs. 0.163	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.888	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 19.322	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari

प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल मनिहारी अन्तर्गत आजमनगर प्रखंड
थ नेपाल तराई पत्र आजमनगर के कटाव पथ के मही खंड टोला का न जो
गीय Online Morititring System MIS पर अपलोड है के बाद 2021 से क्षतिग्रस्त हो जाने के
ण यातायात लायक Moterale हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य
ग, बिहार सरकार के पत्रांक:-मु030-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-
10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान
जोड करते हुए (Moterale) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

निर्देश के आलोक में 2021 अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के करण इस पथ के
वे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Moterale कार्य कराया गया है। MIS में
नोडेड फोटो दिनांक का Lat/Long के साथ लिया गया है। नेपाल तराई से
लनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटरेबल कार्य में
श्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का
ल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए
कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्वत है। MIS की
गप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन
संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।

02/11/21

नीय अभियंता

ण कार्य विभाग

प्रशाखा, आजमनगर

02/11/21

सहायक अभियंता

ग्रामीण कार्य विभाग

कार्य अवर प्रमंडल, आजमनगर

02/11/21

कार्यपालक अभियंता

ग्रामीण कार्य विभाग

कार्य प्रमंडल, मनिहारी

Date:

Inspection Report for flood damage work

1. Name of PIUs-

EE RWD MANIHARI

2. Name of Block/Road-

Azamnagar

A. For Road

Tol Naband Path Azamgar Paikwahon Path To
Madhi Singh Tola ward No-1

1. Damage Location/Chainage :

at - 100, 200, 300 at different change

2. Damage Length :

109 M

3. Nature of Damage :

4. Details of Restoration :

Side cutting

i Material being used in Restoration

Bricks : bats

ii Equipment/Tools being used in Restoration works:

Tractor

iii Procedure taken up in Restoration works

Manual

iv Restored Length

109 M

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

Signature of JE/AE/EE

Signature

(Name of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : T01 NABARD PATH AZAMNGAR PAIKWAHAN PATH TO MADHI SINGH
TOLA WARD NO -1

DISTRICT KATIHAR

DIVISION MANIHARI


BLOCK AZAMNAGAR

LENGTH OF ROAD (IN KM) 1.545


Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.000
3	BRIKCK BAT	16.313
4	SAND BAGS	0.000
5	BAMBOO WORK	0.000
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		16.313
Add G.S.T. @ 12%		1.958
Add Labour Cess @ 1%		0.163
Add Seigniorage Fee @ 10%		0.888
Total Cost of Restoration Work =		19.322


J.E.
RWD


A.E.
RWD


J.E.
RWD

*Technically Sanction for Rs 19.322 lacs (Rupees Nineteen lacs
— thirty two thousand — two hundred) only.*


Superintendent Engineer
Rural Works Department
Works Circle, Purnea