



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

MANSARI HAT TO KURSEL

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 4600	
DISTRICT	KATIHAR	
BLOCK	MANSARI	
DIVISION	MANIHARI	
TOTAL LENGTH OF ROAD	4.600	KM
TOTAL COST OF F.D.R. PART - A	Rs. 3.441	Lacs
ADD G.S.T @ 12%	Rs. 0.413	Lacs
ADD Labour Cess @ 1%	Rs. 0.034	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.187	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 4.075	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Manihari

प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल मनिहरी अन्तर्गत मनसाही प्रखंड के पथ MANSAME HAT TO KURSEL (.....) जो विभागीय Online Morititring System MIS पर अपलोड है के बाद 2021 से क्षतिग्रस्त हो जाने के कारण यातायात लायक Moterable हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-22/10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान अपलोड करते हुए (Moterable) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में 2021 अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के करण इस पथ के रोडवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Moterable कार्य कराया गया है। MIS में उपलोडेड फोटो दिनांक 31.10.21 का Lat/Long के साथ लिया गया है। नेपाल तराई से निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटरेबल कार्य में आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का पाइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धत है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।

मनसाही
28/11/21

कनीय अभियंता

ग्रामीण कार्य विभाग

कार्य प्रशाखा, मनसाही

मनसाही
30-11-21

सहायक अभियंता

ग्रामीण कार्य विभाग

कार्य अवर प्रमंडल, मनसाही

कार्यपालक अभियंता

ग्रामीण कार्य विभाग

कार्य प्रमंडल, मनिहरी

Inspection Report for flood damage work

Date:

1. Name of PIUs- Executive Engineer Manihari

2. Name of Block/Road- Mansahi / Mansahi Hat to Kursel.

A. For Road Mansahi Hat to Kursel.

1. Damage Location/Chainage : at different change

2. Damage Length : 88 M

3. Nature of Damage : Road Washout.

4. Details of Restoration :

i Material being used in Restoration

: Bricks Bala

ii Equipment/Tools being used in Restoration works:

: Tractor/Roller etc.

iii Procedure taken up in Restoration works

: Brick Bala Laying, Rolling.

iv Restored Length

: 88 M

B. For Bridge

1. Damage Location/Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration :

i Material being used in Restoration

ii Equipment/Tools being used in Restoration works:

iii Procedure taken up in Restoration works

iv Restored Length

Signature of JE/AE/EE

July 30.11.21
AE

Signature

(Name of Inspector)

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD MANSAHI HAT TO KURSEL
DISTRICT KATIHAR
DIVISION MANIHARI
BLOCK MANSAHI
LENGTH OF ROAD (IN KM) 4.600

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.000
3	BRIKCK BAT	3.441
4	SAND BAGS	0.000
5	BAMBOO WORK	0.000
6	STEEL DRUM SHEET	0.000
7	GSB	0.000
TOTAL COST OF PROJECT =		3.441
Add G.S.T. @ 12%		0.413
Add Labour Cess @ 1%		0.034
Add Seigniorage Fee @ 10%		0.187
Total Cost of Restoration Work =		4.075

[Signature]
28/11/21
J.E.
RWD

[Signature]
30.11.21
A.E.
RWD

[Signature]
E.E.
RWD

Technically Sanction for Rs. 4.075 Lac (Rs.
Crore. four Lac. seven ..
Thousand. five Hundred.) Only

[Signature]
Superintendent Engineer
Rural Works Department
Works Circle, Purnea