



FLOOD DAMAGE REPAIR (FDR)
YEAR 2021-22

FOR T/A

DISTRICT :- BEGUSARAI
BLOCK :- BACHHAWARA

CONSTRUCTION COST	:- Rs. 0.798 Lac
TOTAL COST	:- Rs. 0.798 Lac

MMGSY YOJNA

NAME OF ROAD :- FLOOD DAMAGE REPAIR OF CHAN
BHARKHOOT L06 CHHOT KHUT TO
LAXMAN TOLA BHARAT CHOWK

TOTAL LENGTH	: 1.800KM
LENGTH DAMAGE DUE TO FLOOD	: 0.016 KM.

SUBMITTED BY:
EXECUTIVE ENGINEER
R.W.D. WORKS DIVISION, TEGHRA

**Flood Damage Repair of Chan
Bharkhoot L06 Chhot khut to
Laxman tola Bharat chowk**

Name of Road :-

Year 2021-22

District :-

Begusarai

Block :-

Bachhawara

GENERAL ABSTRACT OF COST

Sl No.	Item of Work	Amount (in Rs.) As Per Estimate
1	COST OF FDR	69,184.00
2	Add L.C. @1%	692.00
3	ADD GST @ 12%	8,302.00
	Sub Total Rs. :--	78,178.00
	Add S.F. @ 10% on Material Rate	1,564.00
	Total Rs. :--	79,742.00
	Say Rs. :--	79,800.00

Gul 22/11/21

J.E

A.E.

22/11/21
E.E.

RWD. Teghra RWD. Teghra

RWD. Teghra

Sanctioned for Rs 79,800 = 00 say seventy nine thousand Eight Hundred only including @ HCL and Crp.

10.12.21

10/12/21
बसोबस बाबबका
बाबोब बाबे बिबाब
40 बाबे बाबक, बाबबोब

SDB SL.NO	MOR D Ref.N o	Description	Unit	NOS	LENGTH	WIDTH	HEIGHT	QUANTITY	RATE	AMOUNT (In Rs.)
1		Providing brick bats including ,spreading,laying, hand packing with CI hammers in layers has exceeding 75mm thick including cost of light barriers,danger equal,choukidar,taxes,royalty etc all complete job, as per specifications and direction of E/I including cost of bricks,.....all complete job.								
		Qty From Calculation Sheets	Cum					36.48	1896.72	69,184.00

G.R. Singh
J.E
RWD. Teghra

A.E.
RWD. Teghra

am/ef
E.E.
RWD. Teghra 11/7

ABSTRACT OF QUNTITY (QUANTITY CALCULATION SHEET)

SL. NO.			NO.	LENGTH	WIDTH	DEPTH		QUANTITY	
#REF!	Providing brick bats including ,spreading,laying, hand packing with CI hammers in layers has exceeding 75mm thick including cost of light barriers,danger equal,choukidar,taxes,royalty etc all complete job, as per specifications and direction of E/I including cost of bricks,.....all complete job.								
			1.00	5.5	2.600	0.975	=	13.943	
			1.00	10.4	2.667	0.813	=	22.533	
	TOTAL QUANTITY			15.9			=	36.476	CuM

J.E

A.E.

E.E.

F.D.R.OF ROAD FROM CHAN BHARKHUT L06 CHHOT KHUT TO LAXMAN TOLA BHARAT CHOWK



G.V.
 24/10/22
 J.E.

24/10/22
 A.E.

24/10/22
 E.E.

RWD (W) DIVISION TEGHRA

RWD (W) DIVISION TEGHRA

RWD (W) DIVISION TEGHRA

F.D.R.OF ROAD FROM CHAN BHARKHUT L06 CHHOT KHUT TO LAXMAN TOLA BHARAT CHOWK



GHS
 24/11/22
 J.E.

LM
 24.11.22
 A.E.

gmBie
 24/11/22
 E.E.

RWD (W) DIVISION TEGHRA

RWD (W) DIVISION TEGHRA

RWD (W) DIVISION TEGHRA

कार्यपालक अभियंता का कार्यालय

ग्रामीण कार्य विभाग, कार्य प्रमण्डल, समस्तीपुर

पत्रांक—

Comp. Teghna, 01

दिनांक— 7.12.21

प्रेषक,

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, समस्तीपुर।

सेवा में,

कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, तेघड़ा (बेगूसराय)।

विषय: शीर्ष-FDR अन्तर्गत पथों की जांच प्रतिवेदन समर्पित करने के संबंध में
प्रसंग : कार्यपालक अभियंता, ग्रामीण कार्य विभाग, तेघड़ा (बेगूसराय) के पत्रांक—

11.12.21

दिनांक— 24.11.2021

महाशय,

उपर्युक्त विषयक प्रसांगिक पत्र के संबंध में कहना है कि ग्रामीण कार्य विभाग, कार्य प्रमण्डल, तेघड़ा (बेगूसराय) के अधीन शीर्ष-FDR अन्तर्गत वर्ष- 2021-22 के पथों की जाँच कर जाँच प्रतिवेदन आवश्यक कारवाई हेतु समर्पित किया जाता है।

अनु०— पथों की सूची।

विश्वासभाजन

7.12.21

कार्यपालक अभियंता

ग्रामीण कार्य विभाग, कार्य प्रमण्डल, समस्तीपुर।

ग्रामीण कार्य विभाग, कार्य प्रमण्डल, तेघड़ा द्वारा कराये गये पथों की जाँच से संबंधित प्रतिवेदन

क्र० सं०	पथ का नाम	क्षतिग्रस्त भाग (मी० में)	कराये गये कार्य	कराये गये कार्य की राशि (रु०)	GST @ 12%	L. Cess @ 1%	S.F. @ 10%	Total	अभियुक्ति
1	NH JHAMATIA GHAT - GOPALPUR	188.000	Bricks bats,sand bags,Bamboo piling	700937.00	84112.00	7009.00	13883.00	805941.00	कार्य पूर्ण ।
2	NH-28 Rani to Bhajos Dih	711.000	Bricks bats	416574.00	49989.00	4166.00	24074.00	494803.00	कार्य पूर्ण ।
3	X Road - Chan Barkhut C. Ghat	174.000	Brics Bats,Sand bags	414436.00	49732.00	4144.00	9366.00	477678.00	कार्य पूर्ण ।
4	Kadrabad (PWD Road) To (Dharampur) Bachhwara	95.000	Bricks bats,sand bags,GSB Gr-II	218310.00	26197.00	2183.00	4934.00	251624.00	कार्य पूर्ण ।
5	Railway Gumti Bachhwara to Siswa Road	120.000	Brics Bbat	279283.00	33514.00	2793.00	16141.00	331731.00	कार्य पूर्ण ।
6	Chamtha REO Goptol to Chiraiyatok(Rescined work)	27.000	Bricks Bats, Sand bags	69608.00	8353.00	696.00	1573.00	80230.00	कार्य पूर्ण ।
7	Chan Bharkhoot L06 Chhot khut to Laxman tola Bharat chowk	16.000	Brics bats	69184.00	8302.00	692.00	1564.00	79742.00	कार्य पूर्ण ।
8	Constriction of bridge of size 4x24.75 m. on Dadopur ghat of Baya river of Bachhawara block in Begusarai Dist.	39.000	Brics Bats,Sand bags	71333.00	8560.00	713.00	1612.00	82218.00	कार्य पूर्ण ।
9	PWD RD - MOKARIR	79.000	Brics bats	134076.00	16089.00	1341.00	3030.00	154536.00	कार्य पूर्ण ।
10	L039 - T01 Chabilapur to Barkurwa (VR39)	78.000	Brics bats	663207.00	79585.00	6632.00	38326.00	787750.00	कार्य पूर्ण ।
11	Tara Chowk to Rampur	5.000	Sand bags,Bricks bats,HP -600mm dia	93011.00	11161.00	930.00	2102.00	107204.00	कार्य पूर्ण ।
12	PWD ROAD - DAHRATHPUR	132.000	Sand bags	115900.00	13908.00	1159.00	2619.00	133586.00	कार्य पूर्ण ।
13	Patni Chowk Rwd Road to Makratol	168.000	E/W,Sand bags,Brics bats,HP NP-3 1000mm dia	788628.00	94635.00	7886.00	17823.00	908972.00	कार्य पूर्ण ।
14	L023-NH-28 To Temahuan(VR23)Chlwanr	6.000	Bricks bats	90680.00	10882.00	907.00	5243.00	107712.00	कार्य पूर्ण ।
15	S048 Mahadalit Tola to Larwapur Bandh Via House of Munna Mahto (Telan)	507.000	Sand bags	319926.00	38391.00	3199.00	7230.00	368746.00	कार्य पूर्ण ।
16	Bachhwara to Samsa Road	341.000	Brics bats	426284.00	51154.00	4263.00	24636.00	506337.00	कार्य पूर्ण ।
17	PMGSY Road Dasrathpur house of ganga giri to MMGSY Road Satbhaiya tola	82.000	Sand bags	87851.00	10542.00	879.00	1985.00	101257.00	कार्य पूर्ण ।
18	L023 - NH-28 To Temahuan (VR23)	61.000	Sand bags	158317.00	18998.00	1583.00	3578.00	182476.00	कार्य पूर्ण ।
19	PWD Road to Rajapur Ragho	21.000	Brics bats	44129	5295.00	441.00	997.00	50862.00	कार्य पूर्ण ।

20	L03-Teghra Atarua P Road To Mananpur	219.000	Bricks bats	235058	28207.00	2351.00	13177.00	278793.00	कार्य पूर्ण ।
21	L032-T02 to Maheshpur	19.000	Bricks bats	116536	13984.00	1165.00	6534.00	138219.00	कार्य पूर्ण ।
22	T02 Churamanchak To Gaura Sima	135.000	Bricks bats	173613	20834.00	1736.00	9733.00	205916.00	कार्य पूर्ण ।
23	PWD To Din Dhayal Path	180	GSB, WBM Gr-III	303852	36462.00	3039.00	18056.00	361409.00	कार्य पूर्ण ।
24	NH-28 To Ayodha	887	Bricks bats ,GSB	369511	44341.00	3695.00	7039.00	424586.00	कार्य पूर्ण ।
25	L038-Issapur To Samastipur Siwan	357	Bricks bats Sand bags	1216963	146036.00	12170.00	27503.00	1402672.00	कार्य पूर्ण ।

उपरोक्त सभी पथों की जाँच की गई जो संतोषप्रद है ।

8825000.00


Excutive Engineer

RWD (W) Division Samastipur

Inspection Report for Flood Damage Work

Date:-

- 1 Name of PIUs- Executive Engineer , R.W.D. Works Division, Teghra , Begusarai
- 2 Name of Block- Baehhawara
- 3 Name of Road /Bridge- Chan Bharkhat Log Chhat Khut to Lakman
tala Bharat chowk.
- A. For Road -
 - 1 Damage Location/Chainage : Ch - 0.355km to 0.361km, 0.391km to 0.401km
 - 2 Damage Length : 16.40 M
 - 3 Nature of Damage : Flank and crest washed out due to flood work
 - 4 Details of Restoration Works :
 - i Material being used in Restoration Works : Bricks bats
 - ii Equipments/ Tools being used in Restoration Works : Tractor, JCB, skilled labour, etc.
 - iii Procedure taken up in Restoration Works : Laying of Bricks bats with light ramming.
 - iv Restored Length : 16.40 M
- B For Bridge - N/A
 - 1 Damage Location/Chainage : N/A
 - 2 Damage Length : N/A
 - 3 Nature of Damage : N/A
 - 4 Details of Restoration Works : N/A
 - i Material being used in Restoration Works : N/A
 - ii Equipments/ Tools being used in Restoration Works : N/A
 - iii Procedure taken up in Restoration Works : N/A
 - iv Restored Length : N/A


J.E.


A.E.


Executive Engineer

R.W.D. Works Division, Teghra, Begusarai

Work done, Sah's factory


Signature

(Name of Inspector)