



बिहार सरकार

ग्रामीण कार्य विभाग

Rural Works Department, Govt. of Bihar

FDR

ESTIMATE FOR MOTERABLE OF ROAD

YEAR - 2021-22

DISTRICT :- DARBHANGA

BLOCK :- BAHADURUR

Total Cost of Project:- Rs. 12.50559 Lacs

11.28/9.34

Name of Raad :- Gopipatti Muslim Tola to Dekuli-Sisauni.

Total Length :- 1.715 KM.

Effective Length :- 0.441 KM.

EXECUTIVE ENGINEER
RWD, DARBHANGA-1

Inspection Report of Flood Damage work

Name of PIUs:- RWD Works Division, Darbhanga

Name of Block/Road:- *gopibatti muklim talu to Dehul-Sikauri*

A. For Road

1. Damage Location Chainage:- *0 to 1.715 km*
2. Damage Length :- *0.441 km*
3. Nature of Damage :- *Road Surface damage.*
4. Details of Restoration Works

- i. Material being used in Restoration works:- *Brick Bats*
- ii. Equipment's /Tools being used in Restoration works:- *TCB/Tractor, Labour*
- iii. Procedure taken up in Restoration works:- *Laying of Brick work with*
- iv. Restored Length:- *0.441 km* *Light Ramping*

B. For Bridge

1. Damage Location Chainage:-
2. Damage Length :-
3. Nature of Damage :-
4. Details of Restoration Works

- i. Material being used in Restoration works:-
- ii. Equipment's /Tools being used in Restoration works:-
- iii. Procedure taken up in Restoration works:-
- iv. Restored Length:-

M/R

work found satisfactory.

Signature of JE/AE/EE

Charu
11/12/21
AE

Signature

(Name of Inspection)

25/12/21

FDR

DISTRICT :-	DARBHANGA	
BLOCK :-	BAHADURPUR	
Name of Raad :-	Gopipatti Muslim Tola to Dekuli-Sisauni.	
	Length of the Road:-	1.715 KM.
	Effective Length	0.441 KM.

GENERAL ABSTRACT OF COST

Sl No.	Item of Work				Amount
					(in Rs.)
1	Cost for restoration				9,54,965.92 / 10,58,224.41
2	Add 12 % GST				1,14,595.91 / 1,26,986.93
3	Add 1 % Labour Cess				9549.65 / 10,582.24
4	Seigniorage Fee	Quantity (in cum)	Rate (in Rs.)	%	
	(Br. Bats) in cum	530.676	1032.00	10.00	49403.9 / 54,765.79
		478.72			
	Total cost:-				11,28,515.38 / 12,50,559.37
	Say Rs.				11,28,515.38 / 12,50,559.00

[Signature]
66.11.2021
Junior Engineer
Bahadurpur

[Signature]
6.11.21
Assistant Engineer
Bahadurpur

[Signature]
Executive Engineer
R.W.D.(W) Division, Darbhanga-1

कार्यपालक अभियंता, लेनीपुर के लॉच प्रालेख के आधार पर —

Technically sanctioned for Rs 1128515 = 11 (Rs)
Eleven lacs twenty Eight thousand five hundred fifteen
only)

[Signature]
अधिक्षण अभियंता
कार्य अंचल, दरभंगा
[Signature]

				2nd KM									
cum	1	3.00			3.00	0.350	0.350		0.400	3.350			
cum	1	27.00	3.00	4.00	3.50	0.350	0.350	0.400	0.350	38.750			
cum	1	3.00	3.00	3.20	3.10	0.400	0.250		0.350	2.750			
cum	1	6.00			0.80				0.350	1.440			
cum	1	4.00			0.80				0.250	1.480			
cum	1	5.00			0.40	0.075	0.250		0.150	1.275			
cum	1	30.00	3.00	3.30	3.15	0.850	0.850	0.350	0.350	38.350			
cum	1	30.00			3.00	0.350	0.400		0.450	40.350			
cum	1	14.00	3.00	3.50	3.25	0.850	0.850		0.750	31.350			
cum	1	13.00	3.50	4.00	3.75	0.850	0.350		0.450	21.350			
cum	1	15.00			3.20	0.400	0.350	0.400	0.450	21.450	12.03		
cum	1	2.00			0.80				0.075	0.120			
cum	1	30.00			3.75	0.800	0.350	0.350	0.350	75.350	956.05		
cum	1	20.00			3.75	0.800	0.400		0.350	37.350	6.60	670.41	
										353.450	254.350	3078.420	
												155222.4	

309.52

9,54,965.92

P. Bahani
06.11.2021
Junior Engineer
Bahadurpur

M. K. M.
Assistant Engineer
Bahadurpur

P. K. S.
Executive Engineer
R.W.D.(M) Division, Dargah-1

Verified & found correct

M. K.
11-12-21
JE

Charvi
11/12/21
AE

M. K. M.
EE