



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MORTABLE REPAIRING OF ROAD

F.D.R MORTABLE RESTORATION (YEAR - 2021)

L085 - T04 TO CHHATERGACHH COLONY.

DETAILED ESTIMATE OF F. D. R MORTABLE REPAIRING ROAD

BRIDGE LENGTH	188.32M		
DISTRICT	KISHANGANJ		
BLOCK	POTHIA		
DIVISION	KISHANGANJ-2		
TOTAL LENGTH OF BRIDGE	:	188.320	M
TOTAL COST OF F.D.R PART - A	:	13.823	LAKH
ADD GST @ 12 %	:	1.659	LAKH
ADD LABOUR CESS @ 1 %	:	0.138	LAKH
ADD Seigniorage Fee @ 10%	:	0.475	LAKH
TOTAL COST OF RESTORATION WORK in Rs.	:	16.095	LAKH


Submitted By:-
EXECUTIVE ENGINEER
RURAL WORKS DEPARTMENT
WORKS DIVISION KISHANGANJ-2

प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल किशनगंज -2 अन्तर्गत PMUSSY
खंड के पथ Lo 85 - Tou to Chhatengach Colony (PMUSSY) जो
विनागीय Online Monitoring System MIS पर अपलोड है के बाढ़ 2021 से क्षतिग्रस्त हो जाने के
करण यातायात लायक Moterale हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य
विभाग, बिहार सरकार के पत्रांक:-गु0अ0-4(गु0) विविध (कार्य) -23-291/2019-4276/पटना, दिनांक-
2/10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान
अपलोड करते हुए (Moterale) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में 15/11/21 अतिवृष्टि/बाढ़ उपचार से आए बाढ़ के कारण इस पथ के
खंड के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Moterale कार्य कराया गया है। MIS में
अपलोडेड फोटो दिनांक का Lat/Long के साथ लिया गया है। नेपाल तराई से
कलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। गोदरेवल कार्य में
वश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का
इल, घघरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए
ए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धृत है। MIS की
छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विनागीय आदेशों की छायाप्रति प्राक्कलन
संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।


नीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा,
15/11/21


सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल,
15/11/21


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल किशनगंज-2
15/11/21

Inspection Report for Flood Damage Work

1. Name of PIUs : *Kishanganj-2*
 2. Name Of Block / Road : *Pathar /*
 3. For Road : *6085-1764 176 Chhatargachh Colony*
 4. Damage Location / Chainage :
 5. Damage Length :
 6. Nature Of Damage :
 7. Details Of Restoration :
 8. Material Being Used In Restoration :
 9. Equipment / Tools Being Used In Restoration Works :
 10. Procedure Taken Up In Restoration Works :

11. Restored Length :

B. For Bridge

1. Damage Location / Chainage : *6085-1764 176 Chhatargachh Colony*
 2. Damage Length : *8.800 km*
 3. Nature Of Damage : *237 m*
 4. Details Of Restoration : *Diversion Cut & erosion*
 5. Material Being Used In Restoration : *Earthwork, Bunker Filling, Filling, Brickbat*
 6. Equipment / Tools Being Used in Restoration Works : *laying Ee Bag with G sand*
 7. Procedure Taken Up In Restoration Works : *Soil, Bunker, Brick, Sand, Ee Bag*
 8. Restored Length : *Tractor, Trolley, JCB*
 9. : *Manually*
 10. : *237 m*

Signature of JE / AE / EE

(Name Of Inspector)

ABSTRACT OF COST

Name of Work :-	L085 - T04 TO CHHATERGACHH COLONY	
Block :-	Pothia	
Sl. No.	Particulars	Amount (In Rs.)
A	Cost of Restoration work :-	Rs 1382272.00
B	Add 12 % GST	Rs 165873.00
C	Add 1 % L. Cess	Rs 13823.00
D	Add S.Fee @ 10 % of Material Cost	Rs 47521.00
	Total Cost with GST, LC & S.Fee	Rs 1609489.00


J.E.
R.W.D
Pothia


A.E.
R.W.D
Pothia


E.E.
R.W.D
Kishanganj - 2

Technically sanction for Rs. 16,09,489.00 (Rupees
Sixteen Lacs nine thousand four hundred Eighty nine) only


04/04/22
E.O.


अधीक्षण अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल, किशनगंज

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD :-	L085 - T04 TO CHHATERGACHH COLONY		
DISTRICT :	KISHANGANJ		
DIVISION :	KISHANGANJ-2		
BLOCK :-	POTHIA		
LENGTH OF BRIDGE (IN M)	188.32		
Sl. No.	ITEM OF WORK		Amount (In LAKHS.)
1	LOCAL SAND		1.174
2	HUME PIPE		0.000
3	BRICK BATS		6.437
4	SAND BAGS		5.264
5	BAMBOO WORK		0.947
6	STEEL DRUM SHEET		0.000
	TOTAL COST OF PROJECT		13.823
	Add 12 % GST		1.659
	Add 1 % L. Cess		0.138
	Add Seigniorage Fee @ 10 % of Material Cost		0.475
	Total Cost of Restoration Work		16.095


J.E.
R.W.D
POTHIA


A.E.
R.W.D
POTHIA


E.E.
R.W.D
Kishanganj - 2

Detailed Estimate

Name of Work :- L085 - T04 TO CHHATERGACHH COLONY												
SIL No.	SDB SIL No.	MORD Ref.No	Description	No.	No.	Length (M)	Width (M)	Height (M)	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
1	WRD	5.7.7	Providing bamboo piles including labour for cutting of 62 mm to 75 mm dia bamboo piles to size and making shoes and driving etc complete job as per specification and direction of E/I									
				1	70	5.00	-	-	350.00			
				1	70	5.00	-	-	350.00			
				1	70	5.00	-	-	350.00			
				1	105	5.00	-	-	525.00			
				Total:-					1575.00	Mtr.	52.24	82278.00
2	WRD	5.7.9	Supplying, fitting and fixing 62 mm to 75 mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I. wire including cost of G.I. wire or nails, all material and labour complete job as per specification and direction of E/I.									
				1	5	20.00	-	-	100.00			
				1	5	20.00	-	-	100.00			
				1	5	20.00	-	-	100.00			
				1	5	30.00	-	-	150.00			
				Total:-					450.00	Mtr.	27.71	12470.00
3	3.14	303.1	Construction of subgrade and earthen shoulders									
			Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m, as per Technical Specification Clause 303.1.									
				1	1	30.00	6.00	1.10	198.00			
				1	1	20.00	6.00	0.90	108.00			
				Total:-					306.00	Cum	174.93	53529.00
4	9.2 (i)	1100 & 800	Sand filling or Type B (First class) bedding									
			Fillling and spreading local sand over brick bats as per drawing and technical specification Clause 305.3.9									
				1	1	20.00	1.95	0.35	13.65			
				1	1	20.00	1.80	0.40	14.40			
				1	1	20.00	1.75	0.35	12.25			
				1	1	30.00	1.85	0.30	16.65			
				1	1	25.00	1.85	0.30	13.88			
				1	1	26.00	1.85	0.30	14.43			
				1	1	28.00	1.85	0.30	15.54			
				1	1	24.00	1.85	0.30	13.32			
				1	1	24.00	1.40	0.30	10.08			
				Total:-					124.20	Cum	514.43	63892.00
5	WRD	5.7.40	Brick bats									
			Providing laying and spreading brick bats in Road ditches all complete as per approved design, specifications and direction of E/I									
				1	1	20.00	1.95	1.35	52.65			
				1	1	20.00	1.80	0.85	30.60			
				1	1	20.00	1.75	0.75	26.25			
				1	1	30.00	1.85	1.25	69.38			
				1	1	25.00	1.35	0.75	25.31			
				1	1	26.00	1.55	0.80	32.24			
				1	1	28.00	1.50	0.65	27.30			
				1	1	24.00	1.35	0.45	14.58			
				1	1	24.00	1.40	0.55	18.48			
				Total:-					296.79	Cum	2168.72	643654.00

SL No.	SDB SL No.	MORD Ref.No	Description	No.	No.	Length (M)	Width (M)	Height (M)	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
6		5.7.53	Providing and filling empty cement bags									
			Supply of new bag with labour for filling new EC bag with local sand (volume of filled bag 1.2 cft and weight 50kg), stitching on two line by approved nylon thread with stitching machine & generator, stacking the bags and placing with a lead of 150m including supply of nylon threads etc all complete as per approved design, specification and direction of E/I.									
				1	1	20.00	1.20	1.80	43.20			
				1	1	30.00	1.50	1.85	83.25			
				1	1	30.00	1.45	1.75	76.13			
				1	1	10.00	1.25	1.95	24.38			
				1	1	20.00	1.35	1.45	39.15			
				1	1	20.00	1.40	1.80	50.40			
				1	1	28.00	1.40	1.25	49.00			
				1	1	26.00	1.40	1.35	49.14			
				1	1	25.00	1.40	1.60	56.00			
				Total:-					470.65	Cum		
				@ 0.034 Cum each bag					13843	No.	38.03	526449.00
				TOTAL								1382272.00

SEIGNORAGE FEE 10% FOR ROYALTY MATERIAL

LOCAL SAND			124.20	1.20	=	149.04	Cum	141.85	21141.00
BRICK BAT			296.79	1.20	=	356.15	Cum	1,050.00	373955.00
GSB			0.00	1.28	=	0.00	Cum	285.35	0.00
LOCAL SAND			470.65	1.20	=	564.78	Cum	141.85	80114.00
TOTAL MATERIAL COST:-									475210.00
SEIGNORAGE FEE 10%									47521.00

[Signature]
J.E
R.W.D
Pothia

[Signature]
A.E
R.W.D
Pothia

[Signature]
E.E
R.W.D
Kishanganj