

तकनीकी प्रतिवेदन


पथ का नाम :- टो. खे मुरुजापुर
पथ की लंबाई :- 9.529 कि०मी०
प्राक्कलित राशि :- रु. 1,39,807.00
प्रमण्डल का नाम :- बेनीपुर
अंचल का नाम :- दरभंगा
योजना शीर्ष :-
योजना वर्ष :- 2021-22

प्रस्तुत प्राक्कलन विभागीय पत्रांक—मु.अ. 4-4275 पटन दिनांक—22.10.21
के आदेशानुसार पथ में कराये गये यातायात पुर्नस्थापना कार्य के निमित्त तैयार की गयी है।

यह प्राक्कलन टो. खे मुरुजापुर कार्य के लिए तैयार की गई है। वर्ष 2021 में आयी प्रलयंकार बाढ/अतिवृष्टि के कारण पथ कई जगहो पर क्षतिग्रस्त हो गया था। जिसके कारण आवागमन अवरुद्ध हो गई थी जिसमें अस्थाई यातायात पुर्नस्थापन कार्य किया गया है।

प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू अनुसूचित दर पर, जो संवेदक लाभांश को छोडकर था, उसे प्रावधान करते हुए तैयार किया गया है।

अतः किये गये कार्यों के भुगतान हेतु प्राक्कलन की प्रशासनिक स्वीकृति अपेक्षित है।


कनीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रशाखा बेनीपुर


सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमण्डल बेनीपुर


कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल बेनीपुर।

Abstract of cost.

Name of Road:-T06-T01 to Murtuzapur (VR6)

Sl No	Particulars of Item	Quantity (In M ³)	Rate	Amount
1	Providing and laying Filling in ditches with brick bats including loading, unloading and light ramming all complete job. As per specification & Direction of E/I	45.29	2004.96	90805
2	Providing and laying RCC NP3 type Hume Pipeall complete job as per specification and direction of E/I.	10	1582.72 2878.17	15827.20 28782
			Total =	119586
			Add 12% GST	14350
			1% L.C	1196
			S.Fee (45.29*1032*0.1)= 4674	4674
			Grand Total=	139807

1,06,631.20
12,796.20
1066.00

1,25,167.20

Say Rupees 1,39,800.00
20/11/17

J.E
J.E
RWD, Benipur

A.E
A.E
RWD, Benipur

E.E
RWD, Benipur

*Technically Sanctioned for Rs = 1,39,800 (Rupees one Lacs
Thirty nine Thousand Eight Hundred) only
Technically sanctioned for Rs 1,25,167.20 (one Lakh twenty five
thousand one hundred sixty seven rupees)*

Superintending Engineer
Superintending Engineer
RWD, Works Circle, Darbhanga

Flood Estimate

Name of Road:-T06-T01 to Murtuzapur (VR6)

Item No.1	Providing and laying Filling in ditches with brick bats including loading, unloading and light ramming all complete job. As per specification & Direction of E/I				
S.No	Chainage (In M)	Length (In M)	Average Width (In M)	Average Height (In M)	Qty in M ³
	1800m to 1900m	5.00	0.40	0.20	0.40
		1.00	1.50	(.2+.25)/2	0.34
	2400m to 2500m	4.50	(4+8)/2	(1.5+1.8)/2	44.55
Total =					45.29

Item No.2	Providing and laying RCC NP3 type Hume Pipeall complete job as per specification and direction of E/I.				
	600mm dia H.P	2*2.5*2			10

[Signature]
J.E
RWD,Benipur

[Signature]
A.E
RWD,Benipur

[Signature]
E.E
RWD, Benipur

Checked and Verified

[Signature]
13.12.2021
A.E

[Signature]
13/12/21
G.E

Inspection Report of Flood Damage work

Name of PIUs:- RWD Works Division, Benipur

Name of Block/Road:- Benipur | To to mustuzapur

A. For Road

1. Damage Location Chainage:- Ch. 1800 Km to 1900 Km, Ch-2400 Km to Ch 2500 Km
2. Damage Length :- 10.50 m
3. Nature of Damage :- Road crust
4. Details of Restoration Works
 - i. Material being used in Restoration works:- Bridge bats, HPC
 - ii. Equipment's /Tools being used in Restoration works:- Tractor
 - iii. Procedure taken up in Restoration works:- manually filling
 - iv. Restored Length:- 10.50 m

B. For Bridge

1. Damage Location Chainage:-
2. Damage Length :-
3. Nature of Damage :-
4. Details of Restoration Works
 - i. Material being used in Restoration works:-
 - ii. Equipment's /Tools being used in Restoration works:-
 - iii. Procedure taken up in Restoration works:-
 - iv. Restored Length:-

N/A

work found satisfactory.

Signature of JE/AE/EE

Signature
(Name of Inspection)