

तकनीकी प्रतिवेदन

पथ का नाम	:-	शिवनारायण चौधरी डे बर से नेउरी रोड
पथ की लंबाई	:-	2.45 कि०मी०
प्राक्कलित राशि	:-	रु. 3, 11, 85 3=00
प्रमण्डल का नाम	:-	दरभंगा बेनीपुर
अंचल का नाम	:-	दरभंगा
योजना शीर्ष	:-	
योजना वर्ष	:-	2021-22

प्रस्तुत प्राक्कलन विभागीय पत्रांक- मु.अ. 4-42754215 दिनांक-22.10.21 के आदेशानुसार पथ में कराये गये यातायात पुर्नस्थापना कार्य के निमित्त तैयार की गयी है।

यह प्राक्कलन शिवनारायण चौधरी डे बर से नेउरी कार्य के लिए तैयार की गई है। वर्ष 2021 में आयी प्रलयंकार बाढ़/अतिवृष्टि के कारण पथ कई जगहो पर क्षतिग्रस्त हो गया था। जिसके कारण आवागमन अवरुद्ध हो गई थी जिसमें अस्थाई यातायात पुर्नस्थापन कार्य किया गया है।

प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू अनुसूचित दर पर, जो संवेदक लाभांश को छोड़कर था, उसे प्रावधान करते हुए तैयार किया गया है।

अतः किये गये कार्यों के भुगतान हेतु प्राक्कलन की प्रशासनिक स्वीकृति अपेक्षित है।


कनीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रशाखा बेनीपुर


सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमण्डल बेनीपुर


कार्यपालक अभियंता
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल बेनीपुर।

Abstract of cost.

Name of Road:- SHIVNARAYAN CHOUDHARY KE GHAR to NEURI TOLA

o	Particulars of Item	Quantity (In M ³)	Rate	Amount
	Providing and laying Filling in ditches with brick bats including loading, unloading and light ramming all complete job. As per specification & Direction of E/I	131.65	2004.96	263953
			Total =	263953
	Add 12% GST		=	31674
	1% L.C		=	2640
	(S.Fee)- B/Bat(131.65*1032* 0.1)=13586		=	13586
			Grand Total=	311853

Say Rupees 311850=00

[Signature]
J.E

RWD, Benipur

[Signature]
A.E

RWD, Benipur

[Signature]
E.E

RWD, Benipur

Technically sanctioned for RS 3,11,850=00 (Rupees Three Lacs eleven Thousand Eight Hundred Fifty) only

[Signature]
Superintending Engineer
RWD, Works Circle, Darbhanga

Flood Estimate

Name of Road:- SHIVNARAYAN CHOUDHARY KE GHAR to NEURI TOLA

Item No.1	Providing and laying Filling in ditches with brick bats including loading, unloading and light ramming all complete job. As per specification & Direction of E/I				
	Chainage (In M)	Length (In M)	Average Width (In M)	Average Height (In M)	Qty in cum
	0m to 100m	43.00	$(3.5+4+4.5)/3$	$(0.3+0.8+1)/3$	120.40
	2nd km	2*6	$(1+1.5)/2$	$(0.6+0.9)/2$	11.25
			Total =		131.65


J.E.
RWD, Benipur


A.E.
RWD, Benipur


E.E.
RWD, Benipur

checked and Verified


13-12-2024
AZ

335
13/12/24
CE

Inspection Report of Flood Damage work

Name of PIUs:- RWD Works Division, Benipur

Name of Block/Road:- Benipur / Shiv Narayan Chaudhari ke ghar se Neuri Tola

A. For Road

1. Damage Location Chainage:- ch. 0.00, ch. 1.000 to ch. 2.000m
2. Damage Length :- 55m
3. Nature of Damage :- Road crust & flank
4. Details of Restoration Works
 - i. Material being used in Restoration works:- Brick ball
 - ii. Equipment's / Tools being used in Restoration works:- tractor
 - iii. Procedure taken up in Restoration works:- manually
 - iv. Restored Length:- 55m

B. For Bridge

1. Damage Location Chainage:-
2. Damage Length :-
3. Nature of Damage :-
4. Details of Restoration Works
 - i. Material being used in Restoration works:-
 - ii. Equipment's / Tools being used in Restoration works:-
 - iii. Procedure taken up in Restoration works:-
 - iv. Restored Length:-

N/A

work found satisfactory.

Signature of JE/AE/EE

Signature
(Name of Inspection)