

कार्यपालक अभियंता का कार्यालय

ग्रामीण कार्य विभाग, कार्य प्रमण्डल, मंझौल-बखरी।

पत्रांक 1471/3140

दिनांक 7/12/21

प्रेषक,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, मंझौल-बखरी।

सेवा में,

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, रोसड़ा।

विषय: जाँच प्रतिवेदन भेजने के संबंध में।

प्रसंग:- अधीक्षण अभियंता, ग्रामीण कार्य विभाग, कार्य अंचल, समस्तीपुर के पत्रांक 1927 दिनांक 16.11.2021

महाशय,

उपरोक्त विषयक संदर्भ में कहना है कि प्रासंगिक पत्र के आलोक में योजनाओं का मेरे एवं मेरे द्वारा गठित टीम के द्वारा आपके प्रमण्डल के अधीन F.D.R अन्तर्गत कराये गये पथों का जाँच किया गया। 86 योजनाओं का जाँच प्रतिवेदन इस पत्र के साथ संलग्न कर अग्रेतर कार्रवाई करने हेतु भेजी जा रही है। जिसका लगभग अनुमानित राशि योजना के नाम के सामने के अंकित है।

विश्वासभाजन



कार्यपालक अभियंता

ग्रामीण कार्य विभाग,

कार्य प्रमण्डल, मंझौल-बखरी।

Inspection Report for Flood Damage Work

Date:- 7/12/21

1. Name of PIUs- Executive Engineer, R.W.D, Works , Division, :- Rosera

2. Name of Block:- Singhia

3. Name of Road/Bridge- MDR Bharraria.

A. For Road.

1. Damage Location/Chainage

$\frac{25.85258657}{86.2032846}$, $\frac{25.85258679}{86.20329143}$, $\frac{25.85255428}{86.20326037}$

2. Damage Length

:- 0.400 Km

3. Nature of Damage

:- Due to flood crust and flank damaged

4. Details of Restoration Works

:- Brick Bat filling

i. Material being used in Restoration Works :

ii. Equipments/Tools being used in Restoration Works:

iii. Procedure taken up in Restoration Works :

iv. Restored Length : 0.400 km

B. For Bridge

1. Damage Location / Chainage :

2. Damage Length :

3. Nature of Damage :

4. Details of Restoration Works :

i. Material being used in Restoration Works :

ii. Equipments/Tools being used in Restoration works :

iii. Procedure taken up in Restoration Works :


iv. Restored Length :

work done found satisfactory


J.E.


A.E.


Executive Engineer,
R.W.D Works Division,
ROSERA


Executive Engineer
RWD Works Division
(Name of Inspector)
Manjhar Bakhari

ग्रामीण कार्य विभाग, कार्य प्रमंडल-रोसाडा अंतर्गत FDR के तहत मरम्मत/ Motorable कराए गये
पथों की जॉब की सूची।

38


प्रखंड	पथ का नाम	कराए गए कार्य	मरम्मत कराए जाने हेतु पथ की लंबाई किलोमीटर	मरम्मत कराए जाने हेतु पथ की राशी	अभियुक्ती	
Singhia	MDR-Bhararia	Brick Bat Filling	0.400	9.47	पूर्ण	2769
Singhia	PWD Path To Gadua	Brick Bat Filling	0.150	2.43	पूर्ण	2772
Singhia	L070-T02 Bhairson To Bisaharia	Brick Bat Filling	0.900	6.95	पूर्ण	2756
Singhia	Singhia To Kalali Chowk Path	Brick Bat Filling	0.2	3.82	पूर्ण	2767
Singhia	L045-T01 To Behat (VR45)	Brick Bat Filling	0.3	8.73	पूर्ण	2747
Singhia	T02 (Sonsa) To Parhat	Brick Bat Filling	0.4	4.91	पूर्ण	2759
Singhia	L021-T01 to Jamua Mohidinpur	Brick Bat Filling	0.3	16.40	पूर्ण	2757
Singhia	Improvement of road From Bharhar to Kanjara (Mhadalit Tola) To Pansalla mian road via Bangthaiya	Brick Bat Filling	3	13.93	पूर्ण	2766
Singhia	Singhia Mahe Road To Petfora	Brick Bat Filling	2.275	3.45	पूर्ण	2752
Singhia	L045-T02 Sonsa Chowk To Basua	Brick Bat Filling	2.5	6.60	पूर्ण	2748
Singhia	Bara Chowk to Sonmani Via Laxminia	Brick Bat Filling	0.9	6.99	पूर्ण	2744
Singhia	SH56 to Bharihar Tola 2835	Brick Bat Filling	0.15	6.04	पूर्ण	2765
Singhia	MMS (Bharahar Pansalla) Path To Laxminia	Brick Bat Filling	0.25	5.83	पूर्ण	2765
Singhia	Quotahar (T02) Mungelia 2843	Brick Bat Filling	0.4	6.31	पूर्ण	2754
Singhia	Improvement of Road from Bachhuliya to Akopur-Harpur-pabra- Iind Phase	Brick Bat Filling	0.35	3.80	पूर्ण	2755
Singhia	L073-T02 Navtoliya	Brick Bat Filling	0.4	5.21	पूर्ण	2753
Singhia	T03 (Jilhaul) to Kichaka Musahari Tola ward no. 01	Brick Bat Filling	0.7	5.49	पूर्ण	2750
Singhia	L081-T01 to Dhakjari (VR81)	Brick Bat Filling	0.2	2.75	पूर्ण	2749
Singhia	T01 Manu - Bela	Brick Bat Filling	0.3	19.79	पूर्ण	2749
Singhia	L056-T02 To Jibudihuli (VR56)	Brick Bat Filling	0.3	5.85	पूर्ण	2749
Singhia	Bharhar to Bhairson 2751	Brick Bat Filling	0.8	6.31	पूर्ण	2749
Singhia	Salehpur Path to Museur 2764	Brick Bat Filling	0.375	4.13	पूर्ण	2749
Singhia	T02 Diha To Murli Ward No 06 2762	Brick Bat Filling	0.25	6.76	पूर्ण	2749
Singhia	Salepur - Tenua Road 2760	Brick Bat Filling	0.3	4.87	पूर्ण	2749
Singhia	T02 Basopatti 2768	Brick Bat Filling	0.45	7.95	पूर्ण	2749
Singhia	T01 - Aurahi Bhira 2745	Brick Bat Filling	0.25	4.97	पूर्ण	2749
Singhia	Diha (Tenua) To Bharison (Bharhar) 2761	Brick Bat Filling	0.3	3.49	पूर्ण	2749
Singhia	Haripur Bela Path 2770	Brick Bat Filling	0.6	5.46	पूर्ण	2749
Singhia	L030-L025 to Rampura (VR30) 2758	Brick Bat Filling	0.9	6.24	पूर्ण	2749

[Signature]
कार्यपालक अभियंता

ग्रामीण कार्य विभाग, कार्य प्रमंडल-गडौल-बखली

82

43



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

GOVT. OF BIHAR

FDR

YEAR 2021-22

Detailed Project Report

Division : Rosera

District :	Samastipur	Block :	Singhia
------------	------------	---------	---------

Name of
Road :

MDR - Bhararia

SUBMITTED BY
THE EXECUTIVE ENGINEER
WORKS DIVISION, ROSERA

तकनीकी प्रतिवेदन

पथ का नाम:— MDR – Bhararia

प्राक्कलित राशि— ^{9.47}13.53 लाख

उपर्युक्त वर्णित पथ विगत बाढ़/बरसात वर्ष 2021–2022 से काफी छतिग्रस्त हो गए थे जिससे आवागमन काफी कठीनाईयुक्त हो गया था तथा दुर्घटनाए होती रहती थी जिसके कारण इस पथ को Brick bats आदि से भर कर मोटेरेबल किया गया है। पथ पर आवागमन जारी है।




Junior Engineer

RWD (w)Section , Singhia



Assistant Engineer

RWD (w)Sub Division , Singhia



Executive Engineer
RWD (w)

Division,Rosera

FDR

Detailed Estimate for

MDR - Bhararia

Block : Singhia
District : Samastipur

ABSTRACT OF COST FOR ROAD

Sl No	Item of Work	Amount (In Rs)	
		As per Estimate	
1	Total Cost for Pavement Works		838209.70
	Total Cost of Project :	Rs -	838209.70
	Total Cost Including (GST + L.Cess) 13% :	Rs -	108967.26
	Total :	Rs -	947176.96
	Say (Lakh) :	Rs -	9.47

[Signature]
22/10/21

Junior Engineer
RWD (W) Section, Singhia

[Signature]
22/10/21

Asstt. Engineer
RWD (W) S. Div. Singhia

[Signature]
22/10/21

Executive Engineer
RWD (W) Div, Rosera

Sanctioned Rs 9,47,000 = 9.47 say nine lakh forty seven thousand only including further charge 12%.

82

[Signature]
10.12.21

वरीष्ठक अधिकारी
राजीव गांधी विभाग
आई बंगला, दरभंगा

FDR
MDR - Bhararia

District : Samastipur
Block : Singhia

Total Length (Km): 0.400

SI No	Reference To Mord Spec.	Brief Description of Item	No	Measurements			Unit	Quantity	Rate (Rs)	Amount (Rs)	
				L (m)	B (m)	D (m)					
1	401	Supply filling brick bat compacted manually	3	7.00	2.75	0.35	cum	20.21			
			5	20.00	4.50	0.30	cum	135.00			
			2	35.00	5.00	0.65	cum	227.50			
			4	25.00	1.75	0.25	cum	43.75			
			2	12.50	1.75	0.15	cum	6.56			
			2	6.25	3.50	0.25	cum	10.94			
			2	2.00	2.50	0.25	cum	2.50			
			1	8.00	2.50	0.35	cum	7.00			
			1	4.00	2.50	0.30	cum	3.00			
			1	16.00	1.25	0.35	cum	7.00			
			1	12.80	1.25	0.175	cum	2.80			
			1	9.00	3.75	0.30	cum	10.13			
			1	4.50	3.75	0.25	cum	4.22			
			2	4.50	1.75	0.35	cum	5.51			
		Total Quantity :					cum	486.12	1724.29	838209.70	
				Total Cost of Pavement in Rs :						8.38	

27/10/21

27/10/21

27/10/21

Junior Engineer
RWD (W) Section, Singhia

Asstt. Engineer
RWD (W) S. Div. Singhia

Executive Engineer
RWD (W) Div, Rosera