

**GENERAL ABSTRACT OF COST FOR EMERGENT REPAIR FOR RESTORATION
OF TRAFFIC**

NAME OF ROAD : HATA DURGAWATI ROAD TO SARIYAV BIND TOLI

DISTRICT KAIMUR (BHABHUA)


BLOCK DURGAWATI

DIVISION MOHANIA


LENGTH OF ROAD (in Km) 0.010

CD STRUCTURES

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
PART-A	RESTORATION COST	
1	Brick Bat Filling	7.670
2	Drainage	0.000
3	Information Board	0.050
	SUB TOTAL OF Restoration	9.287
	LABOUR CESS 1% of cost	0.093
	GST 12 % of cost	1.114
	SEIGNIORAGE FEE @ 10 % on Minor Mines	0.523
	TOTAL OF Restoration	11.017
Part B	Conigency 1 % on Restoration cost	0.110
	TOTAL COST OF PROJECT IN LACS =	11.128


20/10/24
JE
RWD

AE
RWD


25/10/24
EE
RWD

NAME OF Road:- HATA DURGAWATI ROAD TO SARIYAV BIND TOLI

SL No.	SDB SL NO	MORD Ref.No	Description	Unit	NOS	LENGTH	WIDTH	HEIGHT	QUANTITY	RATE	AMOUNT (in Rs.)
1			Brick BAT Filling								
			Emergent Repair by Filling Brick Bats in Flood damaged Stretch of the Road for making it Motorableas per S/D of E/I								
			Road	cum	1	9.00	7.500 (av)	3.000 (av)	202.50		
				cum	1	12.00	6.500 (av)	1.000 (av)	78.00		
				cum	1	12.00	6.500 (av)	1.500 (av)	117.00		
			Net Qty						397.50	1,585.09	6,30,073.00
2	4.1	401	Granular Sub-base with Well Graded Material (Table 400.1)								
		(ii)	For Grading I Material								
			Construction of granular sub-base by providing well graded material, spreading in uniform layers with motor grader on prepared surface, mixing by mix in place method with rotavator at OMC, and compacting with smooth wheel roller to achieve the desired density, complete as per Technical Specification Clause 401.								
			For DAMAGED Road	Cum	1	15.00	3.75	0.100	5.63		
			For DAMAGED Road	Cum	1	75.00	3.75	0.100	28.13		
			Net GSB Qty						33.75	4,057.95	1,36,956.00
3	4.7	405	WBM Grading 3 (By Mechanical Means)								
	(3-B)		Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specification including spreading in uniform thickness, hand packing, rolling with smooth wheel roller 80-100 kN in stages to proper grade and camber, applying and brooming, stone screening to fill-up the interstices of coarse aggregate, watering and compacting to the required density Grading 3 as per Technical Specification Clause 405.								
			For DAMAGED Road	Cum	1	15.00	3.75	0.075	4.22		
			For DAMAGED Road	Cum	1	75.00	3.75	0.075	21.09		
			Net WBM -3 Qty	cum					25.31	5,060.61	1,28,097.00
										TOTAL =	8,95,126.00

Inspection Report for Flood Damage Work

Date

1 Name of PIUs

Executive Engineer, RWD, Work Div Mohania

2 Name of Block/Road

Block - Dargawati
Road Name - Hatha Dargawati Road
Sarajan Bin of TSI 9.

A For Road

1 Damage Location/Chainage

0.300 to 0.375 & 0.400 to 0.415 km

2 Damage Length

75m + 15m = 90m

3 Nature of Damage

crack cutting

4 Details of Restoration Works

i Material being used in Restoration Works

Brick Bat GSB Grt, 1534 Gt
2 Hima pip 1000 kg

ii Equipments/Tools being used in Restoration Works

Tratto, TCB

iii Procedure Taken up in Restoration Works

Depot material

iv Restored Length

90m

B For Bridge

NA

1 Damage Location/Chainage

2 Damage Length

3 Nature of Damage

4 Details of Restoration Works

i Material being used in Restoration Works

NA

ii Equipments/Tools being used in Restoration Works

iii Procedure Taken up in Restoration Works

iv Restored Length

Satisfactory

Signature of JE/AE/EE

20/11/24
JE

20/11/21
AE

20/11/24
Executive Engineer
Rural Works Department
Work Division, Mohania

20/11/24
Signature
Executive Engineer
Rural Works Department
Works Division Bhabhua

GENERAL ABSTRACT OF COST FOR EMERGENT REPAIR FOR RESTORATION OF TRAFFIC

NAME OF ROAD : HATA DURGAWATI ROAD TO SARIYAV BIND TOJI
DISTRICT KAIMUR (BHABHUA)
BLOCK DURGAWATI
DIVISION MOHANIA
LENGTH OF ROAD (in Km) 0.010
CD STRUCTURES

Sl. No.	DESCRIPTION	AMOUNT (LAKHS)
PART-A	RESTORATION COST	
1	Brick Bat Filling	7.618
2	Drainage	0.000
3	Information Board	0.050
	SUB TOTAL OF Restoration	9.234
	LABOUR CESS 1% of cost	0.092
	GST 12 % of cost	1.108
	SEIGNIORAGE FEE @ 10 % on Minor Mines	0.519
	TOTAL OF Restoration	10.954
Part B	Contingency 1 % on Restoration cost	0.110
	TOTAL COST OF PROJECT IN LACS =	11.064

JE
RWD

AE
RWD

EE
Executive Engineer
R.W.D Work Division Moh

Technically Cautioned for Rs. 11.064 Lakh
(Rupees eleven lakh six thousand four hundred)
only.

अधीक्षण अभियंता
ग्रामीण कार्य विभाग
कार्य अंचल, सासाराम