

⑥

# **RURAL WORKS DEPARTMENT**

## **GOVT OF BIHAR**



NAME OF WORKS :-

Nirmali, Hariyahi Mahua to Nirmali Ghera  
Bandh

BLOCK :-

NIRMALI

**FDR**

Rs. 157440.00

YEAR (2021-22)

R.W.D., WORKS CIRCLE, MADHEPURA

R.W.D., WORKS DIVISION, SUPAUL

### प्रतिवेदन

पथ का नाम :- Nirmali, Hariyahi Mahua to Nirmali Ghera Bandh

कार्य का नाम :- Nirmali, Hariyahi Mahua to Nirmali Ghera Bandh

में बाढ़ से क्षतिग्रस्त भाग में यातायात चालू करने का कार्य।

संलग्न प्राक्कलन जूलाई 2021 एवं अक्टूबर 2021 को प्रखण्ड में आयी भीषण बाढ़ से क्षतिग्रस्त Nirmali, Hariyahi, Mahua to Nirmali Ghera Bandh.

में बाढ़ क्षतिग्रस्त मरम्मत मद से यातायात चालू करने हेतु तैयार किया गया है जिसकी प्राक्कलित लागत Rs. 1,57,440 = 00 है।

उक्त पथ का निर्माण MMGSY OLD योजनान्तर्गत हुआ है एवं योजना अनुरक्षण अवधि में गरीब

पथ के कटे (क्षतिग्रस्त) भाग में आवश्यकता अनुसार Hume Pipe, Bamboo, लोकल बालू एवं Brick Bats देने के बाद यातायात चालू कराया गया है। पथ के विभिन्न हिस्से में कराये गये कार्य का विवरणी स्पष्ट रूप से प्राक्कलन में दर्शाया गया है।

प्राक्कलन मदों का दर वर्तमान अनुसूचित दर के अनुरूप है।

  
22.11.21

कनीय अभियंता,  
ग्रामीण कार्य विभाग,  
कार्य प्रशाखा, नर्मली।

  
22.11.21

सहायक अभियंता,  
ग्रामीण कार्य विभाग,  
कार्य अवर प्रमण्डल, नर्मली

  
22.11.21


कार्यपालक अभियंता,  
ग्रामीण कार्य विभाग,  
कार्य प्रमण्डल, सुपौल।


FDR RESTORATION WORK  
YEAR (2020-21)

GENERAL ABSTRACT OF COST

|              |                                                |          |        |
|--------------|------------------------------------------------|----------|--------|
| BLOCK :-     | NIRMALI                                        | DISTRICT | SUPAUL |
| Name of Road | Nirmali, Hariyahi Mahua to Nirmali Ghera Bandh |          |        |

| S.No. | Description of Items      |     | Amounts   |
|-------|---------------------------|-----|-----------|
| A     | TOTAL COST OF RESTORATION | Rs. | 133186.23 |
| B     | Seigniorage Fees          | Rs. | 6940.00   |
| C     | Add @12% GST              | Rs. | 15982.35  |
| D     | Add @1% Labour Cess       | Rs. | 1331.86   |
|       | Total (A+B+C+D)           | Rs. | 157440.44 |
|       | Say                       | Rs. | 157440.00 |

 22.11.21  
J.E.  
RWD Supaul


 22.11.21  
A.E.  
RWD Supaul


  
E.E.  
RWD Works Division Supaul

T.S No. - 01 dt - 19.4.2022

पत्रांक :- मु. अ. - 4 (मु.) विविध (कार्य) 23-291 / 2019-4849 दिनांक-07/12/2021

Technically sanctioned for ₹ 1,57,440.00/- (i.e. Rupees one lakh fifty seven thousand four hundred forty only).

 19/04/2022  
Estimating Officer  
Rural Work Department  
Work Circle, Madhepura

 19/04/22  
Superintending Engineer  
Rural Works Department  
Works Circle, Madhepura



## Inspection Report for Flood Damage Work

Date : 22.11.21

1. Name of PIUs :- E.E. RWD, Works Division Supaul.
2. Name of Block/Road :- Nirmali / Nirmali, Hariyahi, Mahua to Nirmali Chhara Bandh.

### A. For Road

1. Damage Location/Chainage : 100m, 275m, 380m, 400m, 600m, 800m, 900m.
2. Damage Length : 161.8m
3. Nature of Damage : Due to flood
4. Details of Restoration Works :
  - i. Material being used in Restoration work : Brick Bats, CC Bag with Local sand.
  - ii. Equipment/Tools being used in Restoration work : Tractor, Roller
  - iii. Procedure taken up in Restoration work : Filling
  - iv. Restored Length : 161.8m

### B. For Bridge

5. Damage Location/Chainage :
6. Damage Length :
7. Nature of Damage :
8. Details of Restoration Works :
  - i. Material being used in Restoration work :
  - ii. Equipment/Tools being used in Restoration work :
  - iii. Procedure taken up in Restoration work :
  - iv. Restored Length :

'Satisfactory'

*[Signature]*  
22.11.21

Signature of JE/AE/EE

*[Signature]*  
22/11/21

*[Signature]*  
22/11/21

*[Signature]*  
**Executive Eng**  
Signature  
Road Works Department  
(Name of Inspector)