

प्रतिवेदन

पथ का नाम:- Mashia Kushanagar

प्रस्तुत प्राक्कलन कार्य प्रमंडल, सीतामढ़ी अंतर्गत सोनबरसा प्रखंड में 2021 के जुलाई माह में आई भीषण बाढ़ से क्षतिग्रस्त पथ में मरम्मत मद से यातायात चालू करने हेतु योजना शीर्ष FDR के अंतर्गत तैयार किया गया है। जिसकी प्राक्कलित राशि Rs. 3857000.00 है। पथ के क्षतिग्रस्त भाग में आवश्यकतानुसार Brick Bats, Rabbish/ Local Sand भरकर यातायात चालू करने का प्रावधान किया गया है।

प्रस्तुत प्राक्कलन में पथ के अंतर्गत सूचित प्रावधानों एवं वर्तमान अनुसूचित दर के अनुसार कार्यहित एवं स्थलीय आवश्यकता के अनुरूप तैयार किया गया है।


12/11/22

कनीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, सीतामढ़ी।


12/11/22

सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, सीतामढ़ी।


12/11/22

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल, सीतामढ़ी।

कद/अतिरिक्ति से अतिग्रस्त भग्नों का अन्तर्गत मंडलीय बीच प्रतिवेदन के अन्त

निरीक्षक अधिकारी का नाम:- योगेश चन्द्र मिश्रा

निरीक्षण की तिथि:-

3 पथ का नाम:- Machha - 4491, Nagpur

4 पथ की लंबाई:- 0.913 Km

5 कार्य प्रमंडल का नाम:- सीतानदी

6 प्रमंडल का नाम:- सौनखला

7 पथ की स्थिति:- खराब

8 पथ अनुक्रमण अवधि में है:- हाँ

9 अतिग्रस्त भाग की लंबाई:- 89 मीटर

10 अतिग्रस्त भाग में कराये गये कार्य का विवरण:-

(लंबाई X चौड़ाई X गहराई)

कार्यस्थल पर नापी की जाँच की गई। जाँचकर्ता के पृष्ठ संख्या- 03 पर अंकित

नापी को सही पाया गया।

Brick Bats- 188.56 m³

Rabbish- 47.14 m³

11 Temporary Restoration में किन्तु-किन्तु

सामानियों का उपयोग किया गया है।

उसका विवरण :- Brick Bats, Rabbish

12 अभ्युक्ति:-

Satisfactory

निरीक्षक अधिकारी का हस्ताक्षर

पदनाम:- कार्यवाहक अधीक्षक, प्राथमिक कार्य विभाग

कार्यप्रदेश, बेतवा

DETAILED ESTIMATE FOR F.D.R.

General Abstract of Cost

Name of Road : Marhia -Kushanagary
Length of Road : 0.904 KM
Block : Sonbaraa
DISTRICT : SITAMARHI

S.No	Particulars	Total Cost (in Lakh)
	Total Cost for Motorable Roads	385700.00
	Total Cost of Road Repair	385700.00
	Say	385700.00


12/11/2021
JE


12/11/21
AE


12-11-2021
EE

अभिप्रेत-प्रमुख सामान्य कार्य विभाग के पत्र-4549
दिनांक-07/12/2021 के आदेशानुसार प्रशासनिक
संबंधी के प्रस्ताव के अंतर्गत सामान्य संबंधी प्रमाण
की जा रही है। प्रस्तावित संबंधी प्रमाण होने के कारण
युक्त संबंधी संबंधी प्रमाण की अंतर्गत अंतर्गत सामान्य
संबंधी प्रमाण 385700.00. (Rupees Three Lax Eighty
को प्रमाण की जा रही है।

Five thousand Seven hundred only)


Superintending Engineer
Rural Works Department
Works Circle, Sitamarhi

Schedule of Quantity

Of Work : Marhla -Kushanagary

Block : Sombarsa

Sl. No.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	Sand Filling in Foundation Trenches as per Drawing & Technical Specification	0.00	Cum	457.21	0.00
2	Providing and laying of Brick bat obtained from chimney with mechanical means with all spreading, grading to required slope and compacted at OMC to achieve required density with all complete as per the direction of engineer in charge.	235.70			0.00
	Less 20% for Voids	-47.14			
		188.56	Cum	1827.25	344546.08
3	Single bamboo palasiding / walling of whole 2nd class bamboo (Jati or Bethua) 75mm dia and closely packed & driven including fitting fixing with half bamboo kamis horizontally in three rows with cane or tying with wire complete and struts 1.5 m apart longitudinally and providing brush wood as per drawing and technical specifications Clause 1302.5	0.00	Each	140.40	0.00
4	Providing, laying and placing empty cement bag filled with local sand including stitching with sutali etc. ----- do ----- do ----- all complete job as per specification and direction of E/I (Including Royalty and all Taxes)	0.00	no	20.41	0.00
5	Providing and Laying 1000 mm Reinforced Cement Concrete Pipe NP3 as per design in Single Row pipe	0.00	m	3740.68	0.00
6	Providing and Laying 600 mm Reinforced Cement Concrete Pipe NP3 as per design in Single Row pipe	0.00	m	3091.44	0.00
7	Providing Quarry Material Rabbish for filling the voids in bricks bats -----do----- all complete job as per specification and direction of E/I.				
	Taking 20% of Brick Qty for Rabbish	47.14	Cum	873.01	41153.60

Total 385699.68
Say 385700.00


12/11/22
JE


12/11/22
AE


12/11/22
EE

Details of Measurement of ditches filled by brick bats and rabbish

Name Of Work : Marhla -Kushanagary

Record ENTRY

L	W	H	VOLUME
24 00	3 75	0 80	72 00
65 00	3 75+4 00/2	0 65	163 70
Total (in Cum)			235 70

12/1/032
J.R

12/10/122
AE

12-01-2012
UDS