

कार्यपालक अभियन्ता का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमण्डल, हथुआ।

पत्रांक— **244**

दिनांक— **07-03-2022**

प्रेषक,

कार्यपालक अभियन्ता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, हथुआ।

सेवा में,

सचिव,
बिहार, ग्रामीण पथ विकास अभिरण,
बिहार, पटना।

विषय :— बिहार ग्रामीण पथ नई अनुरक्षण नीति-2018 के तहत क्रियान्वित पथ मरम्मत कार्य हेतु राशि उपलब्ध कराने के संबंध में।


महाशय,

उपरोक्त विषयक बिहार ग्रामीण पथ नई अनुरक्षण नीति-2018 के तहत क्रियान्वित पथ मरम्मत कार्य हेतु राशि की अधियाचना विहित प्रपत्र में की जा रही है।

अतः भवदीय से अनुरोध है कि कॉलम 18 में अंकित राशि उपलब्ध कराने की कृपा की जाय।

अनु०— यथोक्त।

विश्वासभाजन,


कार्यपालक अभियन्ता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, हथुआ।

Requisition Format for Scheme Head- MR (3054) under Bihar Rural Road Maintenance Policy- 2018 (Initial Rectification and Surface Renewal)

Name of Works Division :- Rural Works Department, Works Division Hathua.																		
SI No.	Package No.	Name of Road	Project ID as Per MIS	Administrative Approval (AA) Letter No & Date.	Administrative Approval (AA)		Agreement Amount (in Lakh)		Agreement No & Date	Date & Completion as per Agreement.	Actual Date of Completion	Value of RI (in MM/KM)	Thickness of Bitumen layer (in mm)	Value of Bitumen Content in Percentage	Previous Total Amount Allotted (in Lakh)	Up-to date expenditure as per MIS (in Lakh)	Requisition against work done. (in Lakh)	Remarks
					Length (in Lakh)	Amount (in Lakh)	Initial Rectification with surface Renewal (in Lakh)	5 Year Routine Maintenance (in Lakh)										
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19
1	MR-N-19-20/Hathua-17	Laxmipuri to Persauni.	NEA22000613	Letter No-1843 & Dt-17.07.2019	3.950	154.331	97.25047	31.86501	39/M.B.D/2020-21	20.05.2021	-	Good	25	5.00	0.00000	0.00000	96.84265	Completed.
					3.950	154.331	97.25047	31.86501	21.08.2020								96.84265	

प्रमाणित किया जाता है कि पथ में कराये गये कार्य के सभी अवयववार 100 प्रतिशत कार्य का दर्ज मापी का सत्यापन संबंधित कनीय अभियंता 50 प्रतिशत मापी का सत्यापन संबंधित सहायक अभियंता एवं 10 प्रतिशत मापी का सत्यापन अधोहस्ताक्षरी यथा कार्यपालक अभियंता द्वारा किया जा चुका है। कराया गया कार्य मानक एवं विशिष्टियों के अनुरूप है।

JE
R.W.D Works Division, Hathua.

AE
R.W.D Works Division, Hathua.

DAO
R.W.D Works Division, Hathua.

Executive Engineer
R.W.D Works Division, Hathua.

FORM GFR 19 - A

(See Government of India's Decision (1) below Rule - 150)

Form utilisation Certificate up to the month of Up to 31.12.2021

MR-3054 (New Maintenance Policy-2018)

RWD Works Division - HATHUA

1	Head	Amount Received		Expenditure		Balance	
		IN A/C-	0.00	IN A/C-	0.00	IN A/C-	0.00
		By CFMS-	547417407.00	By CFMS-	545829346.00	By CFMS-	1588061.00
		Total-	547417407.00	Total-	545829346.00	Total-	1588061.00
	MR-3054 (New Maintenance Policy-2018)					Certified that sum of Rs 5458.29 Lac has been utilized for the purpose of MR-3054 (New Maintenance Policy-2018) Schemes as given in the margin for which it was sanctioned and that the balance of Rs 15.88 Lac Lacs remaining utilized at the end of the period under.	

2. Certified that I have satisfyd my self that the conditions on which the grants-in aid was sanctioned have been duly

Kind of Checks exercised :-

- (i) Works have been supervised by Executive Engineer/Superintending Engineer.
- (ii) Periodical inspection has been conducted by Executive Engineer/Superintending Engineer.
- (iii) Construction material have been tested.
- (iv) Measurements have been recorded in the MBs and test check conducted by the Assistant Engineer/Executive Engineer.
- (v) All other codal formalities have been observed.

3. Physical Progress achieved :-

- (i) Construction of Road Works.
- (ii) Construction of CD Works



D.A.O

Rural Works Department
Works Division Hathua



Executive Engineer
Rural Works Department
Works Division Hathua

Name of work : Laxmiput - Parsauri	
Name of customer : ANANDMISHRA CONSTRUCTION PRIVATE LIMITED	
(R) Rural Road	
Good	Average
< 4000	4001 - 5000
	Poor
	> 5000

Date	Time	Test No	Distance(m)	Total Distance(m)	BUMI(cm)	Speed(Km/Hr)	Ultimate(Km)	Corrected UI (mm/Km)	IRI	Status	Latitude	Direction	Longitude	Direction	Remarks
06/03/22	17:09:15	1	100	100	26.0 cm	7.1 Km/Hr	2600.0 mm/Km	2679	3.64	Good	26.3639536	N	84.3331537	E	Normal
06/03/22	17:09:37	1	100	200	28.0 cm	16.6 Km/Hr	2800.0 mm/Km	2866	3.87	Good	26.4639120	N	83.9506143	E	Normal
06/03/22	17:09:55	1	100	300	31.0 cm	20.4 Km/Hr	3100.0 mm/Km	3147	4.2	Good	26.4637575	N	83.9515467	E	Normal
06/03/22	17:10:12	1	100	400	29.0 cm	20.7 Km/Hr	2900.0 mm/Km	2960	3.98	Good	26.4636316	N	83.9530421	E	Normal
06/03/22	17:10:31	1	100	500	30.0 cm	19.2 Km/Hr	3000.0 mm/Km	3053	4.09	Good	26.4636316	N	83.9530421	E	Normal
06/03/22	17:10:48	1	100	600	32.0 cm	21.3 Km/Hr	3200.0 mm/Km	3241	4.32	Good	26.4636316	N	83.9530421	E	Normal
06/03/22	17:11:04	1	100	700	29.0 cm	21.6 Km/Hr	2900.0 mm/Km	2960	3.98	Good	26.4636316	N	83.9530421	E	Normal
06/03/22	17:11:20	1	100	800	30.0 cm	22.7 Km/Hr	3000.0 mm/Km	3053	4.09	Good	26.464068	N	83.9522486	E	Normal
06/03/22	17:11:37	1	100	900	34.0 cm	21.8 Km/Hr	3400.0 mm/Km	3428	4.54	Good	26.4666433	N	83.9515467	E	Normal
06/03/22	17:11:55	1	100	1000	31.0 cm	19.2 Km/Hr	3100.0 mm/Km	3147	4.2	Good	26.4673033	N	83.9508143	E	Normal
06/03/22	17:12:18	1	100	1100	30.0 cm	15.7 Km/Hr	3000.0 mm/Km	3053	4.09	Good	26.4678755	N	83.9502268	E	Normal
06/03/22	17:12:39	1	100	1200	32.0 cm	17.1 Km/Hr	3200.0 mm/Km	3241	4.32	Good	26.4685602	N	83.9496623	E	Normal
06/03/22	17:12:54	1	100	1300	34.0 cm	23.9 Km/Hr	3400.0 mm/Km	3428	4.54	Good	26.4693785	N	83.9496882	E	Normal
06/03/22	17:13:09	1	100	1400	36.0 cm	23.6 Km/Hr	3600.0 mm/Km	3615	4.76	Good	26.4701757	N	83.9500971	E	Normal
06/03/22	17:13:24	1	100	1500	32.0 cm	25.2 Km/Hr	3200.0 mm/Km	3241	4.32	Good	26.4711809	N	83.9504405	E	Normal
06/03/22	17:13:38	1	100	1600	33.0 cm	25.2 Km/Hr	3300.0 mm/Km	3334	4.43	Good	26.4719686	N	83.9506846	E	Normal
06/03/22	17:13:53	1	100	1700	30.0 cm	24.5 Km/Hr	3000.0 mm/Km	3053	4.09	Good	26.4730482	N	83.9510127	E	Normal
06/03/22	17:14:11	1	100	1800	27.0 cm	19.0 Km/Hr	2700.0 mm/Km	2773	3.75	Good	26.4737310	N	83.9505244	E	Normal
06/03/22	17:14:24	1	100	1900	28.0 cm	27.3 Km/Hr	2800.0 mm/Km	2866	3.87	Good	26.4745131	N	83.9507304	E	Normal
06/03/22	17:14:36	1	100	2000	32.0 cm	29.7 Km/Hr	3200.0 mm/Km	3241	4.32	Good	26.4750090	N	83.9508330	E	Normal
06/03/22	17:14:48	1	100	2100	36.0 cm	30.9 Km/Hr	3600.0 mm/Km	3615	4.76	Good	26.4759893	N	83.9511881	E	Normal

Prasanna
4.3.5.E

07/03/22

कार्यपालक अभियंता,

ग्रामीण कार्य विभाग,

कार्य प्रमुख, हरद्वार (गोपालगंज)

Name of work : Laxmiput - Parsauni

Name of customer : ANANDMISHRA CONSTRUCTION PRIVATE LIMITED

(R)Rural Road

Good

Average

Poor

< 4000

4001 - 5000

> 5000

06/03/22	17:15:00	1	100	2200	32.0 cm	31.2 Km/Hr	3200.0 mm/Km	3241	4.32	Good	26.4770918	N	83.9513464	E	Normal
06/03/22	17:15:16	1	100	2300	33.0 cm	22.9 Km/Hr	3300.0 mm/Km	3334	4.43	Good	26.4782362	N	83.9516917	E	Normal
06/03/22	17:15:31	1	100	2400	37.0 cm	22.5 Km/Hr	3700.0 mm/Km	3709	4.87	Good	26.4787073	N	83.9521494	E	Normal
06/03/22	17:15:47	1	100	2500	31.0 cm	23.4 Km/Hr	3100.0 mm/Km	3147	4.2	Good	26.4797583	N	83.9528361	E	Normal
06/03/22	17:16:06	1	100	2600	33.0 cm	18.4 Km/Hr	3300.0 mm/Km	3334	4.43	Good	26.4802179	N	83.9530955	E	Normal
06/03/22	17:16:22	1	100	2700	34.0 cm	23.4 Km/Hr	3400.0 mm/Km	3428	4.54	Good	26.4810114	N	83.9529124	E	Normal
06/03/22	17:16:42	1	100	2800	35.0 cm	18.1 Km/Hr	3500.0 mm/Km	3521	4.55	Good	26.4819097	N	83.9531565	E	Normal
06/03/22	17:17:00	1	100	2900	32.0 cm	19.8 Km/Hr	3200.0 mm/Km	3241	4.32	Good	26.4819231	N	83.9542017	E	Normal
06/03/22	17:17:14	1	100	3000	34.0 cm	24.9 Km/Hr	3400.0 mm/Km	3428	4.54	Good	26.4826136	N	83.9543162	E	Normal
06/03/22	17:17:26	1	100	3100	37.0 cm	28.5 Km/Hr	3700.0 mm/Km	3709	4.87	Good	26.4833555	N	83.9546061	E	Normal
06/03/22	17:17:42	1	100	3200	32.0 cm	24.5 Km/Hr	3200.0 mm/Km	3241	4.32	Good	26.4838629	N	83.9547663	E	Normal
06/03/22	17:17:58	1	100	3300	29.0 cm	21.6 Km/Hr	2900.0 mm/Km	2960	3.98	Good	26.4853086	N	83.9554987	E	Normal
06/03/22	17:18:11	1	100	3400	31.0 cm	27.5 Km/Hr	3100.0 mm/Km	3147	4.2	Good	26.4862242	N	83.9555521	E	Normal
06/03/22	17:18:28	1	100	3500	30.0 cm	20.7 Km/Hr	3000.0 mm/Km	3053	4.09	Good	26.4865293	N	83.9562846	E	Normal
06/03/22	17:18:36	1	100	3600	33.0 cm	19.6 Km/Hr	3300.0 mm/Km	3334	4.43	Good	26.4868898	N	83.9569865	E	Normal
06/03/22	17:18:42	1	100	3700	37.0 cm	22.5 Km/Hr	3700.0 mm/Km	3709	4.87	Good	26.4838629	N	83.9547663	E	Normal
06/03/22	17:18:57	1	100	3800	36.0 cm	24.5 Km/Hr	3600.0 mm/Km	3615	4.76	Good	26.4838629	N	83.9547663	E	Normal
06/03/22	17:19:12	1	100	3900	35.0 cm	22.5 Km/Hr	3500.0 mm/Km	3521	4.85	Good	26.4838629	N	83.9547663	E	Normal
06/03/22	17:19:24	1	100	4000	33.0 cm	23.5 Km/Hr	3300.0 mm/Km	3334	4.43	Good	26.4838629	N	83.9547663	E	Normal

Signature
2-5-2022

07/03/22

सहायक
ग्रामीण कार्य विभाग

कार्य प्रमंडल

07/03/22

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल हथुआ (मोपलगांव)

4700

Name of Customer: ANANDMISHRA CONSTRUCTION PRIVATE LIMITED, Machine no: 19193, Road: Laxmiput - Parsanni, Date: 06/03/22, Section No: 01, Equation: $Y=0.936X+245.3$

UIV mm/km
3350

2000
0

0.1 0.2 0.3 0.4 0.5 0.6 0.7 0.8 0.9 1 1.1 1.2 1.3 1.4 1.5 1.6 1.7 1.8 1.9 2 2.1 2.2 2.3 2.4 2.5 2.6 2.7 2.8 2.9 3 3.1 3.2 3.3 3.4 3.5 3.6 3.7 3.8 3.9 4 4.1

Distance*1000 m

06/03/22
2.55

07/03/22
सहायक अभियन्ता
ग्रामीण कार्य विभाग
कार्य प्रमण्डल

06/03/22
कार्यपालक अभियन्ता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल हथुआ (गोपालगंज)

LAXMIPUR TO PARSAUNI

Schedule XLV-Form No. 134

PANAND MISHRA CONSTRUCTION DIVISION

SUB-DIVISION

MR-N-19-20 HATHUA-17

MEASUREMENT BOOK

MB-NO-467

1.

Name of work -

Situation of work -

Agency by which work is executed -

Date of measurement -

No. and date of agreement.

(These four lines should be repeated at the commencement of the measurements relating to each work).

Particulars	Details of actual measurement				Contents of area
	No.	L.	B.	D.	
N/W- Laxmipura To passouri					
Under-New Maintenance policy					
MR-3054					
Agency - Anand Mishra Construction					
Pvt Ltd.					
Agreement no -					
Date of Commencement - 21-8-2020					
Date of Completion - 20-5-2021					

Recordentry

1	Clearing and grubbing				
1	do Road land				
	do		all comp.		
	200 x 1000 x 30M x 1.00M =				600.00M ²
	200 x 2000 x 30M x 1.00M =				1200.00M ²
	200 x 2000 x 30M x 1.00M =				1200.00M ²
	200 x 2000 x 30M x 1.00M =				1200.00M ²
	200 x 1500 x 30M x 1.00M =				900.00M ²
	200 x 1000 x 30M x 1.00M =				600.00M ²
	200 x 2000 x 30M x 1.00M =				1200.00M ²
	200 x 1000 x 30M x 1.00M =				600.00M ²
	200 x 500 x 30M x 1.00M =				300.00M ²
	200 x 100 x 30M x 1.00M =				60.00M ²
	200 x 100 x 30M x 1.00M =				40.00M ²
	Continuation				
					7900.00M ²
					0.79 Hectare

Continuation