

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

NAME OF ROAD:- RESTORATION OF ROAD FROM DUMWANA TO
JITWARPUR

DIVISION:- R.W.D, WORKS DIVISION, FORBESGANJ

CIRCLE:- R.W.D, WORK CIRCLE, KISHANGANJ

BLOCK:- NARPATGANJ

ESTIMATED COST

2147242.00

प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग, कार्य प्रमंडल, फारबिसगंज अंतर्गत


नारपतगंज..... प्रखंड के पथ.....डीमयाना से जिनवारपुर.....

.....जो विभागीय Online Monitoring System MIS पर अपलोड है के बाढ़ 2021 से क्षतिग्रस्त हो जाने के कारण यातायात लायक Motorable हेतु बनाया गया है। इस कार्य को कराने का निर्देश ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक-मु0अ0-4(मु0) विविध कार्य-23-60/2020-1937/पटना, दिनांक-07.07.2021 से प्राप्त है। इस पत्र के Real time geo-tagged Photograph को कार्य के दौरान अपलोड करते हुए (Motorable) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में.....दुरसा..... नदी/नदी उपधार एवं अतिवृष्टि से आए बाढ़ के कारण इस पथ के Road Way के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Motorable कार्य कराया गया है। नेपाल तराई से निकलने वाली इस नदी के तेज धार एवं अतिवृष्टि से इस पथ में कटाव की स्थिति बनी। Motorable कार्य में आवश्यकता अनुसार Bamboo Pilling/Pitching of E.C Bags filled with local sand/ Local Sand Filling/ Brick bats का इस्तेमाल किया गया है। Motorable कार्य कराकर यातायात बहाल कर दिया गया है। निर्देशानुसार कराये गये Geo-tagged Photograph real time के साथ MIS पर अपलोड है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्धतन है।

प्राक्कलन की यथा शीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।


कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा-


सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल-


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, फारबिसगंज

Inspection Report for Flood Damage Work

1. Name of PIUs :

2. Name Of Block / Road :

Narpatganj / Dumbana TO Jitwarpur

A. For Road

1. Damage Location / Chainage

Ch: 0.7km, Ch - 0.81km, Ch - 13.5km

2. Damage Length

: 339m

3. Nature Of Damage

: Side cutting

4. Details Of Restoration

i) Material Being Used In Restoration

: Brickbats, Local sand, bamboo piling, etc

ii) Equipment / Tools Being Used In Restoration Works

Tractor, JCB, Roller, Bamboo Piling machine

iii) Procedure Taken Up In Restoration Works

iv) Restored Length

: 339m

B. For Bridge

1. Damage Location / Chainage

2. Damage Length

3. Nature Of Damage

4. Details Of Restoration

i) Material Being Used In Restoration

ii) Equipment / Tools Being Used in Restoration Works

iii) Procedure Taken Up In Restoration Works

iv) Restored Length

"S"

  C
12/21/17

Signature of JE / AE / EE


Signature

(Name Of Inspector)

Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads

Damaged during flood in JULY 2021 in ARARIA District

RESTORATION OF ROAD FROM CHAKARDAHA MILL CHOWK TO REWAHI
Dumwana To Jitwarpur

Name of Road:-

Block: NARPATGANJ

District: ARARIA

Divison : RWD, Works Division, FORBESGANJ

Circle: RWD, Work Circle, Kishanganj

COST OF 1ST CUTTING RESTORATION

Rs 1573906.00

COST OF 2ND CUTTING RESTORATION

Rs 573336.00

TOTAL COST OF RESTORATION

Rs 2147242.00

Say

Rs 2147242.00

[Signature]
12/8/21
J.E.

[Signature]
12/08/21
A.E.

[Signature]
12/8/21
E.E.

Ref. E.E. Letter No. *1561/2170* Dt. *28-04-22*

Technically Sanctioned For Rs. *21,47,242.00*

(Rupees. *Twenty one lacs forty seven*

thous and two hundred forty two only)

[Signature]
11/4/22
AE
circle

[Signature]

Superintending Engineer
Rural Works Department
Works Circle, Kishanganj

Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads
Damaged during flood in JULY 2020 in ARARIA District

Name of Road:

RESTORATION OF ROAD FROM DUMWANA TO JITWARPUR

Block: FORBESGANJ

District: APARIA

Division : RWD, Works Division, FORBESGANJ

Circle: RWD, Work Circle, Kishanganj

Sl No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	941.20	627.77	590858.59
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	3120.00	75.86	236678.84
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	870.00	40.06	34852.70
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.				
		Each	9039.58	37.35	337598.68
5	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				

		Cum	110.85	1851.91	205284.62
6	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				
		meter	0.00	5251.25	0.00
	TOTAL AMOUNT =				1405273.00
	ADD 12.00 %GST=				168633.00
	SAY TOTAL AMOUNT =				1573906.00

JE

AE *De*
12/08/21

C
12/08/21
E.E.

WORKS DIV.
PATGANJ

RWD WORKS DIV.NARPATGANJ

RWD WORKS DIV. FORB

Dombana to Jitwarpur



12/09/21
32

12/09/21
AE



[Signature]
06/10/21
JE

Dombang to Jitwarpur

[Signature]
06/10/21
AE

Dombam to Jitwarpm



04/10/21
 32

Rp
 04/10/21
 AE

Donubana to jitwarpur



09/09/21
32

124
09/09/21
AE

Dombana to Jitwarpu



8/10/21
 AE

Do
 8/10/21
 AE