

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

NAME OF ROAD:- RESTORATION OF ROAD FROM CHAKARDAHA MILL
CHOWK TO REWAHI PATHRA

DIVISION:- R.W.D, WORKS DIVISION, FORBESGANJ

CIRCLE:- R.W.D, WORK CIRCLE, KISHANGANJ

BLOCK:- NARPATGANJ

ESTIMATED COST

2079740.00

प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग, कार्य प्रमंडल, फारबिसगंज अंतर्गत

नरपताराज प्रखंड के पथ चौराहा साई नदी की दिवाही
पथ जो विभागीय Online Monitoring System MIS पर अपलोड
है के बाढ़ 2021 से क्षतिग्रस्त हो जाने के कारण यातायात लायक Motorable
हेतु बनाया गया है। इस कार्य को कराने का निर्देश ग्रामीण कार्य विभाग, बिहार
सरकार के पत्रांक-मु0अ0-4(मु0) विविध कार्य-23-60/2020-1937/पटना,
दिनांक-07.07.2021 से प्राप्त है। इस पत्र के Real time geo-tagged
Photograph को कार्य के दौरान अपलोड करते हुए (Motorable) कार्य कराना
सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में..... नदी/नदी उपधार एवं अतिवृष्टि से आए
बाढ़ के कारण इस पथ के Road Way के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन
हेतु Motorable कार्य कराया गया है। नेपाल तराई से निकलने वाली इस नदी
के तेज धार एवं अतिवृष्टि से इस पथ में कटाव की स्थिति बनी। Motorable
कार्य में आवश्यकता अनुसार Bamboo Pilling/Pitching of E.C Bags filled
with local sand/ Local Sand Filling/ Brick bats का इस्तेमाल किया गया है।
Motorable कार्य कराकर यातायात बहाल कर दिया गया है। निर्देशानुसार कराये
गये Geo-tagged Photograph real time के साथ MIS पर अपलोड है। MIS
की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति दर विश्लेषण एवं विभागीय
आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त
दर अदधतन है।

प्राक्कलन की यथा शीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई
की जा सके।

कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा-

सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल-

कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, फारबिसगंज

Inspection Report for Flood Damage Work

1. Name of PIUs	: EE RWD Forbesganj
2. Name Of Block / Road	: Chakardhaka mill chowk TO
A. For Road	Rewahi Pathra
1. Damage Location / Chainage	:
2. Damage Length	: 15M, 22M, 15M, 5M, 5M, 43M
3. Nature Of Damage	: Side Cutting Main Cut
4. Details Of Restoration	: Sand Bamboo, B/Bat
i) Material Being Used In Restoration	: Sand Bamboo, B/Bats
ii) Equipment / Tools Being Used In Restoration Works	: Tractor JCB,
iii) Procedure Taken Up In Restoration Works	:
iv) Restored Length	:
B. For Bridge	
1. Damage Location / Chainage	:
2. Damage Length	:
3. Nature Of Damage	:
4. Details Of Restoration	:
i) Material Being Used In Restoration	:
ii) Equipment / Tools Being Used in Restoration Works	:
iii) Procedure Taken Up In Restoration Works	:
iv) Restored Length	:

NA

"S"

Signature of JE / AE / EE

Re C
12/11/22

Signature

(Name Of Inspector)

Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads
Damaged during flood in JULY 2020 in ARARIA District

RESTORATION OF ROAD FROM CHAKARDAHA MILL CHOWK TO REWAHI PATHR/

Name of Road:-

District: ARARIA

Block: NARPATGANJ

Circle: RWD, Work Circle, Kishanganj

Division : RWD, Works Division, FORBESGANJ

COST OF 1ST CUTTING RESTORATION	Rs	323513.00
COST OF 2ND CUTTING RESTORATION	Rs	351732.00
COST OF 3RD CUTTING RESTORATION	Rs	72873.00
COST OF 4TH CUTTING RESTORATION	Rs	43020.00
COST OF 5TH CUTTING RESTORATION	Rs	100461.00
COST OF 6TH CUTTING RESTORATION	Rs	541877.00
COST OF 6TH CUTTING RESTORATION	Rs	646264.00

TOTAL COST OF RESTORATION

Rs 2079740.00

Say Rs 2079740.00

J.E.

Pe
12/08/21
A.E.

C
12/8/21
E.E.

Ref. E.E. Letter No. 156/8130 Dt. 28-4-22

Technically Sanctioned For Rs. 20,79,740.00

(Rupees Twenty Lacs Seventy nine thousand

Seven hundred forty) Only

28/11/22
AG, circle

Superintending Engineer
Rural Works Department
Works Circle, Kishanganj

Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads
Damaged during flood in JULY 2020 In ARARIA District

Name of Road:

RESTORATION OF ROAD FROM CHAKARDAHA MILL CHOWK TO REWAHI PATHRA Cutting-7

Block: FORBESGANJ

District: ARARIA

Divison : RWD, Works Division, FORBESGANJ

Circle: RWD, Work Circle, Kishanganj

Sl No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	443.38	627.77	278343.45
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	564.00	75.86	42784.25
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	282.00	40.06	11297.08
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.				
		Each	5771.06	37.35	215530.15
5	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				

		Cum	15.54	1870.43	29066.52
6	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				
		meter	0.00	5251.25	0.00
	TOTAL AMOUNT =				577021.00
	ADD 12.00 %GST =				69243.00
	SAY TOTAL AMOUNT =				646264.00

JE
RWD WORKS
DIV.
LRPATGANI

AE *Pr*
12/08/21
RWD WORKS DIV.NARPATGANI

C
12/8/21
E.E.
RWD WORKS
DIV. FORBESGANI



Chakardaha mill Chank to Rewahi



Re
27/09/21
AE



Chakardaha mill chener TO Rewari



Re
 27/09/21



Latitude: 26.288285
Longitude: 87.146234
Elevation: 57.43±6 m
Accuracy: 5.9 m
Time: 27-09-2021 12:14
Note: chakardaha se rewahi path 05frah



Latitude: 26.288267
Longitude: 87.146196
Elevation: 57.81±8 m
Accuracy: 19.4 m
Time: 27-09-2021 12:15
Note: chakardaha se rewahi path 05frah

P2
27/09



12
 27/09



20/27/09



Pr
 27/07