

Navtoli (Dhakjari) to
Name of Road: Benipatti Via Jarail

Block : BENIPATTI District: MADHUBANI Length : 3.060 KM

Sr No.	Item	Item of Work	Nos	Length (M)	Width (M)	Depth (M)	Quantity	Unit	Rate	Amount
1	1.1	Labour for lying dry graded jhama khoa or Stone filter under Brick pitching or Boulder Pitching in slope or apron including light ramming etc. all complete as per approved design, specification and direction of E/I								
		CH 0.400 to 0.800 Km	1	7.50	4.50	0.30	10.125			
			1	4.90	1.70	0.30	2.499			
			1	4.25	1.50	0.30	1.913			
			1	10.90	4.00	0.30	12.425 12.080			
			1	5.00	4.00	0.40	8.000			
			1	20.50 20.0	3.50	0.30	21.525 21.000			
			1	3.50	1.50	0.30	1.575			
			1	2.50	3.00	0.30	2.250			
			1	1.50	3.00	0.30	1.350			
							Total	62.317	Cum	1939.93


118603.00
14232 =
1188 =
6309 =
Total Rs= 143036.36
Rs - 140330 =

Add GST 12% Rs= 14508.76
Add Labour Cess 1% Rs= 1208.90
Add Signorage Fee (62.317x1032x10%) Rs= 6431.06


61.138



20/11/21
JE
RWD BENIPATTI



20/11/21
AE
RWD BENIPATTI


30/11/21
EE
RWD BENIPATTI

check & verified


20.12.2021
5.6


20/12/2021
A.E.


20/12/21
E.E.

Post-facto T/E awarded for Rs. 140330.00 (Rs one lac forty thousand three hundred thirty only.)
Reference letter no. 233 dated 21/2/22
of S.E. Darbhanga-2


Superintending Engineer
RWD Works Circle, Darbhanga
21/12/22

⑤

①

Inspection Report for Flood Damaged Work in the year 2021-22

Date of Inspection

:- 20-12-21

Name of PIU :- RWD (W) Div: Dankhanga-2

Name of Block / PIU

:- Benipatti

Inspector

Name of Road

:- Navtoli (Bhakjari) To Benipatti via Jarai

For Road

:-

1. Damage Location/ Chainage

:- CH - 0.400 km to 0.800 km.

2. Damage Length

:- 60.05 Mtr.

3. Nature of Damage

:-

4. Details of Restoration Works

:- Breaches & pots due to flood.

i. Material being used in Restoration Works :- Brick bats.

ii. Equipment's/ Tools being used in Restoration Works :- Tractor, roller.

iii. Procedure taken up in Restoration Works :- Filling and compaction.

iv. Restored Length :- 60.05 Mtr, Restored Qty = 61.138 m³

Remarks :- work found satisfactory.

[Signature]
20.12.21
Signature of JE/AE

[Signature]
20/12/21
Signature of E.E