

Name of Road.		Ladugama to Bhagwatipur		Block: BENIPATTI		District: MADHUBANI		Length: 1.095 KM		
Sr No.	Item	Item of Work	Nos	Length (M)	Width (M)	Depth (M)	Quantity	Unit	Rate	Amount
1	1.1	Labour for lying dry graded Jhama khoa or Stone filter under Brick pitching in slope or apron including including light ramming etc. all complete as per approved design, specification and direction of E/I (Brick Bats)								
		During 1st Wave		12.5	4.5+3.0 (4.5+3.75)/2	1.8+2.8/2 (1.8+3.0+2.4)/3	107.91			
		CH- 0.200 KM	1	15.00	4.125+3.75	2.667	165.000			
		Deduction for HP	-1	5.00	0.785		-3.925			
							161.075	Cum	1939.93	312480.00
	1.2	Providing and Laying Reinforced Cement Concrete Pipe NP3 as per design in single Row 1000 MM Dia Hume pipeall complete jobdir of E/I								
		Cost of 1000 MM Dia Hume Pipe =5565/Mtr								
		Analysis of carriage (8/10x7.94x62+81.88)=475.704								
		CH- 0.200 KM	1	2	2.500		5.000	RM	6040.70	30204.00
		Total								231727.80

Add GST 12% Rs= 41122.00

Add Labour Cess 1% Rs= 3427.00

Add Signorage Fee (161.075x1032x10%) Rs= 16623.00

Total Rs= 403856.00

JE
RWD BENIPATTI

AE
RWD BENIPATTI

EE
RWD BENIPATTI

checked & verified

20.12.2021
JE

20/12/21
A.E.

20/12/21
EE

Post factor T/s awarded for Rs. 272573.00 (Rs. Two lac Seventy two thousand five hundred seventy two only.)
Reference letter no. 233 dated 21/12/22
of G.E. darbhanga-2

Superintending Engineer
RWD Works Circle, Darbhanga

12

Inspection Report for Flood Damaged Work in the year 2021-22

Date of Inspection :- 20-12-2021 Name of PIU :- RWD (W) Div. Darbhanga-2
(Inspected)
Name of Block / PIU :- Benipatti (RWD(W) Div. Benipatti)
Name of Road :- Ladugama to Bhagwatipur Road

For Road :-

1. Damage Location/ Chainage :- 0.200 KM

2. Damage Length :- 12.50 Mtr

3. Nature of Damage :- Breach

4. Details of Restoration Works :-

i. Material being used in Restoration Works Brick bats & Hume pipe


ii. Equipment's/ Tools being used in Restoration Works Tractor & Rolling

iii. Procedure taken up in Restoration Works Filling & compaction

iv. Restored Length - 12.50 Mtr, One H-pipe of 5m length

Remarks :- work found satisfactory


20.12.21
Signature of JE/AE


20/12/21
Signature of E.E