

Name of Road: Uchchaith to Sahraul

Block : BENIPATTI District: MADHUBANI Length : 4.200 KM

Sr No.	Item	Item of Work	Nos	Length (M)	Width (M)	Depth (M)	Quantity	Unit	Rate	Amount
	1.2	Construction of subgrade and earthen shoulders with approved material obtained from borrow pits with all lifts and leads, transporting to site, spreading, grading to required slope and compacted to meet requirement of Table 300.2 with lead upto 1000 m as per Technical Specification Clause 303.1								
					(4.5+3.5)/2					
		CH-2.700 KM	1	12.70	4.00	0.90	45.720			
					(4.5+3.5)/2					
		CH-3.200 KM	1	19.60	4.00	0.75	58.800			
					(4.5+3.5)/2	(1.2+1.5)/2				
		CH-3.200 KM	1	30.00	4.00	1.35	162.000			
							Total	266.520	Cum	215.849
										57528.00
1	1.2	Labour for lying dry graded jhama khoa or Stone filter under Brick pitching or Boulder Pitching in slope or apron including light ramming etc. all complete as per approved design, specification and direction of E/I								
					(3.5+4)/2	(0.9+0.6)/2	30.937			
		CH-2.700 KM	1	12.70	3.75	0.75	35.719			
					(3.5+4)/2	(0.5+0.7)/2	28.687			
		CH-3.200 KM	1	19.60	3.75	0.60+30%	44.100			
					(3.5+4)/2	(1+0.8)/2	87.75			
		CH-3.200 KM	1	30.00	3.75	0.90	101.250			
							Total	181.069	Cum	1939.93
										351261.00

Total 408789.00
 Add GST 12% Rs= 49055.00
 Add Labour Cess 1% Rs= 4088.00
 Add Signorage Fee (266.52x157.5x10%) Rs= 4184.00
 Add Signorage Fee (181.069x1032x10%) Rs= 18686.00
 Total Rs= 484802.00

JE
 RWD BENIPATTI

AE
 RWD BENIPATTI

EE
 RWD BENIPATTI

check a

20.12.2021

20/12/2021

20/12/21

Post facto T/S for awarded for Rs 338270.00 (Rs Three
 Lacs thirty eight thousand two hundred seventy only.)
 Reference Letter no. 233 dated 21/2/22.
 of S.E. Darbhanga

Superintending Engineer
 RWD Works Circle, Darbhanga

14

Inspection Report for Flood Damaged Work in the year 2021-22

Date of Inspection :- 20.12.21 Name of PIU :- RWD (W) Div. Darbanga-2
Name of Block/PIU :- BENIPATTI (RWD (W) Div Benipatti)
Name of Road :- UCHCHATHI TO SOHRAUL
For Road :-

1. Damage Location/ Chainage :- from CH 2.700km to CH-3.200km

2. Damage Length :- 116.3m

3. Nature of Damage :- Breaches due to flood

4. Details of Restoration Works :-

i. Material being used in Restoration Works E/W & Brick Bats.

ii. Equipment's/ Tools being used in Restoration Works : JCB, Tractor and Roller

iii. Procedure taken up in Restoration Works : Hauling, filling and Compaction

iv. Restored Length : 116.3m

Remarks :- Satisfactory.

[Signature]
20.12.21
5.6
Signature of JE/AE

[Signature]
20/12/21
Signature of E.E