

Name of Road: Sahraul to Trimuhan

Block: BENIPATTI

District: MADHUBANI

Length: 1.412 KM

Sr No.	Item	Item of Work	Nos	Length (M)	Width (M)	Depth (M)	Quantity	Unit	Rate	Amount
1	1.1	Labour for lying dry graded jhama khoa or Stone filter under Brick pitching or Boulder Pitching in slope or apron including light ramming etc. all complete as per approved design, specification and direction of E/I								
				44	(2.5+3)/2	(0.3+0.2)/2	20.25			
			1	54.00	2.75	0.25	32.125			
		CH-0.320 KM	1	10.00	2.00	0.30	6.000			
						Total	43.125	Cum	1939.93	-83659.00-

Add GST 12% Rs= 10039.00
 Add Labour Cess 1% Rs= 837.00
 Add Signorage Fee (43.125x1032x10%) Rs= 4451.00
 Total Rs= 98986.00
 36.25
 83205.00

JE
 RWD BENIPATTI

AE
 RWD BENIPATTI

EE
 RWD BENIPATTI

check on 6/11/21

20.12.2021
 J.E.

20/12/2021
 A.E.

20/12/21
 E.E.

Total Rs. 83205.00 (Eighty three thousand two hundred five only.)

Reference letter no. 233 dt. 21/2/22
 of E.E. darbhanga.2

Superintending Engineer
 RWD Works Circle, Darbhanga

13

Inspection Report for Flood Damaged Work in the year 2021-22

Date of Inspection :- 20.12.21 Name of PIU :- RWD (W) Div. Darbhanga-2
Name of Block/PIU :- BENIPATII (RWD(W) Div Benipatti)
Name of Road :- SAHRAUL TO TRIMUHAN
For Road :-

1. Damage Location/ Chainage :- CH. 0.320Km

2. Damage Length :- 54m

3. Nature of Damage :- Breaches due to flood

4. Details of Restoration Works :-


i. Material being used in Restoration Works Brick Bats


ii. Equipment's/ Tools being used in Restoration Works Tractor & Road Roller

iii. Procedure taken up in Restoration Works : Filling and compaction

iv. Restored Length : 54m

Remarks :- Work found Satisfactory.


20.12.21
J.E.
Signature of JE/AE


20/12/21
Signature of E.E