
(1)

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

NAME OF ROAD:-

RESTORATION OF ROAD FROM THAKUR TOLA BAJRANGWAL CHOUK TO ACHRA SIMA

DIVISION:-

R.W.D, WORKS DIVISION, FORBESGANI

CIRCLE:-

R.W.D, WORK CIRCLE, KISHANGANJ

BLOCK:-

NARPATGANJ

ESTIMATED COST

994613.00

प्रतिवेदन

प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग, कार्य प्रमंडल, फारबिसगंज अंतर्गत

प्रखंड के पथ है जिस्ति क्रिंग के जिस्से के खुन्र हो जीन के कारण यातायात लायक Motorable हेतु बनाया गया है। इस कार्य को कराने का निर्देश ग्रामीण कार्य विभाग, बिहार सरकार के पत्रांक-मु0अ0-4(मु0) विविध कार्य-23-60/2020-1937/पटना, दिनांक-07.07.2021 से प्राप्त है। इस पत्र के Real time geo-tagged Photograph को कार्य के दौरान अपलोड करते हुए (Motorable) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

प्राक्कलन की यथा शीध्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई

की जा सके।

कनीय अभियंता ग्रामीण कार्य विभाग कार्य प्रशाखा— सहायक अभियंता ग्रामीण कार्य विभाग कार्य अवर प्रमंडल— कार्यपालक अभियंता ग्रामीण कार्य विभाग कार्य प्रमंडल,फारबिसगंज

Inspection Report for Flood Damage Work

1.Name of PIUs	: And the state Common death of the
2. Name Of Block / Road	Naspatjans/Thakurtola Bajoangwali chowk
A. For Road	
1 Damage Location / Chainage	ch: 0.410m, ch-0.71cm :78m : cutting
2.Damage Length	:78m
3.Nature Of Damage	: Cutting
4 Details Of Restoration	:
i) Material Being Used In Restoration	: Local Sand, flyme pape soick but familion
ii) Equipment / Tools Being Used In Resto	: Local Sand, Hymepipe Boick but Ramboo pile oration Works : JCB, Roller, toactor, Ramboo pile mani
iii) Procedure Taken Up In Restoration V	
iv) Restored Length	:78m
B. For Bridge	
1 Damage Location / Chainage	:
2 Damage Length	:
3.Nature Of Damage	· ·
4.Details Of Restoration	:
i) Material Being Used In Restoration	:
ii) Equipment / Tools Being Used in Resto	oration Works :
iii) Procedure Taken Up In Restoration We	orks ::
iv) Restored Length	:
V	"°2"
	2011122
A C.	Signature
Signature of JE / AE / EE	(Name Of Inspector)

Abstract of Cost

Name of Work: Estimate for Repairing/Restoration/Making Motorable Roads
Damaged during flood in JULY 2020 in ARARIA District

Name of Road:

RESTORATION OF ROAD FROM THAKUR TOLA BAJRANGWALA CHOUK TO ACHRA SIMA

Block: FORBESGANJ

District: ARARIA

Divison: RWD, Works Division, FORBESGANJ

Circle: RWD, Work Circle, Kishanganj

il No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	609.18	627.77	382422.74
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	558.00	75.86	42329.10
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	339.00	40.06	13580.53
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.				
		Each	5900.78	37.35	220374.90
5	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				

		Cum	52.95	1851.91	98058.82
6	Supply,laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				
		meter	25.00	5251.25	131281.15
	TOTAL AMOUNT =				888047.00
	ADD 12.00 %GST=				106566.00
	SAY TOTAL AMOUNT =				994613.00

12 Se

NARPATGANJ

AE TOBY

RWD WORKS DIV.NARPATGANJ

(12/8)T E.E.

RWD WORKS DIV. FORB

Ref. E.E. Letter No. 1561 3130 Dt. 28-04-22

Technically Sanctioned For Rs. 994617 Co.

(Rupees Nine las Nly four fromand

11/4/22

AE, circle

...)Only

Abstract of Cost

Name of Work: Estimate for Repairing/Restoration/Making Motorable Roads
Damaged during flood in JULY 2019 in ARARIA District

Name of Road:

RESTORATION OF ROAD FROM THAKUR TOLA BAJRANGWALA CHOUK TO ACHRA SIMA

Block:NARPATGANJ

District: ARARIA

Divison: RWD, Works Division, FORBESGANJ

Circle: RWD, Work Circle, Kishanganj

SI No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	609.18	627.77	382422.74
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	558.00	75.86	42329.10
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	339.00	40.06	13580.53
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.				
		Each	5900.78	37.35	220374.90
5	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.			,	22007 1130
		Cum	52.95	1851.91	98058.82
6	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,
		meter	25.00	5251.25	131281.15
		Total A	mount (in Rs)	888047.25	

_ 1E

RWD WORKS DIV. NARPATGANJ RWD WORKS DIV.NARPATGANJ

[2/8/7 E.E.

RWD WORKS DIV. FORBESC

Detailed Estimate

Name of Road:

RESTORATION OF ROAD FROM THAKUR TOLA BAJRANGWALA CHOUK TO ACHRA SIMA

No.	Items of Works	Nos.	(m)	B (m)	D (m) IN (Ay.)	Quantity (m3)	
_	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.						
		1	20.00	(6.0+5.5)/2	(1.5+2.0+1.4)/2	187.83	
		1	45.00	(4.5+5.0)/2	(0.8+2.0+1.4)/2	299.25	
		1	13.00	(6.0+5.5)/2	(1.5+2.0+1.4)/2	122.09	
			13.00	10.0+3.5//2	TOTAL=	609.18	
					Total Qty =	609.18	
p	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.						
		2	20.00	2.00	1.50	120.00	
		2	55.00	2.00	1.50	330.00	
		2	18.00	2.00	1.50	108.00	
	Labour for fitting & fixing 62mm to 75mm dia			_	Total Qty =	558.00	
J I	bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.						
	·	1	_	3.00		120.00	
			55.00	3.00		165.00	
		-	18.00	3.00		54.00	
					Total Qty =	339.00 339.00	
O	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.				Total Qty	333.00	
			2 20.00	(0.6+0.5)/	2 (1.5+2.0+1.4)/3	35.93	
			2 55.00			98.82	
			2 18.00	(0.6+0.5)/			
-		t vone	Total	No of EC Bar	TOTAL=	167.09 5) 5900.78	
	Company of State of S	Total No. of EC Bags =253.45X35.315) SAY NO OF BAGE=					
3	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				in or under	5901	
		1			0.15	17.40	
	1	_1			0.15	24.75	
		1	18.00	0 4.00		10.80	
1		_			Total Qty.	= 52.95	
6	Supply,laying and Carriage of of hume pipe		1				
	1000 mm dia (HPC), all complete job.	_	5 2.00			25.00	
		-	1 0.00	2.50		0.00	
1		-			Total Qty	. = 25.00	

RWD WORKS DIV.

AE DE SON MARPATGANI

C/2/814

RWD WORKS DIV. FORBESGANJ

Takus tols Bayrang bali chowk to Achre sing







Maker tola to Bejragbeli chonk.





Pe reliable

Thakur tols to Bay rangbali Chowk Achra Sing.







Thakur Tols to Bay Nampbali to chowk A chara Suns





