



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

BHAWANIPUR GOWALTOLI VIA HOSPITAL TO SARAKHOR

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 660	
DISTRICT	KATIHAR	
BLOCK	BARSOI	
DIVISION	BARSOI	
TOTAL LENGTH OF ROAD	0.660	KM
TOTAL COST OF F.D.R. PART - A	Rs. 10.154	Lacs
ADD G.S.T @ 12%	Rs. 1.219	Lacs
ADD Labour Cess @ 1%	Rs. 0.102	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.471	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 11.946	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Barsoi


प्रतिवेदन


प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग कार्य प्रमण्डल अन्तर्गत प्रखंड


के पथ (.....) जो
विभागीय Online Monitoring System MIS पर अपलोड है के बाद 2021 से क्षतिग्रस्त हो जाने के
कारण यातायात लायक Movable हेतु बनाया गया है। इस कार्य को करने का निर्देश ग्रामीण कार्य
विभाग, बिहार सरकार के पत्रांक:-मु0अ0-4(मु0) विविध (कार्य) -23-291/2019-4275/पटना, दिनांक-
22/10/2021 से प्राप्त है। इस पत्र से Real time Geotagged Photographs को कार्य के दौरान
अपलोड करते हुए (Movable) कार्य कराना सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में अतिवृष्टि/बाढ़ उपधार से आए बाढ़ के कारण इस पथ के
रोडवे के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Movable कार्य कराया गया है। MIS में
उपलोडेड फोटो दिनांक का Lat/Long के साथ लिया गया है। नेपाल तराई से
निकलनेवाली इस नदी के तेज धार से इस पथ में कटाव की स्थिति बनी। मोटरेबल कार्य में
आवश्यकतानुसार मिट्टी भराई, लोकल बालु भराई, खाली सिमेंट बैग में लोकल बालु भरकर, बॉस का
पाइल, चचरी, बॉस का रनर, ह्यूम पाइप एवं ब्रिक बैट का इस्तेमाल किया गया है। निर्देशानुसार कराए
गए कार्य कि Geotagged Photographs Real Time के साथ MIS पर उद्धत है। MIS की
छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति, दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन
में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अद्यतन है।

प्राक्कलन की यथाशीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।


कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा,


सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल,


कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल,

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : BHAWANIPUR GOWALTOLI VIA HOSPITAL TO SARAKHOR
 DISTRICT KATIHAR
 DIVISION BARSOI
 BLOCK BARSOI
 LENGTH OF ROAD (IN KM) 0.660

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	0.000
2	HUME PIPE	0.000
3	BRICK BATS	8.645
4	SAND BAGS	0.000
5	BAMBOO WORK	1.027
6	STEEL DRUM SHEET	0.482
TOTAL COST OF PROJECT =		10.154
Add G.S.T. @ 12%		1.219
Add Labour Cess @ 1%		0.102
Add Seigniorage Fee @ 10%		0.471
Total Cost of Restoration Work =		11.946

[Signature]
 J.E.
 RWD

[Signature]
 A.E.
 RWD

[Signature]
 E.E.
 RWD

Provisional Technically Sanctioned For Rs. 11.946 Lacs.
 (Rupees — Eleven
 thousand —
 Thousands — Six Hundred) Only

[Signature]
 अधीक्षक अभियंता
 राजीव नगर विभाग
 नगर विकास, पूर्णिया

Inspection Report for Flood damage work

Date:

1. Name of PIUs-

2. Name of Block/Road- Bhairwani pur Chowdoli via Hospital to Sarsikhor

A. For Road

1. Damage Location/Chainage : 280m.
2. Damage Length : 152.80m
3. Nature of Damage :
4. Details of Restoration :
i Material being used in Restoration :
ii Equipment/Tools being used in Restoration works :
iii Procedure taken up in Restoration works :
iv Restored Length :

B. For Bridge

1. Damage Location/Chainage :
2. Damage Length :
3. Nature of Damage :
4. Details of Restoration :
i Material being used in Restoration :
ii Equipment/Tools being used in Restoration works :
iii Procedure taken up in Restoration works :
iv Restored Length :

Signature of JE/AE/EE

Bur
25/8/21
AE

Signature

(Name of Inspector)