

6)

RURAL WORKS DEPARTMENT



GOVERNMENT OF BIHAR

NAME OF ROAD:- RESTORATION OF ROAD FROM RAJMAR TOLA
MIRZAPUR TO LAXMIPUR CHOUK BATHNAHA
BIRPUR MAIN ROAD

DIVISION:- R.W.D, WORKS DIVISION, FORBESGANJ

CIRCLE:- R.W.D, WORK CIRCLE, KISHANGANJ

BLOCK:- NARPATGANJ

ESTIMATED COST

902017.00


प्रतिवेदन


प्रस्तुत प्राक्कलन ग्रामीण कार्य विभाग, कार्य प्रमंडल, फारबिसगंज अंतर्गत


नरपतगंज प्रखंड के पथ जीमरतीला गीर्जापुर-लखनपुर-चौद बख्ता
को मुरुम खड्ड जो विभागीय Online Monitoring System MIS पर अपलोड
है के बाढ़ 2021 से क्षतिग्रस्त हो जाने के कारण यातायात लायक Motorable
हेतु बनाया गया है। इस कार्य को कराने का निर्देश ग्रामीण कार्य विभाग, बिहार
सरकार के पत्रांक-मु0अ0-4(मु0) विविध कार्य-23-60/2020-1937/पटना,
दिनांक-07.07.2021 से प्राप्त है। इस पत्र के Real time geo-tagged
Photograph को कार्य के दौरान अपलोड करते हुए (Motorable) कार्य कराना
सुनिश्चित करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में सुरसर नदी/नदी उपधार एवं अतिवृष्टि से आए
बाढ़ के कारण इस पथ के Road Way के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन
हेतु Motorable कार्य कराया गया है। नेपाल तराई से निकलने वाली इस नदी
के तेज धार एवं अतिवृष्टि से इस पथ में कटाव की स्थिति बनी। Motorable
कार्य में आवश्यकता अनुसार Bamboo Pilling/Pitching of E.C Bags filled
with local sand/ Local Sand Filling/ Brick bats का इस्तेमाल किया गया है।
Motorable कार्य कराकर यातायात बहाल कर दिया गया है। निर्देशानुसार कराये
गये Geo-tagged Photograph real time के साथ MIS पर अपलोड है। MIS
की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति दर विश्लेषण एवं विभागीय
आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त
दर अदधतन है।

प्राक्कलन की यथा शीघ्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई
की जा सके।


12/8/21
कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा-


12/8/21
सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल-


12/8/21
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, फारबिसगंज

Inspection Report for Flood Damage Work

1. Name of PIUs :

2. Name Of Block / Road

Nasbatganj/Rajmar tola Mirzapur tola
Mirzapur to Laxmipur Chank Bathnaha Gurbur main Road

A. For Road

1. Damage Location / Chainage

Ch- 0.7km, 0.82km, 0.9km

2. Damage Length

66m

3. Nature Of Damage

: Washout

4. Details Of Restoration

:

i) Material Being Used In Restoration

: Local sand, Hume pipe, Brick bat E.C bag,

ii) Equipment / Tools Being Used In Restoration Works

Bamboo piling
30 Roller, tractor Bamboopile machine

iii) Procedure Taken Up In Restoration Works

:

iv) Restored Length

: 66m

B. For Bridge

1. Damage Location / Chainage

:

2. Damage Length

:

3. Nature Of Damage

:

4. Details Of Restoration

:

i) Material Being Used In Restoration

:

ii) Equipment / Tools Being Used in Restoration Works

:

iii) Procedure Taken Up In Restoration Works

:

iv) Restored Length


:

Signature of JE / AE / EE

 12/11/22

Signature

(Name Of Inspector)

"S"
 20/11/22

Abstract of Cost

Name of Work : Estimate for Repairing/Restoration/Making Motorable Roads
Damaged during flood in JULY 2020 in ARARIA District

Name of Road:

**RESTORATION OF ROAD FROM RAJMAR TOLA MIRZAPUR TO LAXMIPUR CHOUK BATHNAHA BIRPUR
MAIN ROAD**

Block: FORBESGANJ

District: ARARIA

Division : RWD, Works Division, FORBESGANJ

Circle: RWD, Work Circle, Kishanganj

Sl No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	493.50	627.77	309805.26
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	690.00	75.86	52342.44
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	238.00	40.06	9534.42
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.				
		Each	4187.65	37.35	156395.09
5	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				

		Cum	43.40	1851.91	80373.05
6	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				
		meter	37.50	5251.25	196921.72
	TOTAL AMOUNT =				805372.00
	ADD 12.00 %GST=				96645.00
	SAY TOTAL AMOUNT =				902017.00

[Signature]
12/8/21
JE

RWD WORKS DIV.
NARPATGANJ

[Signature]
12/08/21
AE

RWD WORKS DIV. NARPATGANJ

[Signature]
12/8/21
E.E.

RWD WORKS DIV. FORB

Ref. E.E. Letter No. 1861(3130) Dt. 28-04-22

Technically Sanctioned For Rs. 9,02,017.00

(Rupees Nine lacs two thousand

Seventeen Only

[Signature]
11/4/22
AE, circle.

[Signature]
28/4/22
Superintending Engineer
Rural Works Department
Works Circle, Kishanganj

Rajmar tola mirzapur to Laxmipur chowk Bathnaha
Bihar road



24/11/21
JE

26
12/11/21
AE

Rajmar tola mirzapur to Laxmipura Chowk Bathnaha
Bispur Road



12/8/21
 78

12/8/21
 AE

Rajmar tola mirzapur to Laxmipura Chowk Bathnaha Bypass Road



Latitude: 26.368173
 Longitude: 87.125725
 Elevation: 68.66 m
 Accuracy: 3.2 m
 Time: 21-11-2021 13:52
 Note: Rajmar Tola Mirzapur to
 Laxmipur chowk Bathnaha
 Bypass Mukhya sadak Tak



Latitude: 26.368237
 Longitude: 87.125984
 Elevation: 67.96±15 m
 Accuracy: 16.3 m
 Time: 23-11-2021 14:51
 Note: Rajmar tola mirzapur to

Powered by NoteCam

24/11/21
 JE

24/11/21
 AE

Rajmatala Mirzapur to Laxmipur Chowk Bathnaha Bypass Road



30/08/21
AZ

30/08/21
AZ

farmer tola mirzapur to Laxmipur chowk Balthaha Bupur Road



18/8/21
 JE

Re
 18/08/21
 AE

Rajmar tola mirzapur tola to Laxmipur Chander Bathnaha
Birkpur Road



12/8/21
22

Ra
12/8/21
AE

Rajmah tola mirzapur to Laxmipur chowk to 'Bathnaha'
Birpur Road



12/8/21
SE

Re
12/8/21
AE

Rajmar tola mirzapur Chowk Bathnaha Birpur road



Latitude: 26.368121
Longitude: 87.126237
Elevation: 41.33±150 m
Accuracy: 250.4 m
Time: 02-08-2021 18:30
Note: Rajmar tola Mirzapur to Laxmipur Chowk
Bathnaha virpur Mukhya sadak Tak



Latitude: 26.368169
Longitude: 87.125709
Elevation: 70.69 m
Accuracy: 3.2 m
Time: 17-07-2021 13:21
Note: Rajmar tola Mirzapur
Bathnaha

12/8/21
AE

12/8/21
AE