

Name of Road:		Block : MADHUBANI District: MADHUBANI Length : 0.861KM								
Sr No.	Item	Item of Work	Nos	Length (M)	Width (M)	Depth (M)	Quantity	Unit	Rate	Amount
1	1.1	Labour for lying dry graded jhama khoa or Stone filter under Brick pitching or Boulder Pitching in slope or apron including light ramming etc. all complete as per approved design, specification and direction of E/I								
		CH-0.00 KM	1	3.000	2.700	0.150	1.22			
		CH-0.050KM	1	1.800	1.400	0.150	0.38			
			1	1.400	1.200	0.150	0.25			
		CH-0.100KM	1	2.500	2.500	0.150	0.94			
		CH-0.150KM	1	3.000	2.300	0.300	2.07			
		CH-0.150KM	1	2.400	2.000	0.150	0.72			
		CH-0.150KM	1	3.300	2.500	0.300	2.48			
			1	8.000	3.000	0.600	14.40			
			1	10.500	3.000	0.400	12.60			
		CH-0.250KM	1	6.400	3.200	0.600	12.29			
			1	2.400	1.200	0.150	0.43			
		CH-0.300KM	1	3.000	4.000	0.150	1.80			
		CH-0.350KM	1	8.300	2.600	0.150	3.24			
		CH-0.350KM	1	2.500	2.700	0.150	1.01			
		CH-0.400KM	1	2.400	1.500	0.150	0.54			
		CH-0.400KM	1	2.000	1.900	0.150	0.57			
			1	2.000	1.900	0.150	0.57			
		CH-0.500 KM	1	9.000	2.400	0.300	6.48			
		CH-0.600 KM	2	14.500	2.500	0.300	22.50			
		CH-0.600 KM	1	6.700	2.400	0.300	4.82			
			1	25.000	2.400	0.180	11.23			
							100.53	CUM	1939.93	195026.98

97.445

Add GST 12% Rs=

23403.24 22684.2

Add Labour Cess 1% Rs=

1950.27 1890.2

Add Signorage Fee (100.53x1032x10%) Rs=

10375.01 10056.2

97445

Total Rs=

230755.50

Tb. Rs. 223666.2

20/11/21
20/11/21
20/11/21

RWD BENIPATTI

20/11/21

JE

RWD BENIPATTI

20/10/21

AE

RWD BENIPATTI

20/11/21

20/11/21
E.E

20.12.2021
20.12.2021

20/12/2021
A.E.


①


Inspection Report for Flood Damaged Work in the year 2021-22

Date of Inspection :- 20.12.21 Name of PIU :- RWD (W) Div. Dasthargha
Inspected.
Name of Block/PIU :- Durgauli chaupal Tol House of shyam chaupal
Name of Road :- To Gamharia Muslim Tol house of mahakant
Thai.
For Road :-

1. Damage Location/ Chainage :- 0.00 to 0.600 KM.
2. Damage Length :- 119 Mtr
3. Nature of Damage :- pots due to flood.
4. Details of Restoration Works :-
 - i. Material being used in Restoration Works :- Brick bats
 - ii. Equipment's/ Tools being used in Restoration Works :- Tractor
 - iii. Procedure taken up in Restoration Works :- Filling & compaction.
 - iv. Restored Length :- 119 Mtr, Restored Qty = 97.445 m³

Remarks :- Work found satisfactory.


20.12.21
Signature of JE/AE


20.12.21
Signature of E.E