

GOVERNMENT OF BIHAR
RURAL WORKS DEPARTMENT



Name of work : L029 to Pachaili

District : Araria

Block : Palasi

FDR (2021-22)

Restoration Cost of Road	: Rs. 2.146 Lacs
1% L.Cess of Rest. Cost	: Rs. 0.021 Lacs
12% GST of Rest. Cost	: Rs. 0.258 Lacs
Seigniorage fee	: Rs. 0.061 Lacs
Total Restoration Cost including Labour Cess & GST	: Rs. 2.486 Lacs

R.W.D, WORKS CIRCLE, KISHANGANJ

R.W.D, WORKS DIVISION, ARARIA

Inspection Report for Flood Damage Work

1. Name of PIUs : EE RWD works Division Araria
2. Name Of Block / Road : Lo29 to pachalli
A. For Road Block - palash
1. Damage Location / Chainage : ch-100 & ch-1100
2. Damage Length : 40.04
3. Nature Of Damage : Side cutting in flood
4. Details Of Restoration :
i) Material Being Used In Restoration : L'sand, Bamboo & Brick Bats
ii) Equipment / Tools Being Used In Restoration Works : Tractor & JCB
iii) Procedure Taken Up In Restoration Works : Manually
iv) Restored Length : 40.04

B. For Bridge

1. Damage Location / Chainage :
2. Damage Length :
3. Nature Of Damage :
4. Details Of Restoration :
i) Material Being Used In Restoration :
ii) Equipment / Tools Being Used in Restoration Works :
iii) Procedure Taken Up In Restoration Works :
iv) Restored Length :

} NA

'S' (satisfactory)


Signature of JE / AE / EE


Signature
Executive Engineer
(Name of Inspector)
Kishanganj-2

ग्रामीण कार्य विभाग
बिहार, सरकार

पत्रांक - मु0अ0-4 (मु0) विविध कार्य-23-60/2020 - 1937

पटना, दिनांक 07/07/2021

प्रेषक-

पंकज कुमार पाल (भा0प्र0रो0)
सचिव

सेवा में,

सभी कार्यपालक अभियंता
ग्रामीण कार्य विभाग,

विषय-

बाढ़ अतिवृष्टि से क्षतिग्रस्त पथों/पुलियों को यातयात लायक (Motorable) करने
के संबंध में।

महाशय,

उपर्युक्त विषय के संबंध में निदेश दिया जाता है कि प्रमंडल अन्तर्गत सभी अभियंता बाढ़/अतिवृष्टि से क्षतिग्रस्त पथों का शत प्रतिशत निरीक्षण करेंगे। पथों/पुलियों के क्षतिग्रस्त भाग से पानी उतरते ही उसे यातायात लायक बनाने की कारवाई एवं Motorable किये जाने से पहले तथा Motorable कार्य के बाद का Real time, Geo tagged photographs को MIS पर तत्क्षण अपलोड किया जाना सुनिश्चित करेंगे। इन कार्यों को कराने हेतु कार्यपालक अभियंता पूर्ण रूप से जिम्मेवार होंगे। कार्य न कराने की स्थिति में उनके विरुद्ध अनुशासनिक कार्रवाई की बाध्यता होगी।

विश्वासभाजन

(पंकज कुमार पाल)

सचिव

पटना, दिनांक 07/7/2021

ज्ञापांक- मु0अ0-4 (मु0) विविध कार्य-23-60/2020 - 1937

प्रतिलिपि:-सभी अधीक्षण अभियंता को सूचनार्थ एवं आवश्यक कार्रवाई हेतु प्रेषित। साथ ही उन्हें निदेश दिया जाता है कि वे लगातार अनुश्रवण एवं निरीक्षण करते हुए क्षतिग्रस्त भाग को अतिशीघ्र यातायात लायक बनवाने की कार्रवाई सुनिश्चित करेंगे।

सचिव

पटना, दिनांक 07/7/2021

ज्ञापांक-मु0अ0-4 (मु0) विविध कार्य-23-60/2020 - 1937

प्रतिलिपि:-सभी मुख्य अभियंता, ग्रामीण कार्य विभाग को सूचनार्थ एवं लगातार अनुश्रवण करने हेतु प्रेषित।

सचिव

FDR (2021-22)
GENERAL ABSTRACT OF COST

Name of Road : L029 to Pachalli
District : Araria
Block : Palasi
Cutting Chainage (M) : CH-100M & CH- 1100M

Sl. No.	Item of work	Amount (In Rs.)
1	Filling of Local Sand	84,131.00
2	Labour for cutting 62mm to 75mm dia Bamboo	11,080.00
3	Labour for fitting & fixing 62mm to 75mm dia Bamboo runner	926.00
4	Supply of EC bag of Local Sand	23,489.00
5	Supply & Carriage of Brick Bats	94,990.00
6	Supply, laying and carriage of 1000mm dia HPC	-
a	Sub Total Cost of Work :	2,14,616.00
b	1% L.cess of Total Cost :	2,146.00
	12% GST of Total Cost :	25,754.00
	Seigniorage Fee	6,095.00
d.	Total Cost of Work including GST & Cess :	2,48,611.00

[Signature]
Junior Engineer RWD
Works Sec. Palasi
(Araria)

[Signature]
Assistant Engineer
RWD Works Section
Palasi (Araria)

[Signature]
Executive Engineer
RWD Works Div.
Araria

Supretending Engineer
RWD Circle, Kishanganj

Recd No. 1457 28/04/022

Technically Sanctioned For Rs. 2,48,611/-

(Rupees) Two lakhs forty eight thousand

Six hundred eleven

Only

[Signature]
29/4/22
AG

[Signature]
29/4/22

अधीक्षण अभियन्ता
ग्रामीण कार्य विभाग
कार्य अंचल, किशनगंज

BILL OF QUANTITY

Name of Road:

Block:

District:

Division:

L029 to Pachaili

Palasi

Araria

R.W.D ,Araria

Sl No.	Description	Unit	Quantity	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.	Cum	163.54	514.43	84131.00
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.	Mtr.	200.00	55.40	11080.00
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.	Mtr.	30.00	30.87	926.00
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.	Each	618	38.03	23489.00
5	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.	Cum	43.80	2168.72	94990.00
6	Supply,laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.	meter	0.00	4425.07	0.00
TOTAL AMOUNT =					214616.00

[Signature]
28/12/12

Junior Engineer
RWD Works Sec.
Palasi

[Signature]
28/12/12

Assistant Engineer
RWD Works sec.
Palasi

[Signature]
28/12/12

Executive Engineer
RWD Works Division
Araria

ESTIMATE FOR REPAIRING/ RESTORATION / MAKING MOTORABLE ROADS DAMAGED DURING FLOOD						
Detailed Estimate						
Name of Road:		L029 to Pachaili				
Block:		Palasi				
District:		Araria				
Sl No.	Items of Works	Nos.	L (m)	B (m)	D (m) IN (Av.)	Quantity (m3)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.					
	Ch-100	1	10.00	(3.0+5.0)/2	(1.80+2.50+2.0)/3	84.00
		1	5.00	(1.50+2.50)/2	(1.80+2.0+1.50)/3	17.67
	Ch-1100	1	15.00	(2.0+3.50)/2	(1.50+1.80+1.20)/3	61.88
					Total Qty =	163.54
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.					
	Ch 100	1	10/0.30		4.00	200.00
					Total Qty =	200.00

(Signature)
28/11/21

Junior Engineer
RWD Works Section
Palasi (Araria)

(Signature)
28/11/21

Assistant Engineer
RWD Works Section
Palasi (Araria)

Executive Engineer
RWD Works Division
Araria

[Signature]
Executive Engineer
RWD Works Division
Araria

[Signature]
Assistant Engineer
RWD Works Section
Palasi (Araria)

[Signature]
Junior Engineer
RWD Works Section
Palasi (Araria)

3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.				1	10.00	3.00		30.00
	Ch 100							Total Qty =	30.00
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-Charge.								
	Ch 100				1	10.00	(0.80+1.20)/2	2.10	21.00
								TOTAL =	21.00
5								Total No. of EC Bags = 21.00X0.034	617.65
								SAY NO OF Bags =	618
	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.								
	Ch-100				1	10.00	3.00	(0.600+0.900)/2	22.50
						10.00	(1.50+1.20+1.0)/3	(0.30+0.60+0.45)/3	5.55
6						20.00	(1.50+2.0)/2	(0.300+0.600)/2	15.75
	Ch 1100				1			Total Qty. =	43.80
6	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.								
					0	2.50		Total Qty. =	0.00
									0.00