



बिहार सरकार

ग्रामीण कार्य विभाग

Rural Works Department, Govt. of Bihar

HEAD-FDR/2245

STATE :- BIHAR

AA COPY

DISTRICT :- Madhubani

CIRCLE :- Darbhanga

BLOCK :- Rajangar

YEAR:- 2021-22

Estimate for Motorable in

**L025- T02 to Ekama
under FDR**

TOTAL LENGTH OF ROAD:-

0.717 KM

TOTAL COST FOR MOTORABLE

Rs. 545467.64

Rs. 326872.00

Submitted by:

Executive Engineer

RWD(W) Division, Madhubani

प्रतिवेदन

पथ का नाम	:-	<u>L025- T02 to Ekama</u>
पथ की लम्बाई	:-	<u>0.717 KM</u>
प्राक्कलित राशि	:-	545468 रु0 <u>326872/-</u>
प्रमंडल का नाम	:-	<u>Madhubani</u>
अंचल का नाम	:-	<u>Darbhangha</u>
योजना का नाम	:-	<u>FDR-2245</u>

प्रस्तुत प्राक्कलन

L025- T02 to Ekama


पथ के लिए तैयार किया गया है जो कि बाढ़ एवं अतिवृष्टि के कारण हुए कटाव/जलजमाव/Wave Cut के कारण क्षतिग्रस्त हो गया था। जिसके कारण आवागमन बाधित हो गया था। फलतः ग्रामीणों को काफी कठिनाईयों का सामना करना पड़ रहा था। यह प्राक्कलन सचिव, ग्रामीण कार्य विभाग, बिहार, पटना के पत्रांक-मु0अ0-4 (मु0) विविध (कार्य) -23-60/2020-1937 पटना दिनांक 07.07.2021 के आलोक में तैयार किया गया है।


इस प्राक्कलन में क्षतिग्रस्त हुए पथांश को ईट के टुकड़ों से भरकर उसका सम्पीडन किया जाने का प्रावधान किया गया है।

प्रस्तुत प्राक्कलन वर्तमान स्वीकृति अनुसूचि दर पर तैयार किया गया है। यह कार्य लोकहित एवं जनहित में अत्यावश्यक है। अतः इस प्राक्कलन की स्वीकृति अपेक्षित है। यह कार्य विभागीय रूप से सम्पादित करा लिया गया है।

प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू अनुसूचित दर पर जो संवेदक लाभांश को छोड़कर था। उसे प्रावधान करते हुए तैयार किया गया है।


29/11/21
कनीय अभियंता


31/11/21
सहायक अभियंता,


01/11/21
कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, मधुबनी

Estimate for Motorable in

L025- T02 to Ekama

Length:- 0.717 KM

SI No	Item No	Name of Item	Unit	No	Length	Width	Height	Qty.	Rate	Amount
1		Providing and filling brick bats in ditches including cost of brick bats and labour all complete job as per specification and direction of E/I.	Cum		As per Appendix 1			137.99 230.27 141.68	2004.96	276664 461685
								Add GST 12%		55402
								Add L.Cess 1%		4617
								S Fee		23764
								G. Total:-		545468
										33200
										2767
										14241
										326872/-

Junior Engineer
RWD(W) Section
Rajangar

Assistant Engineer
RWD(W) Sub Division
Rajangar

Executive Engineer
RWD(W) Division, Madhubani

कार्यपालक अभियंता एवं कार्य समंडल- बिहार के द्वारा
समर्पित जाँच प्रतिवेदन के आधार पर

post facto TIS For Rs 326872/- (Rupees Three
Lakh twenty six Thousand and eight Hundred seventy two)

Superintending Engineer
R.W.D. (W) CIRCLE, DARBHANGA

Inspection Report of Flood Damage work

Name of PIUs:- Madhubani

Name of Block/ Road:- Rajnagar/L022-T02 to Ekkamma

A. For Road

1. Damage Location Chainage:- 0.00 to 0.20 ch - 0.20 to 0.717.

2. Damage Length :- 228.5 m.

3. Nature of Damage :- crest damage and Road cuts.

4. Details of Restoration Works

i. Material being used in Restoration works:- Brick Bat ✓

ii. Equipments's/Tools being used in Restoration works:-

iii. Procedure taken up in Restoration works:- Brick Bat Filling ✓

iv. Restored Length:- 228.5 m

B. For Bridge

1. Damage Location Chainage:-

2. Damage Length :-

3. Nature of Damage :-

N/A

4. Details of Restoration Works

i. Material being used in Restoration works:-

ii. Equipments's/Tools being used in Restoration works:-

iii. Procedure taken up in Restoration works:-

iv. Restored Length:-

Satisfactory.


06/12/21
Signature of JE/AE/EE


Signature
(Name of Inspection)