



बिहार सरकार

ग्रामीण कार्य विभाग

Rural Works Department, Govt. of Bihar

HEAD-FDR/2245

STATE :- BIHAR

DISTRICT :- Madhubani

CIRCLE :- Darbhanga

BLOCK :- Rajangar

YEAR:- 2021-22

AA COPY

Estimate for Motorable in

L053 -T01 TO MADHUBANI TOL  
under FDR

TOTAL LENGTH OF ROAD:-

7.633 KM

TOTAL COST FOR MOTORABLE

Rs. 381337.53

Submitted by:  
Executive Engineer  
RWD(W) Division, Madhubani

## Inspection Report of Flood Damage work

Name of PIUs:- Madhubani

Name of Block/ Road:- Rajnagar/T01 to Madhubani tol

### A. For Road

1. Damage Location Chainage:- 3.600 KM
2. Damage Length :- 17.50 M
3. Nature of Damage :- Road cut flank cut
4. Details of Restoration Works

- i. Material being used in Restoration works:- Brick Bat ✓
- ii. Equipments's/Tools being used in Restoration works:-
- iii. Procedure taken up in Restoration works:- Brick Bat Filling ✓
- iv. Restored Length:- 17.50 M .

### B. For Bridge

1. Damage Location Chainage:-
2. Damage Length :- N/A
3. Nature of Damage :-
4. Details of Restoration Works

- i. Material being used in Restoration works:-
- ii. Equipments's/Tools being used in Restoration works:-
- iii. Procedure taken up in Restoration works:-
- iv. Restored Length:-

Satisfactory.



Signature of JE/AE/EE



Signature  
(Name of Inspection)

## प्रतिवेदन

पथ का नाम	:-	<u>L053 -T01 TO MADHUBANI TOL</u>
पथ की लम्बाई	:-	<u>7.633 KM</u>
प्राक्कलित राशि	:-	381338 रू0
प्रमंडल का नाम	:-	<u>Madhubani</u>
अंचल का नाम	:-	<u>Darbhangha</u>
योजना का नाम	:-	<u>FDR-2245</u>

प्रस्तुत प्राक्कलन L053 -T01 TO MADHUBANI TOL


पथ के लिए तैयार किया गया है जो कि बाढ़ एवं अतिवृष्टि के कारण हुए कटाव/जलजमाव/Wave Cut के कारण क्षतिग्रस्त हो गया था। जिसके कारण आवागमन बाधित हो गया था। फलतः ग्रामीणों को काफी कठिनाईयों का सामना करना पड़ रहा था। यह प्राक्कलन सचिव, ग्रामीण कार्य विभाग, बिहार, पटना के पत्रांक-मु0अ0-4 (मु0) विविध (कार्य) -23-60/2020-1937 पटना दिनांक 07.07.2021 के आलोक में तैयार किया गया है।


Hume pipe


इस प्राक्कलन में क्षतिग्रस्त हुए पथांश को ~~खोद~~ एवं ईट के टुकड़ों से भरकर उसका सम्पीडन किया जाने का प्रावधान किया गया है।

प्रस्तुत प्राक्कलन वर्तमान स्वीकृति अनुसूचि दर पर तैयार किया गया है। यह कार्य लोकहित एवं जनहित में अत्यावश्यक है। अतः इस प्राक्कलन की स्वीकृति अपेक्षित है। यह कार्य विभागीय रूप से सम्पादित करा लिया गया है।

प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू अनुसूचित दर पर जो संवेदक लाभांश को छोड़कर था। उसे प्रावधान करते हुए तैयार किया गया है।

  
22/07/21  
कनीय अभियंता

  
22/07/21  
सहायक अभियंता,

  
22/07/21  
कार्यपालक अभियंता,  
ग्रामीण कार्य विभाग,

**Estimate for Motorable in**

**L053 -T01 TO MADHUBANI TOL**

Length:- 7.633 KM

Sl No	Item No	Name of Item	Unit	No	Length	Width	Height	Qty.	Rate	Amount
		Providing and filling brick bats in ditches including cost of brick bats and labour all complete job as per specification and direction of E/I.	Cum	As per Appendix 1				<del>134.42</del> 122.43	2004.96	<del>245467=</del> 269507
		Laying Cement Concrete Pipe NP3 (burried conduits) on first class bedding of granular material including fixing collar with cement sand mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry work in head wall and parapets. (1000 mm dia)	mtr.	As per Appendix 1				7.50	6932.04	51990
									Add GST 12%	38580
									Add L.Cess 1%	3215
									S Fee	18046
									G. Total:-	381338

297457=00  
35695=00  
2975=00  
12635=00  
348762=00

*[Signature]*  
29/10/21  
Junior Engineer  
RWD(W) Section  
Rajangar

*[Signature]*  
29/10/21  
Assistant Engineer  
RWD(W) Sub Division  
Rajangar

*[Signature]*  
30/10/21  
Executive Engineer  
RWD(W) Division, Madhubani

कार्यपालक अल्पिकर, ग्रां काठ वि, कार्य प्रामुख - विरोल के द्वारा समष्टि जौल प्रतिवेदन के आयात पर -

Post-Facto T/S for Rs 3,48,762=00 (Rupees three lacs forty eight thousand seven hundred sixty two) only.

*[Signature]*  
29/10/21  
Superintending Engineer  
RWD Works Circle, Darbhanga