



बिहार सरकार

ग्रामीण कार्य विभाग

Rural Works Department, Govt. of Bihar

HEAD-FDR/2245

STATE :- BIHAR

AA COPY

DISTRICT :- Madhubani

CIRCLE :- Darbhanga

BLOCK :- Rajangar

YEAR:- 2021-22

Estimate for Motorable in

Rampatti Hat to Kaithahi
under FDR

TOTAL LENGTH OF ROAD:-

1.429 KM

TOTAL COST FOR MOTORABLE

Rs. 715158.75

Submitted by:
Executive Engineer
RWD(W) Division, Madhubani

प्रतिवेदन

पथ का नाम	:—	<u>Rampatti Hat to Kaithahi</u>
पथ की लम्बाई	:—	<u>1.429 KM</u>
प्राक्कलित राशि	:—	715159 रु0
प्रमंडल का नाम	:—	<u>Madhubani</u>
अंचल का नाम	:—	<u>Darbhanga</u>
योजना का नाम	:—	<u>FDR-2245</u>

प्रस्तुत प्राक्कलन Rampatti Hat to Kaithahi पथ के लिए तैयार किया गया है जो कि बाढ़ एवं अतिवृष्टि के कारण हुए कटाव/जलजमाव/Wave Cut के कारण क्षतिग्रस्त हो गया था। जिसके कारण आवागमन बाधित हो गया था। फलतः ग्रामीणों को काफी कठिनाईयों का सामना करना पड़ रहा था।

यह प्राक्कलन सचिव, ग्रामीण कार्य विभाग, बिहार, पटना के पत्रांक—मु0अ0—4 (मु0) विविध (कार्य) —23—60/2020—1937 पटना दिनांक 07.07.2021 के आलोक में तैयार किया गया है।


इस प्राक्कलन में क्षतिग्रस्त हुए पथांश को ईट के टुकड़ों से भरकर उसका सम्पीडन किया जाने का प्रावधान किया गया है।

प्रस्तुत प्राक्कलन वर्तमान स्वीकृति अनुसूचि दर पर तैयार किया गया है। यह कार्य लोकहित एवं जनहित में अत्यावश्यक है। अतः इस प्राक्कलन की स्वीकृति अपेक्षित है। यह कार्य विभागीय रूप से सम्पादित करा लिया गया है।

प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू अनुसूचित दर पर जो संवेदक लाभांश को छोड़कर था। उसे प्रावधान करते हुए तैयार किया गया है।


29.10.21.
कनीय अभियंता


31/10/21
सहायक अभियंता,



31/10/21
कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, मधुबनी

Estimate for Motorable in

Rampatti Hat to Kaithahi

Length:- 1.429 KM


Sl No	Item No	Name of Item	Unit	No	Length	Width	Height	Qty.	Rate	Amount
1		Providing and filling brick bats in ditches including cost of brick bats and labour all complete job as per specification and direction of E/I.	Cum		As per Appendix 1			301.91 261.87	2004.96	525039.00 605311
									Add GST 12%	72637 63005=0
									Add L.Cess 1%	6053 5250=0
									S Fee	31157 27025=0
									G. Total:-	715159 620,319=0


29.10.21
Junior Engineer
RWD(W) Section
Rajangar


31/10/21
Assistant Engineer
RWD(W) Sub Division
Rajangar


31/10/21
Executive Engineer
RWD(W) Division, Madhubani

कार्यपालक अभियन्ता- ग्राहक विभाग प्रमखन - बिरोन
के द्वारा समर्पित जॉय प्रविष्टि के आयात नए -
Post- Fecto T/S for Rs 6,20,319=00 (Rupees-
Six lacs twenty thousand three hundred
nineteen only).


18/11/22
Superintending Engineer
RWD Works Circle, Darbhanga

Inspection Report of Flood Damage work

Name of PIUs:- Madhubani

Name of Block/ Road:- Rajnagar/Rampatti Hat to Kaithahi ✓

A. For Road

1. Damage Location Chainage:- 0.504 to 1.40 Km.

2. Damage Length :- 253.00

3. Nature of Damage :- cuts and damage.

4. Details of Restoration Works

i. Material being used in Restoration works:- Brick Bat ✓

ii. Equipments's/Tools being used in Restoration works:-

iii. Procedure taken up in Restoration works:- Brick Bat Filling ✓

iv. Restored Length:- 253

B. For Bridge

1. Damage Location Chainage:-

2. Damage Length :-

3. Nature of Damage :-

N/A

4. Details of Restoration Works

i. Material being used in Restoration works:-

ii. Equipments's/Tools being used in Restoration works:-

iii. Procedure taken up in Restoration works:-

iv. Restored Length:-

Found Satisfactory.

[Signature]
06/12/24

Signature of JE/AE/EE

[Signature]
Signature
(Name of Inspection)