



बिहार सरकार
ग्रामीण कार्य विभाग
Rural Works Department, Govt. of Bihar

HEAD-FDR/2245

STATE :- BIHAR

DISTRICT :- Madhubani

CIRCLE :- Darbhanga

BLOCK :- Rajangar

YEAR:- 2021-22

Estimate for Motorable in

**Lalu Gupta House to Mangarpatti-Pilakhwar REO Road
under FDR**

TOTAL LENGTH OF ROAD:-

5.195 KM

TOTAL COST FOR MOTORABLE

Rs. 335329.10

Submitted by:
Executive Engineer
RWD(W) Division, Madhubani

प्रतिवेदन

पथ का नाम	:-	<u>Lalu Gupta House to Mangarpatti-Pilakhwar REO Road</u>
पथ की लम्बाई	:-	<u>5.195 KM</u>
प्राक्कलित राशि	:-	335329 रु०
प्रमंडल का नाम	:-	<u>Madhubani</u>
अंचल का नाम	:-	<u>Darbhanga</u>
योजना का नाम	:-	<u>FDR-2245</u>

प्रस्तुत प्राक्कलन Lulu Gupta House to Mangarpatti-Pilakhwar REO Road पथ के लिए तैयार किया गया है जो कि बाढ़ एवं अतिवृष्टि के कारण हुए कटाव/जलजमाव/Wave Cut के कारण क्षतिग्रस्त हो गया था। जिसके कारण आवागमन बाधित हो गया था। फलतः ग्रामीणों को काफी कठिनाईयों का सामना करना पड़ रहा था।

यह प्राक्कलन सचिव, ग्रामीण कार्य विभाग, बिहार, पटना के पत्रांक-मु०अ०-4 (मु०) विविध (कार्य) -23-60/2020-1937 पटना दिनांक 07.07.2021 के आलोक में तैयार किया गया है।

Mune pipe देकर

इस प्राक्कलन में क्षतिग्रस्त हुए पथांश को ~~बिछो~~ एवं ईट के टुकड़ों से भरकर उसका सम्पीडन किया जाने का प्रावधान किया गया है।

प्रस्तुत प्राक्कलन वर्तमान स्वीकृति अनुसूचि दर पर तैयार किया गया है। यह कार्य लोकहित एवं जनहित में अत्यावश्यक है। अतः इस प्राक्कलन की स्वीकृति अपेक्षित है। यह कार्य विभागीय रूप से सम्पादित करा लिया गया है।

प्रस्तुत प्राक्कलन संपादित कार्य के समय लागू अनुसूचित दर पर जो संवेदक लाभांश को छोड़कर था। उसे प्रावधान करते हुए तैयार किया गया है।

[Signature]
23.10.21.

कनीय अभियंता

[Signature]
31/10/21

सहायक अभियंता,

[Signature]
31/10/21

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमण्डल, मधुबनी

Estimate for Motorable in

Lalu Gupta House to Mangarpatti-Pilakhwar REO Road

Length:- 5.195 KM

Sl No	Item No	Name of Item	Unit	No	Length	Width	Height	Qty.	Rate	Amount
1		Providing and filling brick bats in ditches including cost of brick bats and labour all complete job as per specification and direction of E/I.	Cum	As per Appendix 1				106.14 90.659	2004.96	181756 = 0 212812
2		Laying Cement Concrete Pipe NP3 (buried conduits) on first class bedding of granular material including fixing collar with cement sand mortar 1:2 but excluding excavation, protection works, backfilling, concrete and masonry work in head wall and parapets. (1000 mm dia)	mtr.	As per Appendix 1				10.00	6932.04	69320
										251076 = 0
								Add GST 12%		-33856 30129 = 0
								Add L.Cess 1%		-2821 2511 = 0
								S Fee		-16519 9355 = 0
								G. Total:-		335329

[Signature]
29.10.21.

Junior Engineer
RWD(W) Section
Rajangar

[Signature]
29/10/21
Assistant Engineer
RWD(W) Sub Division
Rajangar

[Signature]
29/10/21
Executive Engineer
RWD(W) Division, Madhubani

293,071 = 0

कार्मपासक इन्जिनियर मास्कार वि० कार्म प्रमपुल- विरेम
के दूर। समर्पित जॉय प्रतिकेन के आवाज -
Post-Facto T/S for Rs 293,071 = 0 (Rupees -
Two lacs ninety three thousand seventy one only -

[Signature]
Superintending Engineer
RWD Works Circle, Darbhanga

Inspection Report of Flood Damage work

Name of PIUs:- Madhubani

Name of Block/ Road:- Rajnagar/Lalu Gupta House to Mangarpatti Pilakhwar REO road

A. For Road

1. Damage Location Chainage:- 2.200
2. Damage Length :- 11.80 m
3. Nature of Damage :- Damage of Crust & Embankment
4. Details of Restoration Works
 - i. Material being used in Restoration works:- Brick Bats
 - ii. Equipments's/Tools being used in Restoration works:-
 - iii. Procedure taken up in Restoration works:- Brick Bat Filling
 - iv. Restored Length:- 11.80 m

B. For Bridge

1. Damage Location Chainage:-
2. Damage Length :-
3. Nature of Damage :-
4. Details of Restoration Works
 - i. Material being used in Restoration works:-
 - ii. Equipments's/Tools being used in Restoration works:-
 - iii. Procedure taken up in Restoration works:-
 - iv. Restored Length:-

Satisfactory

Signature of JE/AE/EE

Signature
(Name of Inspection).