

Name of Road:- Dankatta to Karhara

Block : BENIPATTI District: MADHUBANI

Length : 4.092 KM

Sr No.	Item	Item of Work	Nos	Length (M)	Width (M)	Depth (M)	Quantity	Unit	Rate	Amount
1	1.1	Labour for lying dry graded Jhama khoa or Stone filter under Brick pitching or Boulder Pitching in slope or apron including light ramming etc. all complete as per approved design, specification and direction of E/I								
		CH-1.000 KM	1	28.93 30.00	3.75+3.05	0.45	50.625			
		CH-1.000 KM	1	10.00	3.75	0.30	11.250			
		CH-1.700 KM	1	3.00	1.00	0.30	0.900			
		CH-1.720 KM	1	1.00	1.00	0.30	0.300			
		CH-1.750 KM	1	1.50	3.00	0.30	1.350			
		CH-2.000 KM	6	1.00	1.00	0.30	1.800			
		CH-2.100 KM	1	1.00	1.00	0.30	0.300			
		CH-2.400 KM	1	2.00	1.00	0.30	0.600			
		CH-2.450 KM	1	5.00	3.75	0.30	5.625			
		CH-3.000 KM	1	3.00	2.00	0.30	1.800			
							74.550	Cum	1939.93	139919.00

[Signature]
JE
RWD BENIPATTI

[Signature]
AE
RWD BENIPATTI

72.12% Add GST 12% Rs= 17355
Add Labour Cess 1% Rs= 1445
Add Signorage Fee (50-025x1032x10%) Rs= 7626
Total Rs= 171049
72.12%
167907
13597
74437
165551.00
m-1/1/11
EE 30/11/21
RWD BENIPATTI

check & verified

[Signature]
20.12.2021
SC

[Signature]
20/12/2021
A.E.

[Signature]
20/12/21
E.E.

Post facto T/E awarded for Rs. 165551.00 (Rs One lac Sixty five thousand five hundred fifty one only.)
Reference Letter no. 233 dated 21/2/22
of E.E. Darbhanga-2

[Signature]
Superintending Engineer
RWD Works Circle, Darbhanga

(10)

Inspection Report for Flood Damaged Work in the year 2021-22

Date of Inspection :- 20-12-2021 Name of PIU :- RWD (W) Div. Dharbhanga 2

Name of Block :- Benipatti

Name of Road :- Bankatta to Karhara Road

For Road :-

1. Damage Location/ Chainage :- 1.00 KM to 3.00 KM

2. Damage Length :- ~~61.45 Mtr~~ 61.45 Mtr

3. Nature of Damage :- pot patch

4. Details of Restoration Works :-


i. Material being used in Restoration Works Brick bats


ii. Equipment's/ Tools being used in Restoration Works Tractor & Roller

iii. Procedure taken up in Restoration Works Filling & compaction

iv. Restored Length 61.45 Mtr

Remarks :- Works found satisfactory


20.12.21
Signature of JE/AE


20/12/21
Signature of E.E