

24 Name of Road: LOS8 to Bishanpur

Block : BENIPATTI District: MADHUBANI

Length : 2.21 KM

Sr No.	Item	Item of Work	Nos	Length (M)	Width (M)	Depth (M)	Quantity	Unit	Rate	Amount
1	1.1	Construction of embankment with approved material obtained from borrow pit lift up to 1.5 mtr. all complete job dir of E/I								
					(3.5+4.5)/2	(1+0.8)/2				
		CH-0.200 KM	1	15.00 21.00	4.00	0.90	54.00 75.60			
					(3.5+4.5)/2	(0.4+0.6)/2				
		CH-1.000 KM	5	4.0 20.00	4.00	0.50	55.00 40.00			
					(3.5+4.5)/2	(0.7+0.8)/2				
		CH-1.500 KM	1	13.00	4.00	0.75	39.00			
						Total	123.60 154.60	Cum	215.849	33370.00
1	1.1	Labour for lying dry graded jhama khoa or Stone filter under Brick pitching or Boulder Pitching in slope or apron including light ramming etc. all complete as per approved design, specification and direction of E/I								
						0.45+30	16.875 22.00			
		CH-0.200 KM	1	15.00 20.00	3.00					
					(3+4)/2	(1.2+1)/2				
		CH-1.000 KM	1	21.00	3.50	1.10+60	62.775 80.85			
					(3+4)/2	(0.6+0.9)/2				
		CH-1.500 KM	1	15.00	3.50+30	0.75+50	24.375 39.38			
						Total	147.23	Cum	1939.93	285616.00

Total Rs= 318986.00
 Add GST 12% Rs= 22884.70
 Add Labour Cess 1% Rs= 3189.86
 Add Signorage Fee (154.60x157.5x10%) Rs= 2427.00
 Add Signorage Fee (147.23x1032x10%) Rs= 15194.00
 Total Rs= 378075.00

JE
 RWD BENIPATTI

AE
 RWD BENIPATTI

EE
 RWD BENIPATTI

check & verified

20.12.2021
 JE

20/12/2021
 AE

20/12/21
 EE

post facto T/F awarded for Rs. 261908.00 (Rs) Two Lac
 Sixty one thousand nine hundred eight only.
 Reference Letter no. 233 dated 21/2/22
 of EE darbhanga-2

Superintending Engineer
 RWD Works Circle, Darbhanga
 21/2/22

(15)

Inspection Report for Flood Damaged Work in the year 2021-22

Date of Inspection :- 20/12/21 Name of PIU :- RWD (W) Div. Darbhanga-2
Name of Block/PIU :- Benipatti (RWD (W) Div Benipatti)
Name of Road :- LOSB to Bishanpur
For Road :-

1. Damage Location/ Chainage :- 0.200km, 1.00km, 1.5km
2. Damage Length :- 51m
3. Nature of Damage :- Breaches and pot holes due to flood.

4. Details of Restoration Works :-

- i. Material being used in Restoration Works Earthwork & Brick Bats
- ii. Equipment's/ Tools being used in Restoration Works Tractor & Roller
- iii. Procedure taken up in Restoration Works filling and compaction.
- iv. Restored Length 51m.

Remarks :-

Sect's Factory.

[Signature]
20/12/21
Signature of E.E

[Signature]
20.12.21
Signature of JE/AE