

Name of Road: TOS to Chandpura

Block : BENIPATTI District: MADHUBANI

Length : 3.104 KM

Sr No.	Item	Item of Work	Nos	Length (M)	Width (M)	Depth (M)	Quantity	Unit	Rate	Amount
1	1.1	Labour for lying dry graded jhama khoa or Stone filter under Brick pitching or Boulder Pitching in slope or apron Including light ramming etc. all complete as per approved design, specification and direction of E/I								
		CH-0.750 KM	1	15	2.50	0.20	7.500			
		CH-0.750 KM	1	7.50	3.00	0.30	6.750			
						Total	14.250	CUM	1939.93	27644.00

Add GST 12% Rs= 3317.00

Add Labour Cess 1% Rs= 276.00

Add Signorance Fee (14.25x1032x10%) Rs= 1471.00

Total Rs= 32708.00

[Signature]
JE
6/11/21
RWD BENIPATTI

[Signature]
AE
16/11/21
RWD BENIPATTI

[Signature]
EE
16-11-21
RWD BENIPATTI

[Signature]
Chief Engineer

[Signature]
20.12.2021
D.G

[Signature]
20/12/2021
A.E.

[Signature]
20/12/21

Post facto T/S accorded for Rs. 32708.00 (Thirty two thousand Seven hundred Eight only.)
Reference Letter no. 233 dated 21/2/22 of EE darbhanga-2

[Signature]
Superintending Engineer
RWD Works Circle, Darbhanga
21/2/22


22


Inspection Report for Flood Damaged Work in the year 2021-22

Date of Inspection :- 20-12-2021 Name of PIU :- RWD (W) Div. ~~Beni~~ Darbhanga 2
Name of Block / PIU :- Benipatti (RWD (W) Div Benipatti)
Name of Road :- To 5 to Chandpura Road
For Road :-

1. Damage Location/ Chainage :- 0.750 KM
2. Damage Length :- 22.50 Mtr
3. Nature of Damage :- Breaches
4. Details of Restoration Works :-
 - i. Material being used in Restoration Works Brick bats
 - ii. Equipment's/ Tools being used in Restoration Works Tractor & Roller
 - iii. Procedure taken up in Restoration Works Filling & compaction
 - iv. Restored Length 22.50 Mtr

Remarks :- Works found satisfactory


20.12.21
Signature of JE/AE


20/12/21
Signature of E.E