

me of Road:- L039 to South
ishanpur

Block : BENIPATTI District: MADHUBANI Length : 1.613 KM

Sr No.	Item	Item of Work	Nos	Length (M)	Width (M)	Depth (M)	Quantity	Unit	Rate	Amount
1	1.1	Labour for lying dry graded jhama khoa or Stone filter under Brick pitching or Boulder Pitching in slope or apron Including light ramming etc. all complete as per approved design, specification and direction of E/I								
			1	15.00	(5.5+3.75)/2	$\frac{4+6}{2}$ (0.5+0.7)/2	24.67			
		CH-0.700 KM	1	30.00 10.00	4.63	0.60	83.250 27.75			
					(1.2+1.5)/2					
		CH-0.100 KM	1	12.00	1.35	0.15	2.430			
							85.080	Cum	1939.93	166213.00

Add GST 12% Rs= 19946.00
 Add Labour Cess 1% Rs= 1662.00
 Add Signorage Fee (85.68x1032x10%) Rs= 8842.00
 Total Rs= 196663.00

JE
 RWD BENIPATTI

AE
 RWD BENIPATTI

EE
 RWD BENIPATTI

20.12.2021
 S.G

20/12/2021
 A.E.

20/12/21
 E.E

Post facto T/S awarded for Rs. 148951.00 (Rs. One
 Lakh forty eight thousand nine hundred fifty one only.)
 Reference Letter no. 233 dated 21/2/22.
 of EE Darbhanga-2

Superintending Engineer
 RWD Works Circle, Darbhanga

(19)

Inspection Report for Flood Damaged Work in the year 2021-22

Date of Inspection :- 20.12.21 Name of PIU :- RWD (W) Div. Darbhanga-2
Name of Block/PU :- Benipatti (RWD(W) Div Benipatti)
Name of Road :- L039 to South Bishanpur.
For Road :-

1. Damage Location/ Chainage :- 0.100 to 700 km.

2. Damage Length :- 37 Mtr

3. Nature of Damage :- Pots due to Flood.

4. Details of Restoration Works :-

i. Material being used in Restoration Works :- Brick bats.

ii. Equipment's/ Tools being used in Restoration Works :- Tractors.

iii. Procedure taken up in Restoration Works :- Filling & compaction.

iv. Restored Length :- 37.00 Mtr Restored Qty :- 64.893 m³.

Remarks :- Work found satisfactory.

[Signature]
20.12.21
Signature of JE/AE

[Signature]
20/12/21
Signature of E.E