

Road: Arer To Nagwas

Block: BENIPATTI

District: MADHUBANI

Length: 9.200 KM

Item	Item of Work	Nos	Length (M)	Width (M)	Depth (M)	Quantity	Unit	Rate	Amount
1	1.1	Labour for lying dry graded jhama khoa or Stone filter under Brick pitching or Boulder Pitching in slope or apron Including light ramming etc. all complete as per approved design, specification and direction of E/I							
	CH-00.800 KM	1	6	3.50	0.30	6.30			
	CH-00.800 KM	1	2.50	2.00	0.15	0.75			
	1.000 KM	1	2.50	5.00	0.30	3.75			
	1.200 KM	1	2.50	5.00	0.30	3.75			
	1.500 KM	1	2.50	2.00	0.30	1.50			
	1.800 KM	1	5.00	3.00	0.15	2.25			
	1.800 KM	1	8.00	3.00	0.30	7.20			
	2.400 KM	5	5.00	2.50+2.3	0.30	18.00			
	2.400 KM	2	7.00	2.50	0.30	10.50			
	2.800 KM	10	2.00	2.50+2.3	0.30	15.00			
	3.100 KM	1	5.00	2.00	0.15	1.50			
	3.200 KM	1	3.00	3.00	0.30	2.70			
	3.300 KM	1	5.00	2.50	0.30	3.75			
	3.300 KM	2	4.00	2.50	0.30	6.00			
	3.400 KM	2	4.00	2.50	0.30	6.00			
	3.700 KM	2	2.00	2.50	0.30	3.00			
	4.000 KM	1	5.00	2.50+2.2	0.30	3.75			
	4.100 KM	1	6.00	1.50	0.30	2.70			
	4.200 KM	1	1.50	3.00	0.30	1.35			
	4.700 KM	1	5.00	3.00	0.30	4.50			
	4.800 KM	1	5.00	2.00	0.15	1.50			
	4.900 KM	1	7.00	2.50	0.30	5.25			
	5.600 KM	1	5.00	3.00	0.30	4.50			
						116.25	CUM	1939.93	225518.00

221733.00

114.3 Add GST 12% Rs= 27062.00 266082
 Add Labour Cess 1% Rs= 2255.00 23172
 Add Signorage Fee (116.25x1032x10%) Rs= 11997.00 117962
 114.3 Total Rs= 266832.00

70-19-262355

[Signature]
 JE
 RWD BENIPATTI

[Signature]
 AE
 RWD BENIPATTI

[Signature]
 EE
 RWD BENIPATTI

check & verified

[Signature]
 20/11/21
 EE

[Signature]
 20.12.2021
 5.6

Post paid ST/S for Rs 262354.00 (Rs. Two Lacs Sixty two thousand three hundred fifty four only) Reference Letter no 28 dated 21/2/22 of EE Darbhanga-2

[Signature]
 Superintending Engineer
 RWD Works Circle, Darbhanga

23

Inspection Report for Flood Damaged Work in the year 2021-22


Date of Inspection :- 20.12.21 Name of PIU :- RWD (W) Div. Darbhanga.2
Name of Block :- BENI PATTI
Name of Road / PIU :- ARER TO NAGWAS (RWD (W) Div Benipatti)
For Road :-


1. Damage Location/ Chainage :- CH 0.800km to 5.600km
2. Damage Length :- 139.5m
3. Nature of Damage :- Breached due to flood

4. Details of Restoration Works :-

- i. Material being used in Restoration Works : Brick Bats
- ii. Equipment's/ Tools being used in Restoration Works : Tractor & Roller
- iii. Procedure taken up in Restoration Works : Filling and compaction
- iv. Restored Length : 139.5m

Remarks :- Work found Satisfactory


20/12/21
Signature of E.E


20.12.21
Signature of JE/AE