

Improvement of Road
on Pall S.H (REO Missing Link) Road
to Baingara Road

Block : BENIPATTI


District: MADHUBANI


Length : 9.400 KM

Sr No.	Item	Item of Work	Nos	Length (M)	Width (M)	Depth (M)	Quantity	Unit	Rate	Amount
1	1.1	Labour for laying dry graded Jhama khoa or Stone filter under Brick pitching or Boulder Pitching in slope or apron including light ramming etc. all complete as per approved design, specification and direction of E/I								
		CH-1.200 KM	1	4.4 40.00	4.50+3.5/2	0.50+1.1/2	88.40 125.000			
		CH-1.450 KM	1	1.50	0.50	0.30	0.225			
		CH-1.50 KM	1	3.00	1.60	0.40	1.920			
		CH-3.200 KM	1	2.50	0.90	0.15	0.338			
		CH-4.600 KM	1	3.90	2.70	0.20	2.106			
			1	0.90	1.50	0.15	0.203			
			1	14.80	1.60	0.15	3.552			
			1	7.00	1.20	0.15	1.260			
			3	0.50	0.50	0.15	0.113			
			2	1.20	0.60	0.15	0.216			
			1	8.40	2.00	0.30	5.040			
			1	8.00	0.50	0.20 0.25	1.60 1.000			
			1	5.00	1.20	0.20	1.200			
			1	20.00	3.75	0.30	22.500			
		CH-7.900 KM	1	11.50	3.75 4.00	0.40	18.400			
			1	17.00	3.75+2.5/2 4.50	0.25	13.281 20.125			
		CH-8.200 KM	1	11.00	1.5+1.60/2 2.50	0.30+1.17 1.235	2.71 13.550			
			1	10.00	2.90	0.25	7.250			
							220.997	Cum	1939.93	328457.00 448117

Rs. 169.314 Add GST 12% Rs= 59774 39415
m Add Labour Cess 1% Rs= 1481 3285
Add Signorage Fee (85-69x1032x10%) Rs= 23631 17478
169.314 Total Rs= 530003
5,28,630.2



JE
RWD BENIPATTI


AE
RWD BENIPATTI


EE
RWD BENIPATTI


20.12.2021


20/12/2021
A.E.


20/12/21
E.E.


D... inspec...

Name of Road :- Improvement of Road from
Pali SH (RE missing link) Road To Balgrs
Road.

~~Reference Letter no 233 dated 21/2/22~~

Post-facto T/S awarded for Rs 388630.00
(Rs Three Lacs Eighty eight thousand 800
hundred thirty only.)

Reference Letter no. 233 dated 21/2/22
of E.E. darbhanga-2


Superintending Engineer
RWD Works Circle, Darbhanga


(12)

Inspection Report for Flood Damaged Work in the year 2021-22

Date of Inspection :- 20/11/2021 Name of PIU :- RWD (W) Div. Daarbhanga-2

Name of Block :- Benipatti

Name of Road :- Pali S.H (RED Missing Link) Road to Baingra road.

For Road :-

1. Damage Location/ Chainage :- 1.2km, 1.450km, 1.5km, 3.2 km, 4.6 km & 7.5 km and 8.2 km
2. Damage Length :- 175.2 m.
3. Nature of Damage :- Breaches and Potholes due to flood.

4. Details of Restoration Works :-

- i. Material being used in Restoration Works Brick-Bats
- ii. Equipment's/ Tools being used in Restoration Works Tractor and Roller
- iii. Procedure taken up in Restoration Works Filling & compaction
- iv. Restored Length 175.2 m.

Remarks :- Satisfactory.

[Signature]
20.12.21
Signature of JE/AE

[Signature]
20/12/21
Signature of E.E