

N.H.-52 Benipatti
Ambedkar
Chauk(Sona cinema)
To Prakhanda
Mukhayalay Tak

Name of Road:

Block : BENIPATTI

District: MADHUBANI

Length : 2.000 KM

Sr No.	Item	Item of Work	Nos	Length (M)	Width (M)	Depth (M)	Quantity	Unit	Rate	Amount
1	1.1	Labour for lying dry graded Jhama khoa or Stone filter under Brick pitching or Boulder Pitching in slope or apron including light ramming etc. all complete as per approved design, specification and direction of E/I								
		CH 0. to 0.200 Km	1	10.60	4.60 4.4 ^{4.4}	0.60	28.62 29.256			
			1	8.30	2.30	0.45	8.591			
			1	7.00	1.20	0.50	4.200			
			1	4.60	3.40	0.45	7.038			
			1	30.00 29.80	3.75 3.65 ^{3.65}	0.50	53.29 56.250			
			1	1.50	2.00	0.45	1.350			
			1	1.50	2.00	0.35	1.050			
			1	8.20	1.70	0.30	4.182			
						Total	111.917	Cum	1939.93	217110.13

108.321

Add GST 12% Rs=

26053.22

Add Labour Cess 1% Rs=

2171.10

Add Signorage Fee (111.917x1032x10%) Rs=

11549.78

108.321

Total Rs=

25684.28

252162
21012
111292
2486312

[Signature]
20/11/21

JE
RWD BENIPATTI

[Signature]
20/11/21

AE
RWD BENIPATTI

[Signature]
20/11/21

EE
RWD BENIPATTI

check & verified

[Signature]
20/12/21
G.E

[Signature]
20.12.2021
S.E

[Signature]
20/12/2021
A.E.

108.321 Acrued for Rs. 248631.00 (Twenty four thousand eight hundred sixty three only.) (Rs) Two lac forty eight thousand six hundred thirty one only.
Reference letter no. 233 dated 21/2/22
of E.E darbhanga-2

Superintending Engineer
RWD Works Circle, Darbhanga

21/2/22

(14)

Inspection Report for Flood Damaged Work in the year 2021-22

Date of Inspection :- 20.12.21 Name of PIU :- RWD (W) Div. Dankhanga-2
Name of Block :- BENIPATTI
Name of Road :- NH 52 BENIPATTI AMBEDKAR CHAUK TO
PRAKHAND NUKHALAY TAK
For Road :-

1. Damage Location/ Chainage :- From CH- 0.00km to 0.200km
2. Damage Length :- 70.9m
3. Nature of Damage :- Pot holes and Breaches due to flood
4. Details of Restoration Works :-
 - i. Material being used in Restoration Works : Brick Bats
 - ii. Equipment's/ Tools being used in Restoration Works : Tractor and Roller
 - iii. Procedure taken up in Restoration Works : Filling and Compaction
 - iv. Restored Length : 70.9m

Remarks :- Work found Satisfactory

20.12.21
Signature of JE/AE

20/12/21
Signature of E.E