



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

DETAILED PROJECT REPORT FOR MOTRABLE REPAIRING OF ROAD

F.D.R. PART - MOTRABLE RESTORATION

KAPSULBARI TO DHAR TOLA DAMDAMA

DETAILED ESTIMATE OF F.D.R. MOTRABLE REPAIRING ROAD

ROAD LENGTH	0 TO 0	
DISTRICT	PURNEA	
BLOCK	KASBA	
DIVISION	PURNEA	
TOTAL LENGTH OF ROAD	0.000	KM
TOTAL COST OF F.D.R. PART - A	Rs. 13.978	Lacs
ADD G.S.T @ 12%	Rs. 1.677	Lacs
ADD Labour Cess @ 1%	Rs. 0.140	Lacs
ADD Seigniorage Fee @ 10%	Rs. 0.935	Lacs
TOTAL COST OF RESTORATION WORK In Rs.	Rs. 16.730	Lacs

SUBMITTED BY
The Executive Engineer,
Works Division, Purnea

GENERAL ABSTRACT OF COST FOR MAINTENANCE OF ROAD

NAME OF ROAD : KAPSULBARI TO DHAR TOLA DAMDAMA
DISTRICT : PURNEA
DIVISION : PURNEA
BLOCK : KASBA
LENGTH OF ROAD (IN KM) : 0.000

Sl. No.	ITEM OF WORK	AMOUNT (LAKHS)
1	EARTH WORK	6.014
2	HUME PIPE	0.000
3	BRIKCK BAT	0.000
4	SAND BAGS	7.964
5	BAMBOO WORK	0.000
6	STEEL DRUM SHEET	0.000
TOTAL COST OF PROJECT =		13.978
Add G.S.T. @ 12%		1.677
Add Labour Cess @ 1%		0.140
Add Seigniorage Fee @ 10%		0.935
Total Cost of Restoration Work =		16.730

[Signature]
14/11/21
J.E.
RWD

[Signature]
14/11/21
A.E.
RWD

[Signature]
14/11/21
E.E.
RWD

Provisional Technical Sanction for Rs 16.730 Lacs
(Rupees Sixteen Lacs Seventy three thousand) only.

[Signature]
10.1.22

KAPSULBARI TO DHAR TOLA DAMDAMA

SL No.	SDB SL NO	MORD Ref.No	Description	Unit	NOS	LENGTH	WIDTH	HEIGHT	QUANTITY	RATE	AMOUNT (in Rs.)
1	3.3	301.5	EARTH WORK								
			Construction of Embankment with approved material obtained from borrow pits with a lift upto 1.5 m transporting to site, spreading grading to required slope and compacting to meet requirement of Table 300.1 and 300.2 with a lead of 1000 m as per Technical								
			C/O To ANNEXURE "B"								
				Cum					1648.52		
3	10.7.40 WRD		Labour for Sand filling in Cement Bag, swing and laying materials.						1648.52	364.81	601396.58
			$1 \times 20 \times (0.50 + 4.0) / 2 \times (2.5)$						112.500		
			$1 \times 195 \times (0.50 + 4.0) / 2 \times (2.00)$						877.500		
			1 Sand Bag = 0.034 Cum Sand	Bag					29118.000	27.351	796406.42
									Total Cost fo Flood Protective work (In Rs.) =		1397803.00
									Total Cost fo Flood Protective work (In Lakh) =		13.978

Dec 24/11/21

JE.

24/11/21
A.E.

24/11/21
E.E.



KAPSI LBARI TO DHAR TOLA DAMDAMA

ANNEXURE "B"

S. No.	Channel No.	Length (in mt.)	Top Width (in mt.)	Top Width + Bottom Width $\div 2$	Height (in mt.)	Qty. (in Cum)	Remarks
1	20.00	1.50	$(1.50+4.0)\div 2$	$(2.10+3.40+2.0)\div 3$		137.50	
1	30.00	$(1.20+1.30)\div 2$	$(1.25+4.17)\div 2$	$(2.40+3.75+2.60)\div 3$		237.13	
1	30.00	$(1.10+1.50)\div 2$	$(1.30+4.30)\div 2$	$(2.50+3.65+2.85)\div 3$		252.00	
1	30.00	$(1.20+1.30)\div 2$	$(1.25+4.18)\div 2$	$(2.60+3.50+2.70)\div 3$		238.92	
1	30.00	$(1.20+1.30)\div 2$	$(1.25+4.32)\div 2$	$(2.90+3.65+2.65)\div 3$		256.22	
1	30.00	$(1.20+1.30)\div 2$	$(1.25+4.17)\div 2$	$(2.40+3.75+2.60)\div 3$		237.13	
1	30.00	$(1.20+1.30)\div 2$	$(1.25+4.02)\div 2$	$(2.55+3.0+2.75)\div 3$		218.71	
1	10.00	$(1.20+1.30)\div 2$	$(1.25+3.97)\div 2$	$(2.60+2.70+2.85)\div 3$		70.91	
Total=						1648.52	

[Signature]
J.E.

[Signature]
A.E.

[Signature]
A.E.

निरीक्षण प्रतिवेदन

अधीक्षण अभियंता, ग्रामीण कार्य विभाग, कार्य अंचल पूर्णियाँ के पत्रांक 1361 दिनांक 20.11.2021 में दिये गये निर्देश के आलोक में दिनांक 30.11.2021 से दिनांक _____ तक ग्रामीण कार्य विभाग, कार्य अंचल पूर्णियाँ अन्तर्गत ग्रामीण कार्य विभाग, कार्य प्रमंडल पूर्णियाँ, में कसबा, जलारगढ़, श्रीनगर के नगर एवं पूर्णियाँ पूर्व प्रखंड के वर्ष 2021 की बाढ़ से निम्नलिखित क्षतिग्रस्त पथों के Temporary Restoration कार्य के स्थल का निरीक्षण किया गया एवं इन कार्यों को प्राक्कलन के अनुरूप पाया गया। कार्य की वर्तमान स्थिति संतोषजनक है एवं पथ इस स्थल पर मोटेरेबल है।

Block - Kasba

Sl. No	Division	Road Name	Road Status	Length (In Km.)	Estimated Cost for Restoration (In Lakh)	Remarks
1	2	3	4	5	6	7
1	Purnea	Basantpur PMGSY Path To Harijan Tola Basantpur Dogachhi	Completed	1.878	7.490 4.609	RESTORATION WORK COMPLETED
2	Purnea	Repair of road from Kasba to Garua	Completed	12.600	1.174	RESTORATION WORK COMPLETED
3	Purnea	Kapsulbari to Dhar Tola Damdama	Completed	2.000	16.730	RESTORATION WORK COMPLETED
4	Purnea	Jalkar PMGSY Path to Kharaiya	On Going	2.085	13.247	RESTORATION WORK COMPLETED
5	Purnea	Dhankhania Ghat Giyanganj PMGSY Road - Bathan Cock RCD Road	Completed	6.940	2.723	RESTORATION WORK COMPLETED

[Signature]
11/12/21

कनीय अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रशाखा, कसबा

[Signature]
08/12/21

सहायक अभियंता,
ग्रामीण कार्य विभाग,
कार्य अवर प्रमंडल, कसबा

[Signature]
08/12/21

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल पूर्णियाँ

[Signature]
08/12/21

कार्यपालक अभियंता,
ग्रामीण कार्य विभाग,
कार्य प्रमंडल कटिहार