

Estimate for Restoration work of Road from Bisfi Mandir to Koriyani Via Ramuniya for the year 2021-2022 in Bisfi Block

Length-4.881 KM

Sr NO.	Item of Work							
1	Labour for lying dry graded jhama khoa or Stone filter under Brick pitching in slope or apron including including light ramming etc. all complete as per approved design, specification and direction of E/I (Brick Bats)							
Ch	Nos	Length	Width	Height	Quantity	Unit	Rate	Amount
91	1	30.00	2.00	0.30	18.00			
	1	11.00	3.00	0.90	29.70			
175	1	10.00	3.00	0.20	6.00			
200	1	40.00	2.50	0.20	20.00			
415	1	19.00	3.75	0.90	64.13			
2250	1	15.00	2.75	0.45	18.56			
	1	7.00	3.00	0.30	6.30			
					162.69	Cum	1939.93	315602

Add 12% GST =Rs 37872
 Add 1% L/Cess =Rs 3156
 Add Signorage Fee(162.69x1032X10%) =Rs 16789
 Total =Rs 373420

Bhaskar
 20/11/21
 JE
 RWD
 Bisfi

Ankur
 20/11/21
 A E
 RWD
 Bisfi

27/11/21
 27/11/21
 EE
 RWD
 Benipatti

Damaged Length = 132 metre

Restored Qty = 162.69 m³.

Signature
 27/11/21
 EE


27/11/21
 JE

W. M.
 27/11/20/21

Signature

Name of Road:- Bisfi mandir to Koriyami
via Ramaniga

Post-facto T/s awarded for Rs. 373420.00
(Rs Three Lacs seventy three thousand ~~three~~
four hundred ~~four~~ twenty only.)
Reference Letter no. 233 dated 21/2/22
of EE Darbhanga-2


Superintending Engineer
RWD Works Circle, Darbhanga

Inspection Report for Flood Damaged Work in the year 2021-22

Date of Inspection :- 27-11-2021 Name of PIU :- RWD (W) Div. Darbhanga-2
To 05-12-2021 (Inspected)
Name of Block/PIU :- Bisfi (RWD (W) Div. Benipatti)
Name of Road :- "Bisfi Mandir To Koriyani via Ramuniya"

For Road

:-

1. Damage Location/ Chainage :- In between chainage - 91 to 2250 Metre.
2. Damage Length :- 132 Metre.
3. Nature of Damage :- Due to flood, so many pot patch develops, & also breaches occurred.

4. Details of Restoration Works :-

- i. Material being used in Restoration Works — Brick Bets.
- ii. Equipment's/ Tools being used in Restoration Works — Tractor, Roller,
- iii. Procedure taken up in Restoration Works — Section-wise restoration work initiated/completed
- iv. Restored Length — 132 Metre.

Remarks :- Work found Satisfactory. signed

Signature of E.E.

Signature of JE/AE

19/02/2022
AE
JE