


कार्यपालक अभियंता का कार्यालय
ग्रामीण कार्य विभाग, कार्य प्रमंडल, समस्तीपुर


प्रतिवेदन


योजना का नाम : Samastipur Block ke Ramkrishnampur REO
लंबाई : Sadak to Vishampur REO Sadak tak.
क्षतिग्रस्त लंबाई : 1.60 कि०मी०।
प्राक्कलित राशि : 0.20 कि०मी०
प्रखंड : 2.82 लाख।
: समस्तीपुर।

प्रस्तुत प्राक्कलन समस्तीपुर प्रखंड उपरोक्त पथ के तत्कालीन मरम्मत कार्य के लिए बनाया गया है। विगत दिनों अत्यधिक बाढ़ के पानी एवं अतिवृष्टि के कारण पथ के आर-पार कट जाने एवं गड्ढे हो जाने के कारण यातायात बाधित हो रहा था। आवागमन सुचारु रूप से करने के लिए ब्रीक्स बैट्स का प्रावधान इस प्राक्कलन में किया गया है। यह पथ पंचवर्षीय अनुरक्षण है।

प्राक्कलन वर्तमान अनुसूचित दर पर बनाया गया है जिसकी तकनीकी अनुमोदन एवं प्रशासनिक स्वीकृति अपेक्षित है।


30/10/2024
कनीय अभियंता
ग्रामीण कार्य विभाग
कार्य प्रशाखा, समस्तीपुर


30/10/2024
सहायक अभियंता
ग्रामीण कार्य विभाग
कार्य अवर प्रमंडल, समस्तीपुर


30.10.24
कार्यपालक अभियंता
ग्रामीण कार्य विभाग
कार्य प्रमंडल, समस्तीपुर

**Details measurement FDR Road for "Samastipur Block ke
Ramkishanpur REO sadak se Vishanpur REO sadak tak path Nirman."**

For year 2021-22

item.No.	Item of work	No	length	width	thickness	Qty
1	supplying & Filling Bricks Bat & compacting Manually by CI hammer Including all Complete Job					
		1	11.00	3.00	0.50	16.50
		1	15.00	3.00	0.50	22.50
		1	8.00	3.00	0.50	12.00
		1	4.50	3.00	0.30	4.05
		1	2.50	2.40	0.25	1.50
		1	1.00	1.00	0.23	0.23
		1	3.50	1.50	0.30	1.58
		1	3.50	3.00	0.60	6.30
		1	2.50	2.00	0.15	0.75
		1	2.50	2.00	0.40	2.00
		1	1.50	1.00	0.15	0.23
		1	2.00	2.00	0.25	1.00
		1	1.00	1.00	0.15	0.15
		1	3.00	2.50	0.30	2.25
		1	5.00	2.00	0.20	2.00
		1	2.50	2.50	0.30	1.88
		1	5.00	2.50	0.36	4.50
		1	1.00	1.00	0.25	0.25
		1	10.00	3.50	0.53	18.45
		1	6.00	4.00	0.60	14.40
		1	10.00	3.00	0.45	13.50
		1	3.50	4.00	0.40	5.60
		1				0.00
		1				0.00
					Total Qty	131.60 cum

2	Prov.laying spreading GSB....					
		0				0.00
		0				0.00
		0				0.00
					Total Qty	0.00 cum

Santa
30/10/21
JE

Shro
30/10/21
JE

Sh
30/10/21

**Details measurement FDR Road for "Samastipur Block ke
Ramkishanpur REO sadak se Vishanpur REO sadak tak path Nirman."**

For year 2021-22

item.No.	Item of work	Unit	rate	Qty	Amount
1	supplying & Filling Bricks Bat & compacting Manually by CI hammer Including all Complete Job				
		cum	1896.72	131.60	249598.9
2	Prov. Laying spreading GSB-II				
		cum	2122	0.00	0
				Total	249598.9

Sanjay
30/10/21
JE

Sanjay
30/10/2021
AE

GENERAL ABSTRACT OF COST

Block Samastipur
construction length of Road

District- Samastipur
1.6 KM

Name of Road :-

Samastipur Block ke Ramkishanpur REC
se Vishanpur REO sadak tak path Nirma
work

Sr.no	Item of work	Amount
A	Total cost of Construction	249599
	Add GST@12%	29952
	Add labour Cess@1%	2496
	Total Project Cost(A)	282047

Santosh
30/10/21
junior Engineer

30/10/21
Assistant Engineer

30/10/21
Executive E

Provisionary Technician
Sanctioned
for Rs 2,82,000/- say Two Lakh
Eighty Two Thousand only including C.P. at 0.1% C

24/12/21
T.A
24.12.2021