

Estimate for Restoration work of Road from Parwatta Link Road to Keshwa T02 PWD Main Path Road for the year 2021-2022 in Bisfi Block

Length-1.067 KM

Sr NO.	Item of Work							
1	Labour for lying dry graded jhama khoa or Stone filter under Brick pitching in slope or apron including including light ramming etc. all complete as per approved design, specification and direction of E/I (Brick Bats)							
Ch	Nos	Length	Width	Height	Quantity	Unit	Rate	Amount
0	1	6.00 ✓	2.50 3.00 ✓	0.30 0.20 ✓	6.30	3.6 ✓		
0.200 Km	1	22.00 ✓	3.00 ✓	0.30 0.10 ✓	19.80	9.9 ✓		
0.350 Km	1	8.00 ✓	4.25 1.20 ✓	0.60 0.40 ✓	20.40	3.84 ✓		
0.400 Km	1	17.00 ✓	4.25 3.50 ✓	1.20 1.00 ✓	86.70	59.5 ✓		
		53 Metre			133.20	Cum	1939.93	258398.68

149064.00

Add 12% GST

Add 1% L/Cess

Add Signorage Fee(133.20x1032x10%) =Rs

Total

76.84 m³=Rs

=Rs

=Rs

31007.84

2583.99

18746.24

305736.74

178882

14912

79302

1763732

[Signature]
JE

RWD

Bisfi

[Signature]
20/11/21

AE

RWD

Bisfi

[Signature]
27.11.21

RWD

Benipatti

Damaged Length = 53 Metre

Restored Qty = 76.84 m³

Verified and found correct

[Signature]
27/11/21

[Signature]
27/11/21

[Signature]
27/11/2021
A2/Birghwan

:- 27.11.2021
2021

Name of PIU :- RWD (W) Div. Darbhanga-2
(Inspected)

Name of Road :- Parwatta Lene Road to
Kaswa to 2 Pwd main Path road.

Post-facto T/S accorded for Rs 176373.00
(Rs one lac seventy five thousand three
hundred seventy three only.)

Reference Letter no. 233 dated 21/2/22

Superintending Engineer
RWD Works Circle, Darbhanga

Inspection Report for Flood Damaged Work in the year 2021-22

Date of Inspection :- 27.11.2021 Name of PIU :- RWD (W) Div. Darbhanga-2
to 05.12.2022 (Inspection).
Name of Block / PIU :- Bisfi (RWD (W) Div. Benipatti).
Name of Road :- Porwita Underroad to Keshwa Toz PWD main path.

For Road :-

1. Damage Location/ Chainage :- At ch. 0.200 km to 0.400 km.
2. Damage Length :- 53.00 Mtr.
3. Nature of Damage :- Due to flood, pot fetch develops.
4. Details of Restoration Works :-
 - i. Material being used in Restoration Works Broken Bits.
 - ii. Equipment's/ Tools being used in Restoration Works :- Tractor & Roller.
 - iii. Procedure taken up in Restoration Works :- Section wise work initiated & completed.
 - iv. Restored Length 53.00 Mtr.

Remarks :- Work found satisfactory.

Signature of JE/AE

W. M. M.
19/02/22
JE

Signature of E.E.

[Signature]
19/02/22