
RURAL WORKS DEPARTMENT





861741

GOVERNMENT OF BIHAR

NAME OF ROAD:-

RESTORATION OF ROAD FROM BHAGKOHALIYA TO MUSHALMAN TOLA

DIVISION:-

R.W.D, WORKS DIVISION, FORBESGANJ

CIRCLE:-

R.W.D, WORK CIRCLE, KISHANGANJ

BLOCK:-

FORBESGANJ

ESTIMATED COST

843189.00

प्रतिवेदन

प्रस्तुत प्रावकलन ग्रामीण कार्य विभाग, कार्य प्रमंडल, फार्रावसमंज अंतर्गत क्षार्मिक्तिल प्रखंड के पथ प्राक्तिक के अंतर्गत के अंतर्गल के अंतर्गल के जो विभागीय Online Monitoring System MIS पर अपलेड़ है के बाढ़ 2021 से क्षतिग्रस्त हो जाने के कारण यातायात लायक Motorable हेतु बनाया गया है। इस कार्य को कराने का निर्देश ग्रामीण कार्य विमाग, विहार सरकार के पत्रांक-मु030-4(मु0) विविध कार्य-23-60/2020-1937/पटना, दिनांक-07.07.2021 से प्राप्त है। इस पत्र के Real time geo-tagged Photograph को कार्य के दौरान अपलोड करते हुए (Motorable) कार्य कराना स्विधियत करने का निर्देश प्राप्त है।

उक्त निर्देश के आलोक में अिश्विद्धाः नदी / नदी उपघार एवं अतिवृष्टि से आए बाढ़ के कारण इस पथ के Road Way के क्षतिग्रस्त हो जाने से सुरक्षित आवागमन हेतु Motorable कार्य कराया गया है। नेपाल तराई से निकलने वाली इस नदी के तेज धार एवं अतिवृष्टि से इस पथ में कटाव की स्थिति बनी। Motorable कार्य में आवश्यकता अनुसार Bamboo Pilling/Pitching of E.C Bags filled with local sand/ Local Sand Filling/ Brick bats का इस्तेमाल किया गया है। Motorable कार्य कराकर यातायात बहाल कर दिया गया है। निर्देशानुसार कराये गये Geo-tagged Photograph real time के साथ MIS पर अपलोड है। MIS की छायाप्रति, अपलोडेड फोटोग्राफ की छायाप्रति दर विश्लेषण एवं विभागीय आदेशों की छायाप्रति प्राक्कलन में संलग्न की जा रही है। प्राक्कलन में प्रयुक्त दर अदधतन है।

प्राक्कलन की यथा शीध्र अनुमोदन अपेक्षित है ताकि अग्रेतर कार्रवाई की जा सके।

्रीकि रुश्लिथी कनीय अभियंता ग्रामीण कार्य विभाग कार्य प्रशाखा—

सहायक अभियंता ग्रामीण कार्य विभाग कार्य अवर प्रमंडल– कार्यपालक अभियंता ग्रामीण कार्य विभाग कार्य प्रमंडल,फारबिसगंज Inspection Report for Flood Damage Work

Name of PIUs

EE RWD forbattay

Name Of Block / Road

forbusquij

. For Road

Damage Location / Chainage

26, 109442, 87,276888

.Damage Length

39 412250M

Nature Of Damage

flood damage debn upsism

Details Of Restoration

) Material Being Used In Restoration

Local Sand; Echag, brickbat, Bombon pile

i) Equipment / Tools Being Used In Restoration Works

iii) Procedure Taken Up In Restoration Works

· Prestor, TCB, vollary fility madines.
· filling are cub Properly by dange and

iv) Restored Length

B. For Bridge

1.Damage Location / Chainage

2.Damage Length

3. Nature Of Damage

4. Details Of Restoration

i) Material Being Used In Restoration

ii) Equipment / Tools Being Used in Restoration Works

iii) Procedure Taken Up In Restoration Works

iv) Restored Length

50 m

::

Signature

(Name Of Inspector)

Signature of JE / AE / EE

Abstract of Cost

Name of Work: Estimate for Repairing/Restoration/Making Motorable Roads
Damaged during flood in JULY 2019 in ARARIA District

Name of Road:

RESTORATION OF ROAD FROM BHAGKOHALIYA TO MUSHALMAN TOLA

Block: FORBESGANJ

District: ARARIA

Divison: RWD, Works Division, FORBESGANJ

Circle: RWD, Work Circle, Kishanganj

il No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	544.67	627.77	341926.24
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	900.00	75.86	68272.74
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.				
-		Mtr.	300.00	40.06	12018.17
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.	in the second			
		Each	6621.56	37.35	247293.64
5	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				

	Cum	45.00	1851.91	9222
6 Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				83336.11
	mater	0.00		
TOTAL AMOUNT =	meter	0.00	5382.71	0.00
				752847.00
ADD 12.00 %GST=				90342.00
SAY TOTAL AMOUNT =				843189.00

JE WD WORKS DIV.

ORBESGANJ

(ME OF)

RWD WORKS DIV. FORBESGANJ

C. 28/10

RWD WORKS DIV. FORBESGANJ

Ref. E.E. Letter No. 1561 (20180) Dt 28 4 22

Technically Sanctioned in 8, 42, 189 200...

(Rupees.... Eight Lac Footy free fronting

one hundred eighty nine)Only

20 Tales

Ply Engineer

The Remains Department

The Right Works Circle, Kishangani

The Right Works Circle, Circle, Kishangani

The Right Works Circle, Circ

Abstract of Cost

Name of Work: Estimate for Repairing/Restoration/Making Motorable Roads
Damaged during flood in JULY 2019 in ARARIA District

Name of Road:

RESTORATION OF ROAD FROM BHAGKOHALIYA TO MUSHALMAN TOLA

Block: FORBESGANJ

District: ARARIA

Divison: RWD, Works Division, FORBESGANJ

Circle: RWD, Work Circle, Kishanganj

No.	Description	Unit	Quantity (m3)	Rate (Rs)	Amount (Rs)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.				
		Cum	544.67	627.77	341926.24
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.				
		Mtr.	900.00	75.86	68272.74
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.	3 0			
		Mtr.	300.00	40.06	12018.17
4	Supplying of EC bag, filling of local sand, stitching and placing in position as per the direction of Engineer-in-charge.				
ا الموالية الما الما		Each	6621.56	37.35	247293.64
5	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats, all complete job.				
	1994	Cum	45.00	1851.91	83336.11
6	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.				
		meter	0.00	5382.71	0.00
-		Total An	752846.91		

RWD WORKS DIV.

FORBESGANJ

RWD WORKS DIV. FORBESGANJ

Ce 8/10

RWD WORKS DIV. FORBESGANJ

RESTORATION OF ROAD FROM BHAGKOHALIYA TO MUSHALMAN TOLA

SI No.	. Items of Works	Nos.	L (m)	B (m)	(m) IN (Av.)	Quantity (m3)
1	Filling of local sand obtained from river bed, watering & ramming, all complete job as per specification & direction of Engineer-in-charge.					
	specific	_	42.00	(* n. i n) (n	(25.25.25)/2	161.50
		1	12.00	(5.0+4.5)/2	(2.5+3,5+2.5)/3	
		1	38.00	(6.0+5.0)/2	(1.5+2.5+1.5)/3	383.17
		1	0.00	0.00	0.00	0.00
					TOTAL=	544.67
			-	See Age of the See	Total Qty =	544.67
2	Labour for cutting 62mm to 75mm dia bamboo piles to size and making shoes & driving by jet machine etc. all complete job as per specification & direction of Engineer-in-Charge.					
	specimental an outer of angular	2	50.00	3.00	3.00	900.00
		0	0.00	0.00	0.00	0.00
. 17	**	0	0.00	0.00	0.00	0.00
					Total Qty =	900.00
3	Labour for fitting & fixing 62mm to 75mm dia bamboo runners in position at every vertical pile with 150 mm long nails or 38 swg G.I wire including cost of G.I wire or nails etc all complete job as per specification & direction of Engineer-in-Charge.					
7	Engineer-in-charge.	2	50.00	3.00		300.00
		0	0.00	0.00		0.00
		0	0.00	0.00		0.00
				The second second	Total Qty =	300.00
2	Supplying of EC bag, filling of local sand, stitching and placing in position as per the					1 62
	direction of Engineer-in-charge.	2	50.00	(0.6+0.9)/2	(2.0+3.0+2.5)/3	187.50
		2	0.00	(1.6+1.5)/2	(1.5+2.5+1.5)/3	0.00
		0	0.00	0.00	0.00	0.00
		0	0.00	0.00	0.00	0.00
		Fred			TOTAL=	187.50
			Total No	o. of EC Bags	=304.83X35.315	6621.56
-		Cur.		SA	AY NO OF BAGE	= 6622
3	Supply and Carriage of brick bats upto 8 km breach and placing in breaches and lying of bats all complete job.	,				
	an complete job.	1	50.00	4.50	0.20	45.00
		2	0.00	0.90	0.15	0.00
		1	0.00	0.00	0.30	0.00
					Total Qty.	= 45.00
4	Supply, laying and Carriage of of hume pipe 1000 mm dia (HPC), all complete job.			Mariantonia		
		1	0.00	2.50		0.00
		A DOT	To Att		Total Qty	. = 0.00

RWD WORKS DIV.

RWD WORKS DIV. FORBESGANJ

ENENC

RWD WORKS DIV. FORBESGANJ

MIN की हिल्ला देन प्रसल्मात टीला





Ma 24/0/21

(MILION)

अग्रिकाहाक्या (र प्रस्थाम द्रास्य





26/10/21 (76/09)

MIDIONE IN III ELEND SIM





(m25)1921

Millon Elant et Efecto Diane





(m25)1974