



ग्रामीण कार्य विभाग

Rural Works Department, Govt of Bihar

YEAR-2020-21

DETAILED PROJECT REPORT

TEMPORARY RESTORATION WORK

DISTRICT :-

DARBHANGA

BLOCK :-

~~Hanumannagar~~ Bahadurpur

ROAD NAME :

NH 57 SE BANDBASTI

HEAD

FDR

YEAR-2021-22

TOTAL LENGTH OF ROAD

:

2.793

KM

DAMAGE LENGTH

:

0.065

KM

TOTAL COST OF PROJECT

:

0.402

LAKH

6.420

Executive Engineer
RWD Darbhanga-1

Inspection Report of Flood Damage work

Name of PIUs:- RWD Works Division, Darbhanga Inspected by Benipur
Name of Block/Road:- NH 57 Se Bandhikashi

A. For Road

1. Damage Location Chainage:- 0 to 200m & 500 to 800m

2. Damage Length :- 64.5m

3. Nature of Damage :- Road Surface Damage

4. Details of Restoration Works

i. Material being used in Restoration works:- Brick Bats

ii. Equipment's /Tools being used in Restoration works:- JCB/Tractor/Labour

iii. Procedure taken up in Restoration works:- Laying of Brick Bats with

iv. Restored Length:- 64.5m with Ramming.

B. For Bridge

1. Damage Location Chainage:-

2. Damage Length :-

3. Nature of Damage :-

4. Details of Restoration Works

i. Material being used in Restoration works:-

ii. Equipment's /Tools being used in Restoration works:-

iii. Procedure taken up in Restoration works:-

iv. Restored Length:-

N/A

Work found Satisfactory.

Signature of JE/AE/EE

28/3/22

Signature

(Name of Inspection)

E.E Benipur

GENERAL ABTRACT OF COST		
NAME OF ROAD :		NH 57 SE BANDBASTI
DISTRICT		DARBHANGA
BLOCK		HANUMANNAGAR
LENGTH OF ROAD (in Km)		2.793
DAMAGED LENGTH (KM)		0.0645
Sl. No.	DESCRIPTION	AMOUNT
1	Cost of Restoration	35567.990
2	GST @12%	4268.159
3	Labour cess @1%	355.680
4	Seigniorage fee	1830.77 -8.986
5	Grand Total	42022.640200.815
6	Say(lacs)	0.420 -0.402

Scy 42023=0

6/11/21
JE
RWD

6/11/21
AE
RWD

6/11/21
EE
RWD

कार्यालय अभियंता जेनोपुर के लॉच तारिखों के बावजूद
Technicality ~~is not~~ sanctioned
Scy 42,023 (Rs. Forty ^{Two} thousand twenty three only)

26/11/21
अधिक्षण अभियंता
कार्य अंचल, दरभंगा
Abhinav
26/02/22

Detail Estimate For Motorable work of Road

Detail Estimate For Motorable work of Road									
	Name of road	Block			District		Division		Length(KM)
	NH 57 SE BANDBASTI	HANUMANNAGAR			DARBHANGA		DARBHANGA-I		2.793
Sl. No.	Description	Unit	Nos	LENGTH	Avg. width	Avg Hight	Qty	RATE	AMOUNT (in Rs.)
1	Labour and Placing Brick bats with Light raming including cost of brick bats by tractor	cum	1.00	11.00	1.50	0.15	2.48		
			1.00	14.00	3.20	0.25	11.20		
			1.00	24.50	1.00	0.12	2.94		
			1.00	15.00	0.50	0.15	1.13		
	Total						17.74	2,004.96	35,567.99
	DAMAGE LENGTH(M)			0.06					

[Signature]
JE
RWD

[Signature]
AE
RWD

[Signature]
EE
RWD

Verified & found correct

[Signature]
15-12-21
JE

[Signature]
15/12/21
AE

[Signature]
EE
Benipur